

CITY OF NEWTON
PURCHASING DEPARTMENT

CONTRACT FOR PUBLIC WORKS DEPARTMENT
(M.G.L. Ch. 30, Sec. 39M)

PROJECT MANUAL:
COLD-PLANING OF BITUMINOUS CONCRETE PAVEMENT
AT VARIOUS LOCATIONS
INVITATION FOR BID #14-86

Bid Opening Date: March 6, 2014 at 10:00 a.m.

FEBRUARY 2014
Setti D. Warren, Mayor

CITY OF NEWTON, MASSACHUSETTS

PURCHASING DEPARTMENT

INVITATION FOR BID #14-86

The City of Newton invites sealed bids from Contractors for:

COLD-PLANING OF BITUMINOUS CONCRETE PAVEMENT AT VARIOUS LOCATIONS

(See street listing @ Item Sheet /Page 1 & 2 and Special Information on Item Sheet 3)

Bids will be received until:

10:00 a.m., Thursday, March 6, 2014

at the Purchasing Department, Room 204, Newton City Hall, 1000 Commonwealth Avenue, Newton, MA 02459. Bids will not be accepted nor may submitted bids be corrected, modified or withdrawn after the deadline for bids. Immediately following the deadline for bids, all bids received within the time specified will be publicly opened and read aloud.

The work under this contract is for the removal and immediate off-site disposal of 1-1/2" to 2" of bituminous concrete by cold-planing methods. The work shall be performed at multiple municipal roadway locations situated throughout the City of Newton yielding a collective total surface area of approximately seventy seven thousand (77,000) square yards [*].

*** Notice #1:** The quantities represented in this Invitation For Bid are dependent on Mass D.O.T. Chapter 90 funding. These monies are traditionally allotted, and subsequently apportioned by the City of Newton, on or about April 1 of each calendar year. Therefore the quantities listed in this Invitation For Bid may be revised at the time of the bid award.

*** Notice #2:** The work under this contract is to be performed in conjunction with a separately issued paving contract and an in-house DPW site preparation program, therefore the scheduling of this work shall be at the discretion of the City Engineer. The intent is to ensure that the work under this contract is performed immediately before the aforementioned paving process. The successful bidder must be ready, willing and able to accommodate the City of Newton in the scheduling and/or coordination of this work.

Contract Documents will be available online at www.newtonma.gov/bids or pick up at the Purchasing Department after **10:00 a.m., February 20, 2014**. **Bids must be submitted with one Original and one Copy.**

Only paving contractors that have been prequalified by the Massachusetts Department of Transportation (Mass DOT) are eligible to bid on this contract. MassDOT will provide a list of Prequalified Construction Contractors to the City of Newton. Bidders will be verified at time of Bid Opening.

A bid deposit in an amount that is not less than five percent (5%) of the value of the bid, including all add alternates, is required. Bid deposits, payable to the City of Newton, shall be either in the form of a bid bond, or cash, or a certified check on, or a treasurer's or cashier's check issued by, a responsible bank or trust company. Bidders are reminded that the bid deposit covers the City for damages when a bidder withdraws its bid after the bid submission date. **Be advised that to the extent permitted by the law the City will retain all bid deposits for withdrawn bids.**

The City of Newton will award the contract to the lowest eligible and responsible bidder. Please Note: this bid, in accordance with the Chapter 303 Acts of 2008, contains Price Adjustments and new Prevailing Wage requirements. All bidders are required to familiarize themselves with these terms and conditions before submitting a bid.

Anticipated start date is April 1, 2014. Time for completion is one hundred sixty (160) calendar days from the Notice To Proceed. This work is to be performed in conjunction with a separately issued Bituminous Concrete Overlay program.

All bids are subject to the provisions of M.G.L. c.30, §39M. **Wages are subject** to minimum wage rates determined by the Massachusetts Department of Labor and Industries pursuant to M.G.L. c.149, §26 to 27H. The schedule of wage rates applicable to this contract is included in the bidding documents. In addition, the prevailing wage schedule will be updated annually for all public construction projects lasting longer than one (1) year. You will be required to pay the rates set out in any updated prevailing wage schedule. Increases in prevailing wage schedules will not be the basis for change order requests. The successful bidder will be required to provide a Certificate of Insurance demonstrating current coverage of the type and amounts set forth in the Project

Manual. The successful bidder will be required to furnish a **Labor and Materials Payment Bond in the amount of 50%** of the contract total. Wages are paid to drivers for all “**on-site**” work.

Once you’ve downloaded this bid from the internet website (www.newtonma.gov/bids) I strongly suggest you email (purchasing@newtonma.gov) your company’s Name, address, EMAIL, phone, fax AND the INVITATION FOR BID NUMBER and Project Title, so that we may add you to the Bidders List and you will be notified of any/all addendums.

The City will reject any and all bids in accordance with the above referenced General Laws. In addition, the City reserves the right to waive any informalities in any or all bids, or to reject any or all bids (in whole or in part) if it be in the public interest to do so.

CITY OF NEWTON

Nicholas Read
Chief Procurement Officer

February 20, 2014

CITY OF NEWTON
DEPARTMENT OF PURCHASING
INSTRUCTIONS TO BIDDERS

ARTICLE 1 - BIDDER'S REPRESENTATION

- 1.1 Each General Bidder (hereinafter called the "Bidder") by making a bid (hereinafter called "bid") represents that:
1. The Bidder has read and understands the Bidding Documents, Contract Forms, General Conditions, Conditions of the Contract, General Requirements and Project Specification (collectively, referred to as the "Contract Documents") and the bid is made in accordance therewith.
 2. The Bidder has visited the work site and is familiar with the local conditions under which the work has to be performed.
- 1.2 Failure to so examine the Contract Documents and work site will not relieve any Bidder from any obligation under the bid as submitted.

ARTICLE 2 - REQUEST FOR INTERPRETATION

- 2.1 Bidders shall promptly notify the City of any ambiguity, inconsistency, or error which they may discover upon examination of the Contract Documents, the site, and local conditions.
- 2.2 Bidders requiring clarification or interpretation of the Contract Documents shall make a written request to the *Chief Procurement Officer*, at purchasing@newtonma.gov or via facsimile (617) 796-1227. The City will answer such requests if received by **Friday, February 28, 2014** at 12:00 noon.
- 2.3 Interpretation, correction, or change in the Contract Documents will be made by Addendum which will become part of the Contract Documents. The City will not be held accountable for any oral instruction.
- 2.4 Addenda will be emailed to every individual or firm on record as having taken a set of Contract Documents.
- 2.5 Copies of addenda will be made available for inspection at the location listed in the Invitation for Bids where Contract Documents are on file, in addition to being available online at www.newtonma.gov/bids.
- 2.6 Bidders or proposers contacting ANY CITY EMPLOYEE regarding an Invitation for Bid (IFB) or a Request for Proposal (RFP), outside of the Purchasing Department, once an IFB or RFP has been released, may be disqualified from the bidding process.
- 2.7 Bidders downloading information off the internet web site are solely responsible for obtaining any addenda prior to the bid opening. If the bidder makes themselves known to the Purchasing Department, at purchasing@newtonma.gov or via facsimile (617) 796-1227, they shall be placed on the bidder's list. Bidders must provide the Purchasing Department with their company's name, street address, city, state, zip, phone, fax, email address and **INVITATION FOR BID #14-86**.

ARTICLE 3 - MBE PARTICIPATION

- 3.1 Notice is hereby given that the Mayor's Affirmative Action Plan for the City of Newton in effect at the time of this solicitation is applicable to all construction contracts in excess of \$10,000.00.
- 3.2 Notice is hereby given that the City of Newton Minority/Women Business Enterprise Plan and the Supplemental Equal Employment Opportunity Anti-Discrimination and Affirmative Action Program in effect at the time of this solicitation are applicable to all City contracts for goods and services in excess of \$50,000.00.
- 3.3 Copies of the Plans and Program referred to in Sections 3.1 and 3.2 are available at: www.newtonma.gov/purchasing.

ARTICLE 4 - PREPARATION AND SUBMISSION OF BIDS

- 4.1 Bids shall be submitted on the "Bid Form" as appropriate, furnished by the City.
- 4.2 All entries on the Bid Form shall be made by typewriter or in ink.
- 4.3 Where so indicated on the Bid Form, sums shall be expressed in both words and figures. Where there is a discrepancy between the bid sum expressed in words and the bid sum expressed in figures, the words shall control.
- 4.4 Bid Deposits shall be submitted in the amount specified in the Invitation for Bids. They shall be made payable to the City and shall be either in the form of cash, certified check, treasurer's or cashier's check issued by a responsible bank or trust company, or a bid bond issued by a surety licensed to do business in the Commonwealth of Massachusetts; and shall be conditioned upon the faithful performance by the principal of the agreements contained in the bid. Bidders are reminded that the bid deposit covers the City for damages when a bidder withdraws its bid after the bid submission date. **Bid advised that to the extent permitted by law the City will retain all bid deposits for withdrawn bids.**

Bid deposits of the three (3) lowest responsible and eligible Bidders shall be retained until the execution and delivery of the City/Contractor agreement.

- 4.5 The Bid, including the bid deposit shall be enclosed in a sealed envelope with the following plainly marked on the outside:

- * GENERAL BID FOR: **#14-86**
- * NAME OF PROJECT: **Cold-Planing of Bituminous Concrete Pavement**
- * BIDDER'S NAME, BUSINESS ADDRESS, AND PHONE NUMBER

- 4.6 Date and time for receipt of bids is set forth in the Invitation for Bids.
- 4.7 Timely delivery of a bid at the location designated shall be the full responsibility of the Bidder. In the event that Newton City Hall is closed on the date or at the time that bids are due, the date and time for receipt of bids shall be on the next business day following that the Newton City Hall and the Purchasing Department are open.
- 4.8 Bids shall be submitted with one original and one copy. Be advised that a new Massachusetts law has been enacted that required all employees who work on Massachusetts public works construction sites must have no less than 10 hours of OSHA-approved safety and health training. See Chapter 306 of the Acts of 2004, which will become effective July 1, 2006.
1. This requirement will apply to any general bid or sub bid submitted on or after July 1, 2006 and to any contract awarded on or after July 1, 2006.
 2. This law directs the Massachusetts Attorney General to restrain the award of construction contracts to any contractor who is in violation to this requirement and to restrain the performance of these contracts by non-complying contractors.
 3. The contractor and all subcontractors on this project will be required to provide certification of compliance with this requirement. Non-compliance with this new Massachusetts Law will disqualify you from bidding on public contracts.

4.9 PRICE ADJUSTMENT CLAUSES CHAPTER 90 FUNDS

It is the intention of the City to include price adjustments in the award of this Contract. These price adjustments shall be for Fuel when such commodities have been determined to be integral components of the work.

For those commodities designated to be paid as a 'differential' items then the special provision shall provide for a price adjustment formula for the affected items. This adjustment shall be based on the difference between the **Base Price** and the **Period Price** which shall be evaluated on a **monthly** basis, but price adjustments shall only be made if the monthly cost change exceeds **+/- 5 per cent**. Subsequently each respective price adjustment shall be made as specified under each applicable and separate payment item.

IMPORTANT NOTE: Depending on the prevailing market trends at the time of payment these price adjustments may provide for additional compensation to the Contractor, or they may otherwise result in a repayment to the City. The increase or a decrease in the value of the commodity, during the applicable payment period in which the goods and/or services were rendered, shall be the determinant factor.

The City will refer to MassDOT price adjustment tables as included in this bid package to establish the base price and will be used for the actual period price.

Price Adjustment Clauses – to apply as follows:

- **Diesel and Gasoline** – The Base Price, and the Period Price of fuel, shall be the derived average cost of Diesel Fuel and Gasoline Fuel combined for each applicable payment period. Fuel adjustments shall apply to all work in the contract. The Contractor, at its own election, may either choose to bid fuel costs separately, or it may otherwise elect to incorporate fuel costs into separate payment items. In any event the Contractor's final bid prices shall include the fuel costs for all goods and services rendered under this contract.

No price adjustment will be allowed beyond the completion date of the contract unless there is an approved extension of time by the City.

ARTICLE 5 - ALTERNATES

- 5.1 Each Bidder shall acknowledge Alternates (if any) in Section C on the Bid Form.
- 5.2 In the event an Alternate does not involve a change in the amount of the base bid, the Bidder shall so indicated by writing "No Change", or "N/C" or "0" in the space provided for that Alternate.
- 5.3 Bidders shall enter on the Bid Form a single amount for each Alternate which shall consist of the amount for work performed by the Contractor.
- 5.4 The low Bidder will be determined on the basis of the sum of the base bid and the accepted alternates.

ARTICLE 6 - WITHDRAWAL OF BIDS

- 6.1 Any bid may be withdrawn prior to the time designated for receipt of bids on written or electronic request. Electronic withdrawal of bids must be confirmed over the Bidder's signature by written notice postmarked on or before the date and time set for receipt of bids.
- 6.2 Withdrawn bids may be resubmitted up to the time designated for the receipt of bids.
- 6.3 No bids shall be withdrawn within thirty days, Saturdays, Sundays and legal holidays excluded, after the opening of the bids.

ARTICLE 7 - CONTRACT AWARD

- 7.1 The City is soliciting prices for the items set forth in the Building and Related Supplies Annual Bid Item Sheets attached hereto. It is the City's intent to award separate contracts for each item to the lowest, responsive and responsible bidder for such item. Accordingly, the City may award one (1) contract, or as many contracts as there are bidders. Contracts will be awarded within sixty (60) days, Saturdays, Sundays, and legal holidays excluded, after the opening of bids.
- 7.2 The City of Newton reserves the right to waive minor informalities in or to reject any or all Bids if it be in the public interest to do so.
- 7.3 The City reserves the right to reject any bidder who has failed to pay any local taxes, fees, assessments, betterments, or any other municipal charge, unless the bidder has a pending abatement application or has entered into a payment agreement with the collector-treasurer.
- 7.4 As used herein, the term "lowest responsible and eligible Bidder" shall mean the Bidder (1) whose bid is the lowest of those bidders possessing the skill, ability and integrity necessary for the faithful performance of the work; (2) who has met all the requirements of the invitation for bids; (3) who shall certify that he is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed in the work; (4) who, where the provisions of section eight B of chapter twenty-nine apply, shall have been determined to be qualified thereunder.
- 7.5 Subsequent to the award and within five (5) days, Saturday, Sundays and legal holidays excluded, after the prescribed forms are presented for signature, the successful Bidder shall execute and deliver to the City a Contract in the form

included in the Contract Documents in such number of counterparts as the City may require.

- 7.6 In the event that the City receives low bids in identical amount from two or more responsive and responsible Bidders, the City shall select the successful Bidder by a blind selection process chosen by the City such as flipping a coin or drawing names from a hat. The low Bidders who are under consideration will be invited to attend and observe the selection process.

ARTICLE 8 - TAXES

- 8.1 The Bidder shall not include in this bid any tax imposed upon the sale or rental of tangible personal property in this Commonwealth, such as any and all building materials, supplies, services and equipment required to complete the work.
- 8.2 The City is exempt from payment of the Massachusetts Sales Tax, and the Bidder shall not include any sales tax on its bid. The City's exemption Number is E-046-001-404.

ARTICLE 9 – PROPRIETARY SPECIFICATIONS

- 9.1 The City has used a proprietary specification to describe the supply for which is soliciting bids. Such specifications are permitted under M.G.L. c. 30B, §14, provided that the Chief Procurement Officer has prepared a written statement that no other manner of description suffices and the justification therefor.
- 9.2 The required determination and justification have been duly prepared, and a copy may be requested in accordance with the Massachusetts Public Records Law, M.G.L. c. 66, §10.

END OF SECTION

CITY OF NEWTON
DEPARTMENT OF PURCHASING
BID FORM ##14-86

- A. The undersigned proposes to supply and deliver the materials specified below in full accordance with the Contract Documents and Project Manual supplied by the City of Newton entitled:

COLD-PLANING OF BITUMINOUS CONCRETE PAVEMENT AT VARIOUS LOCATIONS
(See street listing @ Item Sheet /Page 1 & 2 and Special Information on Item Sheet 3)

for the contract price specified below, subject to additions and deduction according to the terms of the specifications.

- B. This bid includes addenda number(s) _____, _____, _____, _____,
- C. The Contractor shall insert prices for each item in ink, in both words and figures.

_____ Dollars and \$_____

(Contract price shall equal the Total Bid Price of the attached Item Sheets at pp. 81-85 below)

COMPANY NAME: _____

- D. The undersigned has completed and submits herewith the following documents:

- ☐ Bidder's Qualifications and References Form, 2 pages
- ☐ Signed Bid Form, 2 pages
- ☐ Item Sheets, 8 pages
- ☐ Certificate of Non-Collusion, 1 page
- ☐ Debarment Letter, 1 page
- ☐ IRS Form W-9, 1 page
- ☐ A five percent (5%) bid deposit

- E. Prompt Payment Discounts. Bidders are encouraged to offer discounts in exchange for an expedited payment. Payments may be issued earlier than the general goal of within 30 days of receipt of the invoice only when in exchange for discounted prices. Discounts will not be considered in determining the lowest responsible bidder.

Prompt Payment Discount _____ % _____ Days
Prompt Payment Discount _____ % _____ Days
Prompt Payment Discount _____ % _____ Days

- F. The undersigned agrees that, if selected as general contractor, s/he will within five days, Saturdays, Sundays and legal holidays excluded, after presentation thereof by the City of Newton, execute a contract in accordance with the terms of this bid **and furnish a labor and materials payment bond** of a surety company qualified to do business under the laws

of the commonwealth and satisfactory to the City of Newton in the **sum not less than 50% of the contract price**, the premiums for which are to be paid by the contractor and are included in the contract price.

The undersigned hereby certifies that s/he is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed on the work and that s/he will comply fully with all laws and regulations applicable to awards made subject to section forty-four A of M.G.L. c.30, §39M.

The undersigned certifies that he is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed in the work; (2) that all employees to be employed at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration ("OSHA") that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee; and (3) that all employees to be employed in the work subject to this bid have successfully completed a course in construction safety and health approved by the United States OSHA that is at least 10 hours in duration. The undersigned understands that any employee found on a worksite subject to this section without documentation of successful completion of a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration shall be subject to immediate removal.

The undersigned further certifies under the penalties of perjury that this bid is in all respects bona fide, fair and made without collusion or fraud with any other person. As used in this subsection the word "person" shall mean any natural person, joint venture, partnership, corporation or other business or legal entity. The undersigned further certifies under penalty of perjury that the said undersigned is not presently debarred from doing public construction work in the Commonwealth under the provisions of section twenty-nine F of chapter twenty-nine, or any other applicable debarment provisions of any other chapter of the General Laws or any rule or regulation promulgated thereunder.

The undersigned further certifies under the penalties of perjury that they have familiarized themselves with the changes to the Prevailing Wage Rates, Price Adjustment Clauses, in accordance to Chapter 303 Acts of 2008.

Date _____

(Name of General Bidder)

BY: _____

(Printed Name and Title of Signatory)

(Business Address)

(City, State Zip)

(Telephone) / (FAX)

(E-mail address)

NOTE: If the bidder is a corporation, indicate state of incorporation under signature, and affix corporate seal; if a partnership, give full names and residential addresses of all partners; if an individual, give residential address if different from business address; and, if operating as a d/b/a give full legal identity. Attach additional pages as necessary.

END OF SECTION

CITY OF NEWTON

BIDDER'S QUALIFICATIONS AND REFERENCES FORM

All questions must be answered, and the data given must be clear and comprehensive. Please type or print legibly. If necessary, add additional sheet for starred items. This information will be utilized by the City of Newton for purposes of determining bidder responsiveness and responsibility with regard to the requirements and specifications of the Contract.

1. FIRM NAME: _____
2. WHEN ORGANIZED: _____
3. INCORPORATED? ____ YES ____ NO DATE AND STATE OF INCORPORATION: _____
4. IS YOUR BUSINESS A **MBE**? ____ YES ____ NO **WBE**? ____ YES ____ NO or **MWBE**? ____ YES ____ NO
- * 5. LIST ALL CONTRACTS CURRENTLY ON HAND, SHOWING CONTRACT AMOUNT AND ANTICIPATED DATE OF COMPLETION:

- * 6. HAVE YOU EVER FAILED TO COMPLETE A CONTRACT AWARDED TO YOU?
____ YES ____ NO
IF YES, WHERE AND WHY?

- * 7. HAVE YOU EVER DEFAULTED ON A CONTRACT? ____ YES ____ NO
IF YES, PROVIDE DETAILS.

- * 8. LIST YOUR VEHICLES/EQUIPMENT AVAILABLE FOR THIS CONTRACT:

- * 9. IN THE SPACES FOLLOWING, PROVIDE INFORMATION REGARDING CONTRACTS COMPLETED BY YOUR FIRM SIMILAR IN NATURE TO THE PROJECT BEING BID. A MINIMUM OF FOUR (4) CONTRACTS SHALL BE LISTED. PUBLICLY BID CONTRACTS ARE PREFERRED, BUT NOT MANDATORY.

PROJECT NAME: _____
OWNER: _____
CITY/STATE: _____

DOLLAR AMOUNT: \$ _____ DATE COMPLETED: _____
PUBLICLY BID? _____ YES _____ NO
TYPE OF WORK?: _____
CONTACT PERSON: _____ TELEPHONE #: (____) _____
CONTACT PERSON'S RELATION TO PROJECT?: _____
(i.e., contract manager, purchasing agent, etc.)

PROJECT NAME: _____
OWNER: _____
CITY/STATE: _____
DOLLAR AMOUNT: \$ _____ DATE COMPLETED: _____
PUBLICLY BID? _____ YES _____ NO
TYPE OF WORK?: _____
CONTACT PERSON: _____ TELEPHONE #: (____) _____
CONTACT PERSON'S RELATION TO PROJECT?: _____
(i.e., contract manager, purchasing agent, etc.)

PROJECT NAME: _____
OWNER: _____
CITY/STATE: _____
DOLLAR AMOUNT: \$ _____ DATE COMPLETED: _____
PUBLICLY BID? _____ YES _____ NO
TYPE OF WORK?: _____
CONTACT PERSON: _____ TELEPHONE #: (____) _____
CONTACT PERSON'S RELATION TO PROJECT?: _____
(i.e., contract manager, purchasing agent, etc.)

PROJECT NAME: _____
OWNER: _____
CITY/STATE: _____
DOLLAR AMOUNT: \$ _____ DATE COMPLETED: _____
PUBLICLY BID? _____ YES _____ NO
TYPE OF WORK?: _____
CONTACT PERSON: _____ TELEPHONE #: (____) _____
CONTACT PERSON'S RELATION TO PROJECT?: _____
(i.e., contract manager, purchasing agent, etc.)

10. The undersigned certifies that the information contained herein is complete and accurate and hereby authorizes and requests any person, firm, or corporation to furnish any information requested by the City of Newton in verification of the recitals comprising this statement of Bidder's qualifications and experience.

DATE: _____ BIDDER: _____

SIGNATURE: _____

PRINTED NAME: _____ TITLE: _____

END OF SECTION

CERTIFICATE OF NON-COLLUSION

The undersigned certifies under penalties of perjury that this bid or proposal has been made and submitted in good faith and submitted in good faith and without collusion or fraud with any other person. As used in this certification, the word “person” shall mean any natural person, business, partnership, corporation, union, committee club, or other organization, entity, or group or individuals.

(Signature of individual)

Name of Business

**Request for Taxpayer
Identification Number and Certification**

**Give form to the
requester. Do not
send to the IRS.**

Print or type See Specific instructions on page 2.	Name (as shown on your income tax return)	
	Business name, if different from above	
	Check appropriate box: <input type="checkbox"/> Individual/Sole proprietor <input type="checkbox"/> Corporation <input type="checkbox"/> Partnership <input type="checkbox"/> Limited liability company. Enter the tax classification (D=disregarded entity, C=corporation, P=partnership) ▶ <input checked="" type="checkbox"/> Exempt payee <input type="checkbox"/> Other (see instructions) ▶	
	Address (number, street, and apt. or suite no.)	Requester's name and address (optional)
	City, state, and ZIP code	
List account number(s) here (optional)		

Part I Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. The TIN provided must match the name given on Line 1 to avoid backup withholding. For individuals, this is your social security number (SSN). However, for a resident alien, sole proprietor, or disregarded entity, see the Part I instructions on page 3. For other entities, it is your employer identification number (EIN). If you do not have a number, see *How to get a TIN* on page 3.

Note. If the account is in more than one name, see the chart on page 4 for guidelines on whose number to enter.

Social security number
or
Employer identification number

Part II Certification

Under penalties of perjury, I certify that:

- The number shown on this form is my correct taxpayer identification number (or I am waiting for a number to be issued to me), and
- I am not subject to backup withholding because: (a) I am exempt from backup withholding, or (b) I have not been notified by the Internal Revenue Service (IRS) that I am subject to backup withholding as a result of a failure to report all interest or dividends, or (c) the IRS has notified me that I am no longer subject to backup withholding, and
- I am a U.S. citizen or other U.S. person (defined below).

Certification instructions. You must cross out item 2 above if you have been notified by the IRS that you are currently subject to backup withholding because you have failed to report all interest and dividends on your tax return. For real estate transactions, item 2 does not apply. For mortgage interest paid, acquisition or abandonment of secured property, cancellation of debt, contributions to an individual retirement arrangement (IRA), and generally, payments other than interest and dividends, you are not required to sign the Certification, but you must provide your correct TIN. See the instructions on page 4.

Sign Here	Signature of U.S. person ▶	Date ▶	Name
------------------	----------------------------	--------	------

General Instructions

Section references are to the Internal Revenue Code unless otherwise noted.

Purpose of Form

A person who is required to file an information return with the IRS must obtain your correct taxpayer identification number (TIN) to report, for example, income paid to you, real estate transactions, mortgage interest you paid, acquisition or abandonment of secured property, cancellation of debt, or contributions you made to an IRA.

Use Form W-9 only if you are a U.S. person (including a resident alien), to provide your correct TIN to the person requesting it (the requester) and, when applicable, to:

- Certify that the TIN you are giving is correct (or you are waiting for a number to be issued),
- Certify that you are not subject to backup withholding, or
- Claim exemption from backup withholding if you are a U.S. exempt payee. If applicable, you are also certifying that as a U.S. person, your allocable share of any partnership income from a U.S. trade or business is not subject to the withholding tax on foreign partners' share of effectively connected income.

Note. If a requester gives you a form other than Form W-9 to request your TIN, you must use the requester's form if it is substantially similar to this Form W-9.

Definition of a U.S. person. For federal tax purposes, you are considered a U.S. person if you are:

- An individual who is a U.S. citizen or U.S. resident alien,
- A partnership, corporation, company, or association created or organized in the United States or under the laws of the United States,
- An estate (other than a foreign estate), or
- A domestic trust (as defined in Regulations section 301.7701-7).

Special rules for partnerships. Partnerships that conduct a trade or business in the United States are generally required to pay a withholding tax on any foreign partners' share of income from such business. Further, in certain cases where a Form W-9 has not been received, a partnership is required to presume that a partner is a foreign person, and pay the withholding tax. Therefore, if you are a U.S. person that is a partner in a partnership conducting a trade or business in the United States, provide Form W-9 to the partnership to establish your U.S. status and avoid withholding on your share of partnership income.

The person who gives Form W-9 to the partnership for purposes of establishing its U.S. status and avoiding withholding on its allocable share of net income from the partnership conducting a trade or business in the United States is in the following cases:

- The U.S. owner of a disregarded entity and not the entity,

CONTRACT FORMS

The awarded bidder will be required to complete and submit documents substantially similar in form to the following.

These forms may need to be modified on account of changed circumstances, and are provided for informational purposes only.

CITY - CONTRACTOR AGREEMENT

CONTRACT NO. C -

THIS AGREEMENT made this ____ day of _____ in the year Two Thousand and Fourteen by and between the CITY OF NEWTON, a municipal corporation organized and existing under the laws of the Commonwealth of Massachusetts, hereinafter referred to as the CITY, acting through its Chief Procurement Officer, but without personal liability to him, and hereinafter referred to as the CONTRACTOR.

The parties hereto for the considerations hereinafter set forth agree as follows:

ARTICLE 1. STATEMENT OF WORK. The Contractor shall furnish all labor, materials, and equipment and perform all work required in strict accordance with the Contract Documents for the following project:

COLD-PLANING OF BITUMINOUS CONCRETE PAVEMENT AT VARIOUS LOCATIONS
(See street listing @ Item Sheet /Page 1 & 2 and Special Information on Item Sheet 3)

ARTICLE 2. TIME OF COMPLETION. The Contractor shall commence work under this Contract on the date specified in the written notice of the City to proceed and shall fully complete all work hereunder within the time specified in the Summary of Work and Specific Work Requirements of the Project Manual. Time is of the essence with regard to this contract. Failure to complete within the time specified shall be subject to the assessment of liquidated damages in accordance with the provisions contained in the Project Manual.

ARTICLE 3. THE CONTRACT PRICE. The City shall pay the Contractor for the full and satisfactory performance of the Contract, in current funds a sum not to exceed:

(\$)

ARTICLE 4. CONTRACT DOCUMENTS. The Contract Documents consist of the following documents which are either attached to this Agreement or are incorporated herein by reference:

- a. This CITY-CONTRACTOR Agreement;
- b. The City's Invitation For Bid #14-86 issued by the Purchasing Department;
- c. The Project Manual for: **COLD-PLANING OF BITUMINOUS CONCRETE PAVEMENT AT VARIOUS LOCATIONS** including the Instructions to Bidders; General Conditions; Special Conditions; MWBE/AA Requirements, Wage Rate Requirements and Wage Rate Schedule(s) including any updated prevailing wage rate schedules if applicable; The Supplementary Special Conditions; General Requirements and Project Specifications; and Drawings, if included or referenced therein;
- d. Addenda Number(s) _____;
- e. The Bid Response of the CONTRACTOR submitted for this Project and accompanying documents and certifications;
- f. Certificate(s) of Insurance and surety bond(s) submitted by the CONTRACTOR in connection with this Project;

g. Duly authorized and executed Amendments, Change Orders or Shipping Orders issued by the CITY after execution of this CITY-CONTRACTOR Agreement.

This CITY-CONTRACTOR Agreement, together with the other documents enumerated in this Article, constitute the entire Agreement between the CITY and the CONTRACTOR.

ARTICLE 5. ALTERNATES. The following Alternates have been accepted and their costs are included in the Contract Price stated in Article 3 of this Agreement:

Alternates: _____

ARTICLE 6. APPLICABLE STATUTES. All applicable federal, state and local laws and regulations are incorporated herein by reference and the Contractor agrees to comply with same.

IN WITNESS WHEREOF, the parties have caused this instrument to be executed under seal the day and year first above written.

CONTRACTOR

By _____
Print Name _____
Title _____
Date _____

Affix Corporate Seal Here

City funds are available in the following accounts:
33N401H-586002 -

I further certify that the Mayor, or his designee, is authorized to execute contracts and approve change orders.

By _____
Comptroller of Accounts

Date _____

CITY OF NEWTON

By _____
Chief Procurement Officer

Date _____

By _____
Commissioner of Public Works

Date _____

Approved as to Legal Form and Character

By _____
Associate City Solicitor

Date _____

CONTRACT & BONDS ARE APPROVED

By _____
Mayor or his designee

Date _____

CERTIFICATE OF AUTHORITY - CORPORATE

1. I hereby certify that I am the Clerk/Secretary of _____
(insert full name of Corporation)
2. corporation, and that _____
(insert the name of officer who signed the **contract and bonds.**)
3. is the duly elected _____
(insert the title of the officer in line 2)
4. of said corporation, and that on _____
(insert a date that is ***ON OR BEFORE*** the date the officer signed the **contract and bonds.**)

at a duly authorized meeting of the Board of Directors of said corporation, at which all the directors were present or waived notice, it was voted that

5. _____ the _____
(insert **name** from line 2) (insert **title** from line 3)

of this corporation be and hereby is authorized to execute contracts and bonds in the name and on behalf of said corporation, and affix its Corporate Seal thereto, and such execution of any contract of obligation in this corporation's name and on its behalf, with or without the Corporate Seal, shall be valid and binding upon this corporation; and that the above vote has not been amended or rescinded and remains in full force and effect as of the date set forth below.

6. ATTEST: _____ *AFFIX CORPORATE
(Signature of **Clerk or Secretary**)* SEAL HERE*
7. Name: _____
(Please print or type name in line 6)*
8. Date: _____
(insert a date that is ***ON OR AFTER*** the date the officer signed the **contract and bonds.**)

* The name and signature inserted in lines 6 & 7 **must** be that of the **Clerk or Secretary** of the corporation.

CERTIFICATION OF TAX COMPLIANCE

Pursuant to M.G.L. c.62C, §49A and requirements of the City, the undersigned acting on behalf of the Contractor certifies under the penalties of perjury that the Contractor is in compliance with all laws of the Commonwealth relating to taxes including payment of all local taxes, fees, assessments, betterments and any other local or municipal charges (unless the Contractor has a pending abatement application or has entered into a payment agreement with the entity to which such charges were owed), reporting of employees and contractors, and withholding and remitting child support.*

**Signature of Individual
or Corporate Contractor (Mandatory)

Print Name: _____

By: _____
Corporate Officer
(Mandatory, if applicable)

Print Name: _____

*** Contractor's Social Security Number
(Voluntary) or Federal Identification Number

Date: _____

* The provision in this Certification relating to child support applies only when the Contractor is an individual.

** Approval of a contract or other agreement will not be granted until the City receives a signed copy of this Certification.

*** Your social security number may be furnished to the Massachusetts Department of Revenue to determine whether you have met tax filing or tax payment obligations. Providers who fail to correct their non-filing or delinquency will not have a contract or other agreement issued, renewed, or extended.

CITY OF NEWTON, MASSACHUSETTS

PAYMENT BOND

Know All Men By These Presents:

That we, _____, as PRINCIPAL, and _____, as SURETY, are held and firmly bound unto the City of Newton as Obligee, in the sum of _____ dollars (\$_____) to be paid to the Obligee, for which payments well and truly to be made, we bind ourselves, our respective heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

Whereas, the said PRINCIPAL has made a contract with the Obligee, bearing the date of _____, 2014 for the construction of _____ in Newton, Massachusetts.
(Project Title)

Now, the conditions of this obligation are such that if the PRINCIPAL and all Sub-contractors under said contract shall pay for all labor performed or furnished and for all materials used or employed in said contract and in any and all duly authorized modifications, alterations, extensions of time, changes or additions to said contract that may hereafter be made, notice to the SURETY of such modifications, alterations, extensions of time, changes or additions being hereby waived, the foregoing to include any other purposes or items set out in, and to be subject to, provisions of M.G.L. c. 30, sec. 39A, and M.G.L. c. 149 sec. 29, as amended, then this obligation shall become null and void; otherwise it shall remain in full force, virtue and effect.

In Witness Whereof, the PRINCIPAL and SURETY have hereto set their hands and seals this ____day of _____2014.

PRINCIPAL

SURETY

BY _____

BY _____

(SEAL)

(ATTORNEY-IN-FACT) (SEAL)

(Title)

ATTEST: _____

ATTEST: _____

END OF SECTION

**CITY OF NEWTON, MASSACHUSETTS
PURCHASING DEPARTMENT
GENERAL TERMS AND CONDITIONS**

1. The right is reserved to reject any and all bids, to waive informalities, and to make award as may be determined to be in the best interest of the City of Newton.
2. Prices quoted must include delivery to the City , as specified on the Work Order.
3. No charges will be allowed for packing, crating, freight, Express or cartage unless specifically stated and included in the bid.
4. The award to the successful bidder may be canceled if successful bidder shall fail to prosecute the work with promptness and diligence.
5. Time in connection with discount offered will be computed from the date of delivery to the City, as specified on Work order, or from date correct invoice is received by the City, if the latter date is later than the date of delivery.
6. The successful bidder shall replace, repair or make good, without cost to the City, any defects or faults arising within one (1) year after date of acceptance of articles furnished hereunder (acceptance not to be unreasonably delayed) resulting from imperfect or defective work done or materials furnished by the Seller.
7. The Seller shall indemnify and save harmless the City and all persons acting for on behalf of it from all suits and claims against them, or any of them, arising from or occasioned by the use of any material, equipment or apparatus, or any part thereof, which infringes or is alleged to infringe on any patent rights. In case such material, equipment or apparatus, or any part thereof, in any such suit is held to constitute infringement, the Seller, within a reasonable time, will at its expense, and as the City may elect, replace such material, equipment or apparatus with non-infringing material, equipment or apparatus, or remove the material, equipment or apparatus, and refund the sums paid therefor.
8. The successful bidder shall comply with all applicable Federal State and Local laws and regulations.
9. Purchases made by the City are exempt from Federal excise taxes and bid prices must exclude any such taxes. Tax exemption certificates will be furnished upon request.
10. If so stated in the Invitation For Bid the successful bidder will be required to furnish a performance and/or a labor and material payment bond, in an amount, in a form and with a surety satisfactory to the City. The bidder shall be responsible for the cost of the bond(s).
11. If the Invitation for Bids requires bid surety, this surety shall be in the form of a cash, bid bond, cashier's check, treasurer's check, or certified check on a responsible bank, payable to the City of Newton, and must be filed with the original bid in the Office of the Purchasing Agent. Failure to do so will lead to rejection of bid. The bid surety will be returned to the successful bidder within seven (7) days execution of awarded, and approval by the City of performance and/or payment bond(s). In case of default, the bid surety shall be forfeited to the City.
12. Verbal orders are not binding on the City and deliveries made or work done without formal Work Order or Contract are at the risk of the Seller or Contractor and may result in an unenforceable claim.
13. The Seller shall agree to indemnify, defend and hold the City harmless from any and all claims arising out of the performance of this contract.
14. "Equality - An item equal to that named or described in the specifications of the contract may be furnished by the Vendor and the naming of any commercial name, trademark or other identification shall not be construed to exclude any item or manufacturer not mentioned by name or as limiting competition but shall establish a standard of equality only. An item shall be considered equal to the item so named or described if (1) it is at least equal in quality, durability, appearance, strength and design; (2) it will perform at least equally the function imposed by the general design for the work being contracted for or the material being purchased; and (3) it conforms substantially, even with deviations, to the detailed requirements for the item in the specifications. The name and identification of all materials other than the one specifically named shall be submitted to the City in writing for approval, prior to purchase, use or fabrication of such items. Subject to the provisions of M.G.L., Ch. 30, Sec. 39J, approval shall be at the sole discretion of the City, shall be in writing to be effective, and the decision of the City

shall be final. The City may require tests of all materials so submitted to establish quality standards at the Vendor's expense. All directions, specifications and recommendations by manufacturers for installation, handling, storing, adjustment and operation of their equipment shall be complied with; responsibility for proper performance shall continue to rest with the Vendor.

For the use of material other than the one specified, the Vendor shall assume the cost of and responsibility for satisfactorily accomplishing all changes in the work as shown. If no manufacturer is named, the Vendor shall submit the product he intends to use for approval of the City.

Except as otherwise provided for by the provisions of M.G.L., Ch. 30, Sec. 39J, the Vendor shall not have any right of appeal from the decision of the City condemning any materials furnished if the Vendor fails to obtain the approval for substitution under this clause. If any substitution is more costly, the Vendor shall pay for such costs."

15. Notice is hereby given that the City of Newton Minority/Women Business Enterprise Plan dated December 1999 is applicable to all City of Newton contracts for materials and supplies. A copy of this plan may be obtained from the Purchasing Department.

16. Right To Know:

Any vendor who receives an order or orders resulting from this invitation agrees to submit a Material Safety Data Sheet (MSDS) for each toxic or hazardous substance or mixture containing such substance, pursuant to M.G.L., Ch. 111F, SS8, 9 and 10 and the regulations contained in 441 CMR SS 21.06 when deliveries are made. The vendor agrees to deliver all containers properly labeled pursuant to M.G.L. Ch. 111F, SS 7 and the regulations contained in 441 CMR SS 21.05. Failure to submit an MSDS and/or label on each container will place the vendor in noncompliance with the work order. Failure to furnish MSDSs and/or labels on each container may result in civil or criminal penalties, including bid debarment and action to prevent the vendor from selling said substances or mixtures containing said substances within the Commonwealth. All vendors furnishing substances or mixtures subject to Chapter 111F of the M.G.L. are cautioned to obtain and read the law and rules and regulations referred to above. Copies can be obtained from the State House Book Store, Secretary of State, State House, Room 117, Boston, MA 02133, (617-727-2834) for \$2.00 plus \$.65 postage.

17. **INSURANCE REQUIREMENTS**

The Contractor shall provide insurance coverage as listed below. This insurance shall be provided at the Contractor's expense and shall be in full force and effect during the full term of this Contract.

WORKER'S COMPENSATION

Worker's Compensation: Per M.G.L. c. 149, §34 and c.. 152 as amended.

COMMERCIAL GENERAL LIABILITY

Personal Injury	\$500,000 each occurrence
	\$1,000,000 aggregate
Property Damage	\$500,000 each occurrence
	\$1,000,000 aggregate

VEHICLE LIABILITY

Personal Injury	\$500,000 each person
	\$1,000,000 aggregate
Property Damage	\$300,000 each occurrence
	\$500,000 aggregate

The City shall be named as additional insureds on the Contractor's Liability Policies.

The Contractor shall not commence the work until proof of compliance with this has been furnished to the City by submitting one copy of a properly endorsed insurance certificate issued by a company authorized to write insurance in the Commonwealth. This certificate shall indicate that the contractual liability coverage is in force.

The Contractor shall file the original and one certified copy of all policies with the City within ten (10) days after contract award. If the City is damaged by the Contractor's failure to maintain such insurance and to so notify the City, then the Contractor shall be responsible for all reasonable costs attributable thereto.

Cancellation of any insurance required by this contract, whether by the insurer or the insured, shall not be valid unless written notice thereof is given by the party proposing cancellation to the other party and City at least thirty days prior to the effective date thereof, which shall be expressed in said notice.

FAILURE TO COMPLY WITH THESE TERMS AND CONDITIONS COULD RESULT IN THE CANCELLATION OF YOUR CONTRACT.

CITY OF NEWTON

WAGE RATE REQUIREMENTS

1. GENERAL

- A.** This section summarizes the requirements for the payment of wages to laborers and mechanics employed under the Contract.
- B.** Other duties and requirements of law which may not be specified in this section apply and are inherently a part of the Contract.

2. WAGE RATES

- A.** The rate per hour to be paid to mechanics, apprentices, teamsters, chauffeurs, and laborers employed on the Work shall not be less than the rate of wages in the attached "Minimum Wage Rates" as determined by the Commissioner of Labor and Industries. This schedule shall continue to be the minimum rate of wages for said employees during the life of this Contract.
- B.** Keep posted on the site a legible copy of said schedule. Keep on file the wage rates and classifications of labor employed on this Work in order that they may be available for inspection by the Owner, Administrator, or the Architect.
- C.** Apprentices employed pursuant to this determination of wage rates must be registered and approved by the State Apprenticeship Council wherever rates for journeymen or apprentices are not listed.
- D.** Pay reserve police officers employed on the Work the prevailing rate of wages paid to regular police officers as required by M.G.L. c149, Sec. 34B, as amended. Such police officers shall be covered by Workmen's Compensation Insurance and Employers Liability Insurance by the Contractor.
- E.** The Contractor and all subcontractors shall, on a weekly basis throughout the term of the contract, provide to the City of Newton certified payroll affidavits verifying compliance with M.G.L. c.149, Sec. 27, 27A and 27B. The Contractor is obligated to provide such records to the City directly on a weekly basis. The City may assess a penalty of \$100 for each day beyond the required submission date that such records are received, which amount shall be deducted from any amounts to the Contractor from the City. In the event of chronic late submissions, the City shall report the same to the Office of the Attorney General.
- F.** The Contractor and all subcontractors shall provide a Statement of Compliance within 15 days of the completion of its portion of the work. This statement shall be submitted to the Owner on the form found elsewhere in this section.
- G.** The Contractor shall maintain accurate and complete records, including payroll records, during the Contract term and for three years thereafter.

END OF SECTION



DEVAL L. PATRICK
Governor

THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF LABOR AND WORKFORCE DEVELOPMENT
DEPARTMENT OF LABOR STANDARDS

Prevailing Wage Rates

As determined by the Director under the provisions of the
Massachusetts General Laws, Chapter 149, Sections 26 to 27H

JOANNE F. GOLDSTEIN
Secretary
HEATHER E. ROWE
Director

Awarding Authority: City of Newton
Contract Number: #14-86 **City/Town:** NEWTON
Description of Work: Cold-Planing of Bituminous Concrete Pavement
Job Location: Various Locations

Information about Prevailing Wage Schedules for Awarding Authorities and Contractors

- This wage schedule applies only to the specific project referenced at the top of this page and uniquely identified by the "Wage Request Number" on all pages of this schedule.
- Awarding authorities must request an updated wage schedule from the Department of Labor Standards ("DLS") if it has not opened bids or selected a contractor within 90 days of the date of issuance of the wage schedule.
- The wage schedule shall be incorporated in any advertisement or call for bids for the project as required by M.G.L. c. 149, § 27. Once a contractor has been selected by the awarding authority, the wage schedule shall be made a part of the contract for that project. The wage schedule must be posted in a conspicuous place at the work site during the life of the project in accordance with M.G.L. c. 149, § 27. The wages listed on the wage schedule must be paid to employees performing construction work on the project regardless of whether they are employed by the prime contractor, a filed sub-bidder, or any sub-contractor.
- All apprentices working on the project are required to be registered with the Massachusetts Division of Apprentice Training (DAT). Apprentices must keep his/her apprentice identification card on his/her person during all work hours on the project. If an apprentice rate is listed on the prevailing wage schedule for the trade in which an apprentice is registered with the DAT, the apprentice may be paid the lower apprentice wage rate at the applicable step as provided on the prevailing wage schedule. **If an apprentice rate is not listed on the prevailing wage schedule for the trade in which an apprentice is registered with the DAT, the apprentice must be paid the journeyworker's rate for the trade.**
- The wage rates will remain in effect for the duration of the project, except in the case of multi-year public construction projects. For construction projects lasting longer than one year, awarding authorities must request an updated wage schedule. Awarding authorities are required to request these updates no later than two weeks before the anniversary of the date the contract was executed by the awarding authority and the general contractor. Contractors are required to obtain the wage schedules from awarding authorities, and to pay no less than these rates to covered workers. The annual update requirement is not applicable to 27F "rental of equipment" contracts.
- Every contractor or subcontractor which performs construction work on the project is required to submit weekly payroll reports directly to the awarding authority and keep them on file for three years. Each weekly payroll report must contain: the employee's name, address, occupational classification, hours worked, and wages paid. Do not submit weekly payroll reports to DLS. A sample of a payroll reporting form may be obtained at <http://www.mass.gov/dols/pw>.
- Contractors with questions about the wage rates or classifications included on the wage schedule have an affirmative obligation to inquire with DLS at (617) 626-6953.
- Employees not receiving the prevailing wage rate set forth on the wage schedule may report the violation to the Fair Labor Division of the office of the Attorney General at (617) 727-3465.
- Failure of a contractor or subcontractor to pay the prevailing wage rates listed on the wage schedule to all employees who perform construction work on the project is a violation of the law and subjects the contractor or subcontractor to civil and criminal penalties.

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Construction						
(2 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE A</i>	12/01/2013	\$32.05	\$9.41	\$8.80	\$0.00	\$50.26
	06/01/2014	\$32.40	\$9.41	\$8.80	\$0.00	\$50.61
	08/01/2014	\$32.40	\$9.91	\$8.80	\$0.00	\$51.11
	12/01/2014	\$32.40	\$9.91	\$9.33	\$0.00	\$51.64
	06/01/2015	\$32.75	\$9.91	\$9.33	\$0.00	\$51.99
	08/01/2015	\$32.75	\$10.41	\$9.33	\$0.00	\$52.49
	12/01/2015	\$32.75	\$10.41	\$10.08	\$0.00	\$53.24
	06/01/2016	\$33.25	\$10.41	\$10.08	\$0.00	\$53.74
	08/01/2016	\$33.25	\$10.91	\$10.08	\$0.00	\$54.24
	12/01/2016	\$33.25	\$10.91	\$10.89	\$0.00	\$55.05
(3 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE A</i>	12/01/2013	\$32.12	\$9.41	\$8.80	\$0.00	\$50.33
	06/01/2014	\$32.47	\$9.41	\$8.80	\$0.00	\$50.68
	08/01/2014	\$32.47	\$9.91	\$8.80	\$0.00	\$51.18
	12/01/2014	\$32.47	\$9.91	\$9.33	\$0.00	\$51.71
	06/01/2015	\$32.82	\$9.91	\$9.33	\$0.00	\$52.06
	08/01/2015	\$32.82	\$10.41	\$9.33	\$0.00	\$52.56
	12/01/2015	\$32.82	\$10.41	\$10.08	\$0.00	\$53.31
	06/01/2016	\$33.32	\$10.41	\$10.08	\$0.00	\$53.81
	08/01/2016	\$33.32	\$10.91	\$10.08	\$0.00	\$54.31
	12/01/2016	\$33.32	\$10.91	\$10.89	\$0.00	\$55.12
(4 & 5 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE A</i>	12/01/2013	\$32.24	\$9.41	\$8.80	\$0.00	\$50.45
	06/01/2014	\$32.59	\$9.41	\$8.80	\$0.00	\$50.80
	08/01/2014	\$32.59	\$9.91	\$8.80	\$0.00	\$51.30
	12/01/2014	\$32.59	\$9.91	\$9.33	\$0.00	\$51.83
	06/01/2015	\$32.94	\$9.91	\$9.33	\$0.00	\$52.18
	08/01/2015	\$32.94	\$10.41	\$9.33	\$0.00	\$52.68
	12/01/2015	\$32.94	\$10.41	\$10.08	\$0.00	\$53.43
	06/01/2016	\$33.44	\$10.41	\$10.08	\$0.00	\$53.93
	08/01/2016	\$33.44	\$10.91	\$10.08	\$0.00	\$54.43
	12/01/2016	\$33.44	\$10.91	\$10.89	\$0.00	\$55.24
ADS/SUBMERSIBLE PILOT <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2013	\$84.21	\$9.80	\$18.17	\$0.00	\$112.18
	08/01/2014	\$87.36	\$9.80	\$18.17	\$0.00	\$115.33
	08/01/2015	\$90.51	\$9.80	\$18.17	\$0.00	\$118.48
AIR TRACK OPERATOR <i>LABORERS - ZONE 1</i>	12/01/2013	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	06/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	12/01/2014	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	06/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	12/01/2015	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	06/01/2016	\$37.85	\$7.30	\$12.70	\$0.00	\$57.85
	12/01/2016	\$38.85	\$7.30	\$12.70	\$0.00	\$58.85
For apprentice rates see "Apprentice- LABORER"						

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 2 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
ASBESTOS REMOVER - PIPE / MECH. EQUIPT. HEAT & FROST INSULATORS LOCAL 6 (BOSTON)	12/01/2013	\$30.68	\$10.40	\$5.95	\$0.00	\$47.03
	06/01/2014	\$31.58	\$10.40	\$5.95	\$0.00	\$47.93
	12/01/2014	\$32.48	\$10.40	\$5.95	\$0.00	\$48.83
	06/01/2015	\$33.43	\$10.40	\$5.95	\$0.00	\$49.78
	12/01/2015	\$34.38	\$10.40	\$5.95	\$0.00	\$50.73
ASPHALT RAKER LABORERS - ZONE 1	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
ASPHALT/CONCRETE/CRUSHER PLANT-ON SITE OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BACKHOE/FRONT-END LOADER OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BARCO-TYPE JUMPING TAMPER LABORERS - ZONE 1	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
BLOCK PAVER, RAMMER / CURB SETTER LABORERS - ZONE 1	12/01/2013	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	06/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	12/01/2014	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	06/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	12/01/2015	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	06/01/2016	\$37.85	\$7.30	\$12.70	\$0.00	\$57.85
	12/01/2016	\$38.85	\$7.30	\$12.70	\$0.00	\$58.85
For apprentice rates see "Apprentice- LABORER"						
BOILER MAKER BOILERMAKERS LOCAL 29	01/01/2010	\$37.70	\$6.97	\$11.18	\$0.00	\$55.85

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 3 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - BOILERMAKER - Local 29

Effective Date - 01/01/2010

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	65	\$24.51	\$6.97	\$11.18	\$0.00	\$42.66
2	65	\$24.51	\$6.97	\$11.18	\$0.00	\$42.66
3	70	\$26.39	\$6.97	\$11.18	\$0.00	\$44.54
4	75	\$28.28	\$6.97	\$11.18	\$0.00	\$46.43
5	80	\$30.16	\$6.97	\$11.18	\$0.00	\$48.31
6	85	\$32.05	\$6.97	\$11.18	\$0.00	\$50.20
7	90	\$33.93	\$6.97	\$11.18	\$0.00	\$52.08
8	95	\$35.82	\$6.97	\$11.18	\$0.00	\$53.97

Notes:

Apprentice to Journeyworker Ratio:1:5

BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING)	02/01/2014	\$48.06	\$10.18	\$18.15	\$0.00	\$76.39
BRICKLAYERS LOCAL 3 (NEWTON)	08/01/2014	\$48.96	\$10.18	\$18.22	\$0.00	\$77.36
	02/01/2015	\$49.52	\$10.18	\$18.22	\$0.00	\$77.92
	08/01/2015	\$50.42	\$10.18	\$18.29	\$0.00	\$78.89
	02/01/2016	\$50.99	\$10.18	\$18.29	\$0.00	\$79.46
	08/01/2016	\$51.89	\$10.18	\$18.37	\$0.00	\$80.44
	02/01/2017	\$52.46	\$10.18	\$18.37	\$0.00	\$81.01

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 4 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - BRICK/PLASTER/CEMENT MASON - Local 3 Newton

Effective Date - 02/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.03	\$10.18	\$18.15	\$0.00	\$52.36
2	60	\$28.84	\$10.18	\$18.15	\$0.00	\$57.17
3	70	\$33.64	\$10.18	\$18.15	\$0.00	\$61.97
4	80	\$38.45	\$10.18	\$18.15	\$0.00	\$66.78
5	90	\$43.25	\$10.18	\$18.15	\$0.00	\$71.58

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.48	\$10.18	\$18.22	\$0.00	\$52.88
2	60	\$29.38	\$10.18	\$18.22	\$0.00	\$57.78
3	70	\$34.27	\$10.18	\$18.22	\$0.00	\$62.67
4	80	\$39.17	\$10.18	\$18.22	\$0.00	\$67.57
5	90	\$44.06	\$10.18	\$18.22	\$0.00	\$72.46

Notes:

Apprentice to Journeyworker Ratio:1:5

BULLDOZER/GRADER/SCRAPER OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
---	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

CAISSON & UNDERPINNING BOTTOM MAN LABORERS - FOUNDATION AND MARINE	12/01/2013	\$34.45	\$7.30	\$12.90	\$0.00	\$54.65
	06/01/2014	\$35.20	\$7.30	\$12.90	\$0.00	\$55.40
	12/01/2014	\$35.95	\$7.30	\$12.90	\$0.00	\$56.15
	06/01/2015	\$36.70	\$7.30	\$12.90	\$0.00	\$56.90
	12/01/2015	\$37.45	\$7.30	\$12.90	\$0.00	\$57.65
	06/01/2016	\$38.20	\$7.30	\$12.90	\$0.00	\$58.40
	12/01/2016	\$39.20	\$7.30	\$12.90	\$0.00	\$59.40

For apprentice rates see "Apprentice- LABORER"

CAISSON & UNDERPINNING LABORER LABORERS - FOUNDATION AND MARINE	12/01/2013	\$33.30	\$7.30	\$12.90	\$0.00	\$53.50
	06/01/2014	\$34.05	\$7.30	\$12.90	\$0.00	\$54.25
	12/01/2014	\$34.80	\$7.30	\$12.90	\$0.00	\$55.00
	06/01/2015	\$35.55	\$7.30	\$12.90	\$0.00	\$55.75
	12/01/2015	\$36.30	\$7.30	\$12.90	\$0.00	\$56.50
	06/01/2016	\$37.05	\$7.30	\$12.90	\$0.00	\$57.25
	12/01/2016	\$38.05	\$7.30	\$12.90	\$0.00	\$58.25

For apprentice rates see "Apprentice- LABORER"

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 5 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
CAISSON & UNDERPINNING TOP MAN <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2013	\$33.30	\$7.30	\$12.90	\$0.00	\$53.50
	06/01/2014	\$34.05	\$7.30	\$12.90	\$0.00	\$54.25
	12/01/2014	\$34.80	\$7.30	\$12.90	\$0.00	\$55.00
	06/01/2015	\$35.55	\$7.30	\$12.90	\$0.00	\$55.75
	12/01/2015	\$36.30	\$7.30	\$12.90	\$0.00	\$56.50
	06/01/2016	\$37.05	\$7.30	\$12.90	\$0.00	\$57.25
	12/01/2016	\$38.05	\$7.30	\$12.90	\$0.00	\$58.25
For apprentice rates see "Apprentice- LABORER"						
CARBIDE CORE DRILL OPERATOR <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
CARPENTER <i>CARPENTERS -ZONE 2 (Eastern Massachusetts)</i>	09/01/2013	\$34.53	\$9.80	\$15.61	\$0.00	\$59.94
	03/01/2014	\$35.13	\$9.80	\$15.61	\$0.00	\$60.54
	09/01/2014	\$35.90	\$9.80	\$15.61	\$0.00	\$61.31
	03/01/2015	\$36.67	\$9.80	\$15.61	\$0.00	\$62.08

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - CARPENTER - Zone 2 Eastern MA

Effective Date - 09/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.27	\$9.80	\$1.57	\$0.00	\$28.64
2	60	\$20.72	\$9.80	\$1.57	\$0.00	\$32.09
3	70	\$24.17	\$9.80	\$10.90	\$0.00	\$44.87
4	75	\$25.90	\$9.80	\$10.90	\$0.00	\$46.60
5	80	\$27.62	\$9.80	\$12.47	\$0.00	\$49.89
6	80	\$27.62	\$9.80	\$12.47	\$0.00	\$49.89
7	90	\$31.08	\$9.80	\$14.04	\$0.00	\$54.92
8	90	\$31.08	\$9.80	\$14.04	\$0.00	\$54.92

Effective Date - 03/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.57	\$9.80	\$1.57	\$0.00	\$28.94
2	60	\$21.08	\$9.80	\$1.57	\$0.00	\$32.45
3	70	\$24.59	\$9.80	\$10.90	\$0.00	\$45.29
4	75	\$26.35	\$9.80	\$10.90	\$0.00	\$47.05
5	80	\$28.10	\$9.80	\$12.47	\$0.00	\$50.37
6	80	\$28.10	\$9.80	\$12.47	\$0.00	\$50.37
7	90	\$31.62	\$9.80	\$14.04	\$0.00	\$55.46
8	90	\$31.62	\$9.80	\$14.04	\$0.00	\$55.46

Notes:

Apprentice to Journeyworker Ratio:1:5

CEMENT MASONRY/PLASTERING
BRICKLAYERS LOCAL 3 (NEWTON)

01/01/2014	\$43.60	\$10.90	\$18.71	\$1.30	\$74.51
07/01/2014	\$43.77	\$10.90	\$18.71	\$1.30	\$74.68
01/01/2015	\$44.69	\$10.90	\$18.71	\$1.30	\$75.60
07/01/2015	\$45.29	\$10.90	\$18.71	\$1.30	\$76.20
01/01/2016	\$46.21	\$10.90	\$18.71	\$1.30	\$77.12

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 7 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - CEMENT MASONRY/PLASTERING - Eastern Mass (Newton)

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.80	\$10.90	\$12.21	\$1.30	\$46.21
2	60	\$26.16	\$10.90	\$13.71	\$1.30	\$52.07
3	65	\$28.34	\$10.90	\$14.71	\$1.30	\$55.25
4	70	\$30.52	\$10.90	\$15.71	\$1.30	\$58.43
5	75	\$32.70	\$10.90	\$16.71	\$1.30	\$61.61
6	80	\$34.88	\$10.90	\$17.71	\$1.30	\$64.79
7	90	\$39.24	\$10.90	\$18.71	\$1.30	\$70.15

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.89	\$10.90	\$12.21	\$1.30	\$46.30
2	60	\$26.26	\$10.90	\$13.71	\$1.30	\$52.17
3	65	\$28.45	\$10.90	\$14.71	\$1.30	\$55.36
4	70	\$30.64	\$10.90	\$15.71	\$1.30	\$58.55
5	75	\$32.83	\$10.90	\$16.71	\$1.30	\$61.74
6	80	\$35.02	\$10.90	\$17.71	\$1.30	\$64.93
7	90	\$39.39	\$10.90	\$18.71	\$1.30	\$70.30

Notes:

Steps 3,4 are 500 hrs. All other steps are 1,000 hrs.

Apprentice to Journeyworker Ratio:1:3

CHAIN SAW OPERATOR	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
LABORERS - ZONE 1	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
CLAM SHELLS/SLURRY BUCKETS/HEADING MACHINES	12/01/2013	\$41.49	\$10.00	\$14.18	\$0.00	\$65.67
OPERATING ENGINEERS LOCAL 4	For apprentice rates see "Apprentice- OPERATING ENGINEERS"					
COMPRESSOR OPERATOR	12/01/2013	\$28.11	\$10.00	\$14.18	\$0.00	\$52.29
OPERATING ENGINEERS LOCAL 4	For apprentice rates see "Apprentice- OPERATING ENGINEERS"					
DELEADER (BRIDGE)	01/01/2014	\$45.91	\$7.85	\$16.10	\$0.00	\$69.86
PAINTERS LOCAL 35 - ZONE 2	07/01/2014	\$46.76	\$7.85	\$16.10	\$0.00	\$70.71
	01/01/2015	\$47.66	\$7.85	\$16.10	\$0.00	\$71.61
	07/01/2015	\$48.56	\$7.85	\$16.10	\$0.00	\$72.51
	01/01/2016	\$49.51	\$7.85	\$16.10	\$0.00	\$73.46
	07/01/2016	\$50.46	\$7.85	\$16.10	\$0.00	\$74.41
	01/01/2017	\$51.41	\$7.85	\$16.10	\$0.00	\$75.36

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 8 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.96	\$7.85	\$0.00	\$0.00	\$30.81
2	55	\$25.25	\$7.85	\$3.66	\$0.00	\$36.76
3	60	\$27.55	\$7.85	\$3.99	\$0.00	\$39.39
4	65	\$29.84	\$7.85	\$4.32	\$0.00	\$42.01
5	70	\$32.14	\$7.85	\$14.11	\$0.00	\$54.10
6	75	\$34.43	\$7.85	\$14.44	\$0.00	\$56.72
7	80	\$36.73	\$7.85	\$14.77	\$0.00	\$59.35
8	90	\$41.32	\$7.85	\$15.44	\$0.00	\$64.61

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.38	\$7.85	\$0.00	\$0.00	\$31.23
2	55	\$25.72	\$7.85	\$3.66	\$0.00	\$37.23
3	60	\$28.06	\$7.85	\$3.99	\$0.00	\$39.90
4	65	\$30.39	\$7.85	\$4.32	\$0.00	\$42.56
5	70	\$32.73	\$7.85	\$14.11	\$0.00	\$54.69
6	75	\$35.07	\$7.85	\$14.44	\$0.00	\$57.36
7	80	\$37.41	\$7.85	\$14.77	\$0.00	\$60.03
8	90	\$42.08	\$7.85	\$15.44	\$0.00	\$65.37

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

DEMO: ADZEMAN
LABORERS - ZONE 1

12/01/2013	\$33.50	\$7.30	\$12.70	\$0.00	\$53.50
06/01/2014	\$34.25	\$7.30	\$12.70	\$0.00	\$54.25
12/01/2014	\$35.00	\$7.30	\$12.70	\$0.00	\$55.00
06/01/2015	\$35.75	\$7.30	\$12.70	\$0.00	\$55.75
12/01/2015	\$36.50	\$7.30	\$12.70	\$0.00	\$56.50

For apprentice rates see "Apprentice- LABORER"

DEMO: BACKHOE/LOADER/HAMMER OPERATOR
LABORERS - ZONE 1

12/01/2013	\$34.50	\$7.30	\$12.70	\$0.00	\$54.50
06/01/2014	\$35.25	\$7.30	\$12.70	\$0.00	\$55.25
12/01/2014	\$36.00	\$7.30	\$12.70	\$0.00	\$56.00
06/01/2015	\$36.75	\$7.30	\$12.70	\$0.00	\$56.75
12/01/2015	\$37.50	\$7.30	\$12.70	\$0.00	\$57.50

For apprentice rates see "Apprentice- LABORER"

DEMO: BURNERS
LABORERS - ZONE 1

12/01/2013	\$34.25	\$7.30	\$12.70	\$0.00	\$54.25
06/01/2014	\$35.00	\$7.30	\$12.70	\$0.00	\$55.00
12/01/2014	\$35.75	\$7.30	\$12.70	\$0.00	\$55.75
06/01/2015	\$36.50	\$7.30	\$12.70	\$0.00	\$56.50
12/01/2015	\$37.25	\$7.30	\$12.70	\$0.00	\$57.25

For apprentice rates see "Apprentice- LABORER"

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 9 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
DEMO: CONCRETE CUTTER/SAWYER <i>LABORERS - ZONE 1</i>	12/01/2013	\$34.50	\$7.30	\$12.70	\$0.00	\$54.50
	06/01/2014	\$35.25	\$7.30	\$12.70	\$0.00	\$55.25
	12/01/2014	\$36.00	\$7.30	\$12.70	\$0.00	\$56.00
	06/01/2015	\$36.75	\$7.30	\$12.70	\$0.00	\$56.75
	12/01/2015	\$37.50	\$7.30	\$12.70	\$0.00	\$57.50
For apprentice rates see "Apprentice- LABORER"						
DEMO: JACKHAMMER OPERATOR <i>LABORERS - ZONE 1</i>	12/01/2013	\$34.25	\$7.30	\$12.70	\$0.00	\$54.25
	06/01/2014	\$35.00	\$7.30	\$12.70	\$0.00	\$55.00
	12/01/2014	\$35.75	\$7.30	\$12.70	\$0.00	\$55.75
	06/01/2015	\$36.50	\$7.30	\$12.70	\$0.00	\$56.50
	12/01/2015	\$37.25	\$7.30	\$12.70	\$0.00	\$57.25
For apprentice rates see "Apprentice- LABORER"						
DEMO: WRECKING LABORER <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.50	\$7.30	\$12.70	\$0.00	\$53.50
	06/01/2014	\$34.25	\$7.30	\$12.70	\$0.00	\$54.25
	12/01/2014	\$35.00	\$7.30	\$12.70	\$0.00	\$55.00
	06/01/2015	\$35.75	\$7.30	\$12.70	\$0.00	\$55.75
	12/01/2015	\$36.50	\$7.30	\$12.70	\$0.00	\$56.50
For apprentice rates see "Apprentice- LABORER"						
DIRECTIONAL DRILL MACHINE OPERATOR <i>OPERATING ENGINEERS LOCAL 4</i>	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DIVER <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2013	\$56.14	\$9.80	\$18.17	\$0.00	\$84.11
	08/01/2014	\$58.24	\$9.80	\$18.17	\$0.00	\$86.21
	08/01/2015	\$60.34	\$9.80	\$18.17	\$0.00	\$88.31
DIVER TENDER <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2013	\$40.10	\$9.80	\$18.17	\$0.00	\$68.07
	08/01/2014	\$41.60	\$9.80	\$18.17	\$0.00	\$69.57
	08/01/2015	\$43.10	\$9.80	\$18.17	\$0.00	\$71.07
DIVER TENDER (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2013	\$60.15	\$9.80	\$18.17	\$0.00	\$88.12
	08/01/2014	\$62.40	\$9.80	\$18.17	\$0.00	\$90.37
	08/01/2015	\$64.65	\$9.80	\$18.17	\$0.00	\$92.62
DIVER/SLURRY (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2013	\$84.21	\$9.80	\$18.17	\$0.00	\$112.18
	08/01/2014	\$87.36	\$9.80	\$18.17	\$0.00	\$115.33
	08/01/2015	\$90.51	\$9.80	\$18.17	\$0.00	\$118.48
DRAWBRIDGE OPERATOR (Construction) <i>ELECTRICIANS LOCAL 103</i>	09/01/2013	\$43.96	\$13.00	\$14.42	\$0.00	\$71.38
	03/01/2014	\$44.45	\$13.00	\$14.68	\$0.00	\$72.13
	09/01/2014	\$45.12	\$13.00	\$14.70	\$0.00	\$72.82
	03/01/2015	\$45.84	\$13.00	\$14.72	\$0.00	\$73.56
	09/01/2015	\$46.80	\$13.00	\$14.75	\$0.00	\$74.55
	03/01/2016	\$47.75	\$13.00	\$14.78	\$0.00	\$75.53
For apprentice rates see "Apprentice- ELECTRICIAN"						
ELECTRICIAN <i>ELECTRICIANS LOCAL 103</i>	09/01/2013	\$43.96	\$13.00	\$14.42	\$0.00	\$71.38
	03/01/2014	\$44.45	\$13.00	\$14.68	\$0.00	\$72.13
	09/01/2014	\$45.12	\$13.00	\$14.70	\$0.00	\$72.82
	03/01/2015	\$45.84	\$13.00	\$14.72	\$0.00	\$73.56
	09/01/2015	\$46.80	\$13.00	\$14.75	\$0.00	\$74.55
	03/01/2016	\$47.75	\$13.00	\$14.78	\$0.00	\$75.53

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 10 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - *ELECTRICIAN - Local 103*

Effective Date - 09/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.58	\$13.00	\$0.53	\$0.00	\$31.11
2	40	\$17.58	\$13.00	\$0.53	\$0.00	\$31.11
3	45	\$19.78	\$13.00	\$10.78	\$0.00	\$43.56
4	45	\$19.78	\$13.00	\$10.78	\$0.00	\$43.56
5	50	\$21.98	\$13.00	\$11.11	\$0.00	\$46.09
6	55	\$24.18	\$13.00	\$11.45	\$0.00	\$48.63
7	60	\$26.38	\$13.00	\$11.77	\$0.00	\$51.15
8	65	\$28.57	\$13.00	\$12.11	\$0.00	\$53.68
9	70	\$30.77	\$13.00	\$12.43	\$0.00	\$56.20
10	75	\$32.97	\$13.00	\$12.77	\$0.00	\$58.74

Effective Date - 03/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.78	\$13.00	\$0.53	\$0.00	\$31.31
2	40	\$17.78	\$13.00	\$0.53	\$0.00	\$31.31
3	45	\$20.00	\$13.00	\$11.04	\$0.00	\$44.04
4	45	\$20.00	\$13.00	\$11.04	\$0.00	\$44.04
5	50	\$22.23	\$13.00	\$11.37	\$0.00	\$46.60
6	55	\$24.45	\$13.00	\$11.70	\$0.00	\$49.15
7	60	\$26.67	\$13.00	\$12.03	\$0.00	\$51.70
8	65	\$28.89	\$13.00	\$12.37	\$0.00	\$54.26
9	70	\$31.12	\$13.00	\$12.69	\$0.00	\$56.81
10	75	\$33.34	\$13.00	\$13.03	\$0.00	\$59.37

Notes:

App Prior 1/1/03; 30/35/40/45/50/55/65/70/75/80

Apprentice to Journeyworker Ratio:2:3***

ELEVATOR CONSTRUCTOR
ELEVATOR CONSTRUCTORS LOCAL 4

01/01/2012 \$52.45 \$8.78 \$6.96 \$0.00 \$68.19

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 11 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - ELEVATOR CONSTRUCTOR - Local 4

Effective Date - 01/01/2012

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$26.23	\$8.78	\$0.00	\$0.00	\$35.01
2	55	\$28.85	\$8.78	\$6.96	\$0.00	\$44.59
3	65	\$34.09	\$8.78	\$6.96	\$0.00	\$49.83
4	70	\$36.72	\$8.78	\$6.96	\$0.00	\$52.46
5	80	\$41.96	\$8.78	\$6.96	\$0.00	\$57.70

Notes:

Steps 1-2 are 6 mos.; Steps 3-5 are 1 year

Apprentice to Journeyworker Ratio:1:1

ELEVATOR CONSTRUCTOR HELPER <i>ELEVATOR CONSTRUCTORS LOCAL 4</i>	01/01/2012	\$38.59	\$8.78	\$6.96	\$0.00	\$54.33
For apprentice rates see "Apprentice - ELEVATOR CONSTRUCTOR"						
FENCE & GUARD RAIL ERECTOR <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice - LABORER"						
FIELD ENG.INST.PERSON-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	11/01/2013	\$38.73	\$10.00	\$13.55	\$0.00	\$62.28
	05/01/2014	\$39.50	\$10.00	\$13.55	\$0.00	\$63.05
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.PARTY CHIEF-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	11/01/2013	\$40.15	\$10.00	\$13.55	\$0.00	\$63.70
	05/01/2014	\$40.92	\$10.00	\$13.55	\$0.00	\$64.47
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.ROD PERSON-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	11/01/2013	\$21.10	\$10.00	\$13.55	\$0.00	\$44.65
	05/01/2014	\$21.55	\$10.00	\$13.55	\$0.00	\$45.10
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIRE ALARM INSTALLER <i>ELECTRICIANS LOCAL 103</i>	09/01/2013	\$43.96	\$13.00	\$14.42	\$0.00	\$71.38
	03/01/2014	\$44.45	\$13.00	\$14.68	\$0.00	\$72.13
	09/01/2014	\$45.12	\$13.00	\$14.70	\$0.00	\$72.82
	03/01/2015	\$45.84	\$13.00	\$14.72	\$0.00	\$73.56
	09/01/2015	\$46.80	\$13.00	\$14.75	\$0.00	\$74.55
	03/01/2016	\$47.75	\$13.00	\$14.78	\$0.00	\$75.53
For apprentice rates see "Apprentice- ELECTRICIAN"						
FIRE ALARM REPAIR / MAINTENANCE / COMMISSIONING <i>ELECTRICIANS</i> <i>LOCAL 103</i>	09/01/2013	\$32.97	\$13.00	\$12.77	\$0.00	\$58.74
	03/01/2014	\$33.44	\$13.00	\$13.03	\$0.00	\$59.47
	09/01/2014	\$33.84	\$13.00	\$13.05	\$0.00	\$59.89
	03/01/2015	\$34.38	\$13.00	\$13.06	\$0.00	\$60.44
	09/01/2015	\$35.10	\$13.00	\$13.08	\$0.00	\$61.18
	03/01/2016	\$35.81	\$13.00	\$13.10	\$0.00	\$61.91

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 12 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- TELECOMMUNICATIONS TECHNICIAN"						
FIREMAN (ASST. ENGINEER) OPERATING ENGINEERS LOCAL 4	12/01/2013	\$33.76	\$10.00	\$14.18	\$0.00	\$57.94
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FLAGGER & SIGNALER LABORERS - ZONE 1	12/01/2013	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
	06/01/2014	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
	12/01/2014	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
	06/01/2015	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
	12/01/2015	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
	06/01/2016	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
	12/01/2016	\$20.50	\$7.30	\$12.70	\$0.00	\$40.50
For apprentice rates see "Apprentice- LABORER"						
FLOORCOVERER FLOORCOVERERS LOCAL 2168 ZONE 1	09/01/2013	\$38.61	\$9.80	\$16.71	\$0.00	\$65.12
	03/01/2014	\$38.61	\$9.80	\$16.71	\$0.00	\$65.12

Apprentice - FLOORCOVERER - Local 2168 Zone 1

Effective Date - 09/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.31	\$9.80	\$1.79	\$0.00	\$30.90
2	55	\$21.24	\$9.80	\$1.79	\$0.00	\$32.83
3	60	\$23.17	\$9.80	\$11.34	\$0.00	\$44.31
4	65	\$25.10	\$9.80	\$11.34	\$0.00	\$46.24
5	70	\$27.03	\$9.80	\$13.13	\$0.00	\$49.96
6	75	\$28.96	\$9.80	\$13.13	\$0.00	\$51.89
7	80	\$30.89	\$9.80	\$14.92	\$0.00	\$55.61
8	85	\$32.82	\$9.80	\$14.92	\$0.00	\$57.54

Effective Date - 03/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.31	\$9.80	\$1.79	\$0.00	\$30.90
2	55	\$21.24	\$9.80	\$1.79	\$0.00	\$32.83
3	60	\$23.17	\$9.80	\$11.34	\$0.00	\$44.31
4	65	\$25.10	\$9.80	\$11.34	\$0.00	\$46.24
5	70	\$27.03	\$9.80	\$13.13	\$0.00	\$49.96
6	75	\$28.96	\$9.80	\$13.13	\$0.00	\$51.89
7	80	\$30.89	\$9.80	\$14.92	\$0.00	\$55.61
8	85	\$32.82	\$9.80	\$14.92	\$0.00	\$57.54

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

FORK LIFT/CHERRY PICKER OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
GENERATOR/LIGHTING PLANT/HEATERS OPERATING ENGINEERS LOCAL 4	12/01/2013	\$28.11	\$10.00	\$14.18	\$0.00	\$52.29

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 13 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS)	01/01/2014	\$35.41	\$7.85	\$16.10	\$0.00	\$59.36
GLAZIERS LOCAL 35 (ZONE 2)	07/01/2014	\$36.56	\$7.85	\$16.10	\$0.00	\$60.51
	01/01/2015	\$37.16	\$7.85	\$16.10	\$0.00	\$61.11
	07/01/2015	\$38.06	\$7.85	\$16.10	\$0.00	\$62.01
	01/01/2016	\$39.01	\$7.85	\$16.10	\$0.00	\$62.96
	07/01/2016	\$39.96	\$7.85	\$16.10	\$0.00	\$63.91
	01/01/2017	\$40.91	\$7.85	\$16.10	\$0.00	\$64.86

Apprentice - GLAZIER - Local 35 Zone 2

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.71	\$7.85	\$0.00	\$0.00	\$25.56
2	55	\$19.48	\$7.85	\$3.66	\$0.00	\$30.99
3	60	\$21.25	\$7.85	\$3.99	\$0.00	\$33.09
4	65	\$23.02	\$7.85	\$4.32	\$0.00	\$35.19
5	70	\$24.79	\$7.85	\$14.11	\$0.00	\$46.75
6	75	\$26.56	\$7.85	\$14.44	\$0.00	\$48.85
7	80	\$28.33	\$7.85	\$14.77	\$0.00	\$50.95
8	90	\$31.87	\$7.85	\$15.44	\$0.00	\$55.16

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.28	\$7.85	\$0.00	\$0.00	\$26.13
2	55	\$20.11	\$7.85	\$3.66	\$0.00	\$31.62
3	60	\$21.94	\$7.85	\$3.99	\$0.00	\$33.78
4	65	\$23.76	\$7.85	\$4.32	\$0.00	\$35.93
5	70	\$25.59	\$7.85	\$14.11	\$0.00	\$47.55
6	75	\$27.42	\$7.85	\$14.44	\$0.00	\$49.71
7	80	\$29.25	\$7.85	\$14.77	\$0.00	\$51.87
8	90	\$32.90	\$7.85	\$15.44	\$0.00	\$56.19

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

HOISTING ENGINEER/CRANES/GRADALLS	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
OPERATING ENGINEERS LOCAL 4						

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 14 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - OPERATING ENGINEERS - Local 4

Effective Date - 12/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$22.27	\$10.00	\$0.00	\$0.00	\$32.27
2	60	\$24.29	\$10.00	\$14.18	\$0.00	\$48.47
3	65	\$26.32	\$10.00	\$14.18	\$0.00	\$50.50
4	70	\$28.34	\$10.00	\$14.18	\$0.00	\$52.52
5	75	\$30.37	\$10.00	\$14.18	\$0.00	\$54.55
6	80	\$32.39	\$10.00	\$14.18	\$0.00	\$56.57
7	85	\$34.42	\$10.00	\$14.18	\$0.00	\$58.60
8	90	\$36.44	\$10.00	\$14.18	\$0.00	\$60.62

Notes:

Apprentice to Journeyworker Ratio:1:6

HVAC (DUCTWORK)	02/01/2014	\$42.76	\$9.82	\$19.74	\$2.17	\$74.49
SHEETMETAL WORKERS LOCAL 17 - A	08/01/2014	\$43.61	\$9.82	\$19.74	\$2.17	\$75.34
	02/01/2015	\$44.51	\$9.82	\$19.74	\$2.17	\$76.24
	08/01/2015	\$45.51	\$9.82	\$19.74	\$2.17	\$77.24
	02/01/2016	\$46.51	\$9.82	\$19.74	\$2.17	\$78.24
	08/01/2016	\$47.66	\$9.82	\$19.74	\$2.17	\$79.39
	02/01/2017	\$48.76	\$9.82	\$19.74	\$2.17	\$80.49
	08/01/2017	\$49.86	\$9.82	\$19.74	\$2.17	\$81.59
	02/01/2018	\$51.01	\$9.82	\$19.74	\$2.17	\$82.74

For apprentice rates see "Apprentice- SHEET METAL WORKER"

HVAC (ELECTRICAL CONTROLS)	09/01/2013	\$43.96	\$13.00	\$14.42	\$0.00	\$71.38
ELECTRICIANS LOCAL 103	03/01/2014	\$44.45	\$13.00	\$14.68	\$0.00	\$72.13
	09/01/2014	\$45.12	\$13.00	\$14.70	\$0.00	\$72.82
	03/01/2015	\$45.84	\$13.00	\$14.72	\$0.00	\$73.56
	09/01/2015	\$46.80	\$13.00	\$14.75	\$0.00	\$74.55
	03/01/2016	\$47.75	\$13.00	\$14.78	\$0.00	\$75.53

For apprentice rates see "Apprentice- ELECTRICIAN"

HVAC (TESTING AND BALANCING - AIR)	02/01/2014	\$42.76	\$9.82	\$19.74	\$2.17	\$74.49
SHEETMETAL WORKERS LOCAL 17 - A	08/01/2014	\$43.61	\$9.82	\$19.74	\$2.17	\$75.34
	02/01/2015	\$44.51	\$9.82	\$19.74	\$2.17	\$76.24
	08/01/2015	\$45.51	\$9.82	\$19.74	\$2.17	\$77.24
	02/01/2016	\$46.51	\$9.82	\$19.74	\$2.17	\$78.24
	08/01/2016	\$47.66	\$9.82	\$19.74	\$2.17	\$79.39
	02/01/2017	\$48.76	\$9.82	\$19.74	\$2.17	\$80.49
	08/01/2017	\$49.86	\$9.82	\$19.74	\$2.17	\$81.59
	02/01/2018	\$51.01	\$9.82	\$19.74	\$2.17	\$82.74

For apprentice rates see "Apprentice- SHEET METAL WORKER"

HVAC (TESTING AND BALANCING -WATER)	03/01/2013	\$49.34	\$8.75	\$14.39	\$0.00	\$72.48
PIPEFITTERS LOCAL 537						

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 15 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
HVAC MECHANIC PIPEFITTERS LOCAL 537	03/01/2013	\$49.34	\$8.75	\$14.39	\$0.00	\$72.48
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
HYDRAULIC DRILLS LABORERS - ZONE 1	12/01/2013	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	06/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	12/01/2014	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	06/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	12/01/2015	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	06/01/2016	\$37.85	\$7.30	\$12.70	\$0.00	\$57.85
	12/01/2016	\$38.85	\$7.30	\$12.70	\$0.00	\$58.85
For apprentice rates see "Apprentice- LABORER"						
INSULATOR (PIPES & TANKS) HEAT & FROST INSULATORS LOCAL 6 (BOSTON)	09/01/2013	\$42.11	\$10.95	\$12.10	\$0.00	\$65.16
	09/01/2014	\$44.11	\$10.95	\$12.10	\$0.00	\$67.16

Apprentice - ASBESTOS INSULATOR (Pipes & Tanks) - Local 6 Boston

Effective Date - 09/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.06	\$10.95	\$9.00	\$0.00	\$41.01
2	60	\$25.27	\$10.95	\$9.62	\$0.00	\$45.84
3	70	\$29.48	\$10.95	\$10.24	\$0.00	\$50.67
4	80	\$33.69	\$10.95	\$10.86	\$0.00	\$55.50

Effective Date - 09/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.06	\$10.95	\$9.00	\$0.00	\$42.01
2	60	\$26.47	\$10.95	\$9.62	\$0.00	\$47.04
3	70	\$30.88	\$10.95	\$10.24	\$0.00	\$52.07
4	80	\$35.29	\$10.95	\$10.86	\$0.00	\$57.10

Notes:

Steps are 1 year

Apprentice to Journeyworker Ratio:1:4

IRONWORKER/WELDER IRONWORKERS LOCAL 7 (BOSTON AREA)	09/16/2013	\$40.85	\$7.70	\$18.60	\$0.00	\$67.15
--	------------	---------	--------	---------	--------	---------

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - IRONWORKER - Local 7 Boston

Effective Date - 09/16/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$24.51	\$7.70	\$18.60	\$0.00	\$50.81
2	70	\$28.60	\$7.70	\$18.60	\$0.00	\$54.90
3	75	\$30.64	\$7.70	\$18.60	\$0.00	\$56.94
4	80	\$32.68	\$7.70	\$18.60	\$0.00	\$58.98
5	85	\$34.72	\$7.70	\$18.60	\$0.00	\$61.02
6	90	\$36.77	\$7.70	\$18.60	\$0.00	\$63.07

Notes:

** Structural 1:6; Ornamental 1:4

Apprentice to Journeyworker Ratio:**

JACKHAMMER & PAVING BREAKER OPERATOR	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
LABORERS - ZONE 1	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35

For apprentice rates see "Apprentice- LABORER"

LABORER	12/01/2013	\$33.35	\$7.30	\$12.70	\$0.00	\$53.35
LABORERS - ZONE 1	06/01/2014	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	12/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	06/01/2015	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	12/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	06/01/2016	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	12/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 17 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - LABORER - Zone 1

Effective Date - 12/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$20.01	\$7.30	\$12.70	\$0.00	\$40.01
2	70	\$23.35	\$7.30	\$12.70	\$0.00	\$43.35
3	80	\$26.68	\$7.30	\$12.70	\$0.00	\$46.68
4	90	\$30.02	\$7.30	\$12.70	\$0.00	\$50.02

Effective Date - 06/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$20.46	\$7.30	\$12.70	\$0.00	\$40.46
2	70	\$23.87	\$7.30	\$12.70	\$0.00	\$43.87
3	80	\$27.28	\$7.30	\$12.70	\$0.00	\$47.28
4	90	\$30.69	\$7.30	\$12.70	\$0.00	\$50.69

Notes:

Apprentice to Journeyworker Ratio:1:5

LABORER: CARPENTER TENDER	12/01/2013	\$33.35	\$7.30	\$12.70	\$0.00	\$53.35
LABORERS - ZONE 1	06/01/2014	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	12/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	06/01/2015	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	12/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	06/01/2016	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	12/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10

For apprentice rates see "Apprentice- LABORER"

LABORER: CEMENT FINISHER TENDER	12/01/2013	\$33.35	\$7.30	\$12.70	\$0.00	\$53.35
LABORERS - ZONE 1	06/01/2014	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	12/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	06/01/2015	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	12/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	06/01/2016	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	12/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10

For apprentice rates see "Apprentice- LABORER"

LABORER: HAZARDOUS WASTE/ASBESTOS REMOVER	12/01/2013	\$33.50	\$7.30	\$12.70	\$0.00	\$53.50
LABORERS - ZONE 1	06/01/2014	\$34.25	\$7.30	\$12.70	\$0.00	\$54.25
	12/01/2014	\$35.00	\$7.30	\$12.70	\$0.00	\$55.00
	06/01/2015	\$35.75	\$7.30	\$12.70	\$0.00	\$55.75
	12/01/2015	\$36.50	\$7.30	\$12.70	\$0.00	\$56.50

For apprentice rates see "Apprentice- LABORER"

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 18 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
LABORER: MASON TENDER <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
LABORER: MULTI-TRADE TENDER <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.35	\$7.30	\$12.70	\$0.00	\$53.35
	06/01/2014	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	12/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	06/01/2015	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	12/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	06/01/2016	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	12/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10
For apprentice rates see "Apprentice- LABORER"						
LABORER: TREE REMOVER <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.35	\$7.30	\$12.70	\$0.00	\$53.35
	06/01/2014	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	12/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	06/01/2015	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	12/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	06/01/2016	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	12/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10
This classification applies to the wholesale removal of standing trees including all associated trimming of branches and limbs, and applies to the removal of branches at locations not on or around utility lines. For apprentice rates see "Apprentice- LABORER"						
LASER BEAM OPERATOR <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
MARBLE & TILE FINISHERS <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2014	\$36.66	\$10.18	\$16.83	\$0.00	\$63.67
	08/01/2014	\$37.37	\$10.18	\$16.90	\$0.00	\$64.45
	02/01/2015	\$37.82	\$10.18	\$16.90	\$0.00	\$64.90
	08/01/2015	\$38.53	\$10.18	\$16.97	\$0.00	\$65.68
	02/01/2016	\$38.98	\$10.18	\$16.97	\$0.00	\$66.13
	08/01/2016	\$39.68	\$10.18	\$17.05	\$0.00	\$66.91
	02/01/2017	\$40.14	\$10.18	\$17.05	\$0.00	\$67.37

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - MARBLE & TILE FINISHER - Local 3 Marble & Tile

Effective Date - 02/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.33	\$10.18	\$16.83	\$0.00	\$45.34
2	60	\$22.00	\$10.18	\$16.83	\$0.00	\$49.01
3	70	\$25.66	\$10.18	\$16.83	\$0.00	\$52.67
4	80	\$29.33	\$10.18	\$16.83	\$0.00	\$56.34
5	90	\$32.99	\$10.18	\$16.83	\$0.00	\$60.00

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.69	\$10.18	\$16.90	\$0.00	\$45.77
2	60	\$22.42	\$10.18	\$16.90	\$0.00	\$49.50
3	70	\$26.16	\$10.18	\$16.90	\$0.00	\$53.24
4	80	\$29.90	\$10.18	\$16.90	\$0.00	\$56.98
5	90	\$33.63	\$10.18	\$16.90	\$0.00	\$60.71

Notes:

Apprentice to Journeyworker Ratio:1:3

MARBLE MASONS, TILELAYERS & TERRAZZO MECH	02/01/2014	\$48.10	\$10.18	\$18.15	\$0.00	\$76.43
BRICKLAYERS LOCAL 3 - MARBLE & TILE	08/01/2014	\$49.00	\$10.18	\$18.22	\$0.00	\$77.40
	02/01/2015	\$49.56	\$10.18	\$18.22	\$0.00	\$77.96
	08/01/2015	\$50.46	\$10.18	\$18.29	\$0.00	\$78.93
	02/01/2016	\$51.03	\$10.18	\$18.29	\$0.00	\$79.50
	08/01/2016	\$51.93	\$10.18	\$18.37	\$0.00	\$80.48
	02/01/2017	\$52.50	\$10.18	\$18.37	\$0.00	\$81.05

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 20 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - MARBLE-TILE-TERRAZZO MECHANIC - Local 3 Marble & Tile

Effective Date - 02/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.05	\$10.18	\$18.15	\$0.00	\$52.38
2	60	\$28.86	\$10.18	\$18.15	\$0.00	\$57.19
3	70	\$33.67	\$10.18	\$18.15	\$0.00	\$62.00
4	80	\$38.48	\$10.18	\$18.15	\$0.00	\$66.81
5	90	\$43.29	\$10.18	\$18.15	\$0.00	\$71.62

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.50	\$10.18	\$18.22	\$0.00	\$52.90
2	60	\$29.40	\$10.18	\$18.22	\$0.00	\$57.80
3	70	\$34.30	\$10.18	\$18.22	\$0.00	\$62.70
4	80	\$39.20	\$10.18	\$18.22	\$0.00	\$67.60
5	90	\$44.10	\$10.18	\$18.22	\$0.00	\$72.50

Notes:

Apprentice to Journeyworker Ratio:1:5

MECH. SWEEPER OPERATOR (ON CONST. SITES) OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
---	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MECHANICS MAINTENANCE OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
--	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MILLWRIGHT (Zone 1) MILLWRIGHTS LOCAL 1121 - Zone 1	10/01/2013	\$35.20	\$9.80	\$16.01	\$0.00	\$61.01
	04/01/2014	\$35.98	\$9.80	\$16.01	\$0.00	\$61.79
	10/01/2014	\$36.93	\$9.80	\$16.01	\$0.00	\$62.74
	04/01/2015	\$37.89	\$9.80	\$16.01	\$0.00	\$63.70

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 21 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - MILLWRIGHT - Local 1121 Zone 1

Effective Date - 10/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$19.36	\$9.80	\$4.40	\$0.00	\$33.56
2	65	\$22.88	\$9.80	\$13.21	\$0.00	\$45.89
3	75	\$26.40	\$9.80	\$14.01	\$0.00	\$50.21
4	85	\$29.92	\$9.80	\$14.81	\$0.00	\$54.53

Effective Date - 04/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$19.79	\$9.80	\$4.40	\$0.00	\$33.99
2	65	\$23.39	\$9.80	\$13.21	\$0.00	\$46.40
3	75	\$26.99	\$9.80	\$14.01	\$0.00	\$50.80
4	85	\$30.58	\$9.80	\$14.81	\$0.00	\$55.19

Notes:

Steps are 2,000 hours

Apprentice to Journeyworker Ratio:1:5

MORTAR MIXER	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
LABORERS - ZONE 1	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
OILER (OTHER THAN TRUCK CRANES,GRADALLS)	12/01/2013	\$20.96	\$10.00	\$14.18	\$0.00	\$45.14
OPERATING ENGINEERS LOCAL 4						
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
OILER (TRUCK CRANES, GRADALLS)	12/01/2013	\$24.43	\$10.00	\$14.18	\$0.00	\$48.61
OPERATING ENGINEERS LOCAL 4						
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
OTHER POWER DRIVEN EQUIPMENT - CLASS II	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
OPERATING ENGINEERS LOCAL 4						
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PAINTER (BRIDGES/TANKS)	01/01/2014	\$45.91	\$7.85	\$16.10	\$0.00	\$69.86
PAINTERS LOCAL 35 - ZONE 2	07/01/2014	\$46.76	\$7.85	\$16.10	\$0.00	\$70.71
	01/01/2015	\$47.66	\$7.85	\$16.10	\$0.00	\$71.61
	07/01/2015	\$48.56	\$7.85	\$16.10	\$0.00	\$72.51
	01/01/2016	\$49.51	\$7.85	\$16.10	\$0.00	\$73.46
	07/01/2016	\$50.46	\$7.85	\$16.10	\$0.00	\$74.41
	01/01/2017	\$51.41	\$7.85	\$16.10	\$0.00	\$75.36

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 22 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.96	\$7.85	\$0.00	\$0.00	\$30.81
2	55	\$25.25	\$7.85	\$3.66	\$0.00	\$36.76
3	60	\$27.55	\$7.85	\$3.99	\$0.00	\$39.39
4	65	\$29.84	\$7.85	\$4.32	\$0.00	\$42.01
5	70	\$32.14	\$7.85	\$14.11	\$0.00	\$54.10
6	75	\$34.43	\$7.85	\$14.44	\$0.00	\$56.72
7	80	\$36.73	\$7.85	\$14.77	\$0.00	\$59.35
8	90	\$41.32	\$7.85	\$15.44	\$0.00	\$64.61

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.38	\$7.85	\$0.00	\$0.00	\$31.23
2	55	\$25.72	\$7.85	\$3.66	\$0.00	\$37.23
3	60	\$28.06	\$7.85	\$3.99	\$0.00	\$39.90
4	65	\$30.39	\$7.85	\$4.32	\$0.00	\$42.56
5	70	\$32.73	\$7.85	\$14.11	\$0.00	\$54.69
6	75	\$35.07	\$7.85	\$14.44	\$0.00	\$57.36
7	80	\$37.41	\$7.85	\$14.77	\$0.00	\$60.03
8	90	\$42.08	\$7.85	\$15.44	\$0.00	\$65.37

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, NEW) *

* If 30% or more of surfaces to be painted are new construction,
NEW paint rate shall be used. PAINTERS LOCAL 35 - ZONE 2

01/01/2014	\$36.81	\$7.85	\$16.10	\$0.00	\$60.76
07/01/2014	\$37.66	\$7.85	\$16.10	\$0.00	\$61.61
01/01/2015	\$38.56	\$7.85	\$16.10	\$0.00	\$62.51
07/01/2015	\$39.46	\$7.85	\$16.10	\$0.00	\$63.41
01/01/2016	\$40.41	\$7.85	\$16.10	\$0.00	\$64.36
07/01/2016	\$41.36	\$7.85	\$16.10	\$0.00	\$65.31
01/01/2017	\$42.31	\$7.85	\$16.10	\$0.00	\$66.26

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 23 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 2 - Spray/Sandblast - New

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.41	\$7.85	\$0.00	\$0.00	\$26.26
2	55	\$20.25	\$7.85	\$3.66	\$0.00	\$31.76
3	60	\$22.09	\$7.85	\$3.99	\$0.00	\$33.93
4	65	\$23.93	\$7.85	\$4.32	\$0.00	\$36.10
5	70	\$25.77	\$7.85	\$14.11	\$0.00	\$47.73
6	75	\$27.61	\$7.85	\$14.44	\$0.00	\$49.90
7	80	\$29.45	\$7.85	\$14.77	\$0.00	\$52.07
8	90	\$33.13	\$7.85	\$15.44	\$0.00	\$56.42

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.83	\$7.85	\$0.00	\$0.00	\$26.68
2	55	\$20.71	\$7.85	\$3.66	\$0.00	\$32.22
3	60	\$22.60	\$7.85	\$3.99	\$0.00	\$34.44
4	65	\$24.48	\$7.85	\$4.32	\$0.00	\$36.65
5	70	\$26.36	\$7.85	\$14.11	\$0.00	\$48.32
6	75	\$28.25	\$7.85	\$14.44	\$0.00	\$50.54
7	80	\$30.13	\$7.85	\$14.77	\$0.00	\$52.75
8	90	\$33.89	\$7.85	\$15.44	\$0.00	\$57.18

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, REPAINT)
PAINTERS LOCAL 35 - ZONE 2

01/01/2014	\$34.87	\$7.85	\$16.10	\$0.00	\$58.82
07/01/2014	\$35.72	\$7.85	\$16.10	\$0.00	\$59.67
01/01/2015	\$36.62	\$7.85	\$16.10	\$0.00	\$60.57
07/01/2015	\$37.52	\$7.85	\$16.10	\$0.00	\$61.47
01/01/2016	\$38.47	\$7.85	\$16.10	\$0.00	\$62.42
07/01/2016	\$39.42	\$7.85	\$16.10	\$0.00	\$63.37
01/01/2017	\$40.37	\$7.85	\$16.10	\$0.00	\$64.32

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 24 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 2 - Spray/Sandblast - Repaint

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.44	\$7.85	\$0.00	\$0.00	\$25.29
2	55	\$19.18	\$7.85	\$3.66	\$0.00	\$30.69
3	60	\$20.92	\$7.85	\$3.99	\$0.00	\$32.76
4	65	\$22.67	\$7.85	\$4.32	\$0.00	\$34.84
5	70	\$24.41	\$7.85	\$14.11	\$0.00	\$46.37
6	75	\$26.15	\$7.85	\$14.44	\$0.00	\$48.44
7	80	\$27.90	\$7.85	\$14.77	\$0.00	\$50.52
8	90	\$31.38	\$7.85	\$15.44	\$0.00	\$54.67

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.86	\$7.85	\$0.00	\$0.00	\$25.71
2	55	\$19.65	\$7.85	\$3.66	\$0.00	\$31.16
3	60	\$21.43	\$7.85	\$3.99	\$0.00	\$33.27
4	65	\$23.22	\$7.85	\$4.32	\$0.00	\$35.39
5	70	\$25.00	\$7.85	\$14.11	\$0.00	\$46.96
6	75	\$26.79	\$7.85	\$14.44	\$0.00	\$49.08
7	80	\$28.58	\$7.85	\$14.77	\$0.00	\$51.20
8	90	\$32.15	\$7.85	\$15.44	\$0.00	\$55.44

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (TRAFFIC MARKINGS)	12/01/2013	\$33.35	\$7.30	\$12.70	\$0.00	\$53.35
LABORERS - ZONE 1	06/01/2014	\$34.10	\$7.30	\$12.70	\$0.00	\$54.10
	12/01/2014	\$34.85	\$7.30	\$12.70	\$0.00	\$54.85
	06/01/2015	\$35.60	\$7.30	\$12.70	\$0.00	\$55.60
	12/01/2015	\$36.35	\$7.30	\$12.70	\$0.00	\$56.35
	06/01/2016	\$37.10	\$7.30	\$12.70	\$0.00	\$57.10
	12/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10
For Apprentico rates see "Apprentice- LABORER"						
PAINTER / TAPER (BRUSH, NEW) *	01/01/2014	\$35.41	\$7.85	\$16.10	\$0.00	\$59.36
* If 30% or more of surfaces to be painted are new construction, NEW paint rate shall be used. PAINTERS LOCAL 35 - ZONE 2	07/01/2014	\$36.26	\$7.85	\$16.10	\$0.00	\$60.21
	01/01/2015	\$37.16	\$7.85	\$16.10	\$0.00	\$61.11
	07/01/2015	\$38.06	\$7.85	\$16.10	\$0.00	\$62.01
	01/01/2016	\$39.01	\$7.85	\$16.10	\$0.00	\$62.96
	07/01/2016	\$39.96	\$7.85	\$16.10	\$0.00	\$63.91
	01/01/2017	\$40.91	\$7.85	\$16.10	\$0.00	\$64.86

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 25 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PAINTER - Local 35 Zone 2 - BRUSH NEW

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.71	\$7.85	\$0.00	\$0.00	\$25.56
2	55	\$19.48	\$7.85	\$3.66	\$0.00	\$30.99
3	60	\$21.25	\$7.85	\$3.99	\$0.00	\$33.09
4	65	\$23.02	\$7.85	\$4.32	\$0.00	\$35.19
5	70	\$24.79	\$7.85	\$14.11	\$0.00	\$46.75
6	75	\$26.56	\$7.85	\$14.44	\$0.00	\$48.85
7	80	\$28.33	\$7.85	\$14.77	\$0.00	\$50.95
8	90	\$31.87	\$7.85	\$15.44	\$0.00	\$55.16

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$18.13	\$7.85	\$0.00	\$0.00	\$25.98
2	55	\$19.94	\$7.85	\$3.66	\$0.00	\$31.45
3	60	\$21.76	\$7.85	\$3.99	\$0.00	\$33.60
4	65	\$23.57	\$7.85	\$4.32	\$0.00	\$35.74
5	70	\$25.38	\$7.85	\$14.11	\$0.00	\$47.34
6	75	\$27.20	\$7.85	\$14.44	\$0.00	\$49.49
7	80	\$29.01	\$7.85	\$14.77	\$0.00	\$51.63
8	90	\$32.63	\$7.85	\$15.44	\$0.00	\$55.92

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER / TAPER (BRUSH, REPAINT)
PAINTERS LOCAL 35 - ZONE 2

01/01/2014	\$33.47	\$7.85	\$16.10	\$0.00	\$57.42
07/01/2014	\$34.32	\$7.85	\$16.10	\$0.00	\$58.27
01/01/2015	\$35.22	\$7.85	\$16.10	\$0.00	\$59.17
07/01/2015	\$36.12	\$7.85	\$16.10	\$0.00	\$60.07
01/01/2016	\$37.07	\$7.85	\$16.10	\$0.00	\$61.02
07/01/2016	\$38.02	\$7.85	\$16.10	\$0.00	\$61.97
01/01/2017	\$38.97	\$7.85	\$16.10	\$0.00	\$62.92

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 26 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 2 - BRUSH REPAINT

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$16.74	\$7.85	\$0.00	\$0.00	\$24.59
2	55	\$18.41	\$7.85	\$3.66	\$0.00	\$29.92
3	60	\$20.08	\$7.85	\$3.99	\$0.00	\$31.92
4	65	\$21.76	\$7.85	\$4.32	\$0.00	\$33.93
5	70	\$23.43	\$7.85	\$14.11	\$0.00	\$45.39
6	75	\$25.10	\$7.85	\$14.44	\$0.00	\$47.39
7	80	\$26.78	\$7.85	\$14.77	\$0.00	\$49.40
8	90	\$30.12	\$7.85	\$15.44	\$0.00	\$53.41

Effective Date - 07/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$17.16	\$7.85	\$0.00	\$0.00	\$25.01
2	55	\$18.88	\$7.85	\$3.66	\$0.00	\$30.39
3	60	\$20.59	\$7.85	\$3.99	\$0.00	\$32.43
4	65	\$22.31	\$7.85	\$4.32	\$0.00	\$34.48
5	70	\$24.02	\$7.85	\$14.11	\$0.00	\$45.98
6	75	\$25.74	\$7.85	\$14.44	\$0.00	\$48.03
7	80	\$27.46	\$7.85	\$14.77	\$0.00	\$50.08
8	90	\$30.89	\$7.85	\$15.44	\$0.00	\$54.18

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PANEL & PICKUP TRUCKS DRIVER	12/01/2013	\$31.88	\$9.41	\$8.80	\$0.00	\$50.09
TEAMSTERS JOINT COUNCIL NO. 10 ZONE A	06/01/2014	\$32.23	\$9.41	\$8.80	\$0.00	\$50.44
	08/01/2014	\$32.23	\$9.91	\$8.80	\$0.00	\$50.94
	12/01/2014	\$32.23	\$9.91	\$9.33	\$0.00	\$51.47
	06/01/2015	\$32.58	\$9.91	\$9.33	\$0.00	\$51.82
	08/01/2015	\$32.58	\$10.41	\$9.33	\$0.00	\$52.32
	12/01/2015	\$32.58	\$10.41	\$10.08	\$0.00	\$53.07
	06/01/2016	\$33.08	\$10.41	\$10.08	\$0.00	\$53.57
	08/01/2016	\$33.08	\$10.91	\$10.08	\$0.00	\$54.07
	12/01/2016	\$33.08	\$10.91	\$10.89	\$0.00	\$54.88
PIER AND DOCK CONSTRUCTOR (UNDERPINNING AND DECK)	08/01/2013	\$40.10	\$9.80	\$18.17	\$0.00	\$68.07
PILE DRIVER LOCAL 56 (ZONE 1)	08/01/2014	\$41.60	\$9.80	\$18.17	\$0.00	\$69.57
	08/01/2015	\$43.10	\$9.80	\$18.17	\$0.00	\$71.07
PILE DRIVER	08/01/2013	\$40.10	\$9.80	\$18.17	\$0.00	\$68.07
PILE DRIVER LOCAL 56 (ZONE 1)	08/01/2014	\$41.60	\$9.80	\$18.17	\$0.00	\$69.57
	08/01/2015	\$43.10	\$9.80	\$18.17	\$0.00	\$71.07

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 27 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - PILE DRIVER - Local 56 Zone 1

Effective Date - 08/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.05	\$9.80	\$18.17	\$0.00	\$48.02
2	60	\$24.06	\$9.80	\$18.17	\$0.00	\$52.03
3	70	\$28.07	\$9.80	\$18.17	\$0.00	\$56.04
4	75	\$30.08	\$9.80	\$18.17	\$0.00	\$58.05
5	80	\$32.08	\$9.80	\$18.17	\$0.00	\$60.05
6	80	\$32.08	\$9.80	\$18.17	\$0.00	\$60.05
7	90	\$36.09	\$9.80	\$18.17	\$0.00	\$64.06
8	90	\$36.09	\$9.80	\$18.17	\$0.00	\$64.06

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.80	\$9.80	\$18.17	\$0.00	\$48.77
2	60	\$24.96	\$9.80	\$18.17	\$0.00	\$52.93
3	70	\$29.12	\$9.80	\$18.17	\$0.00	\$57.09
4	75	\$31.20	\$9.80	\$18.17	\$0.00	\$59.17
5	80	\$33.28	\$9.80	\$18.17	\$0.00	\$61.25
6	80	\$33.28	\$9.80	\$18.17	\$0.00	\$61.25
7	90	\$37.44	\$9.80	\$18.17	\$0.00	\$65.41
8	90	\$37.44	\$9.80	\$18.17	\$0.00	\$65.41

Notes:

Apprentice to Journeyworker Ratio:1:3

PIPEFITTER & STEAMFITTER
PIPEFITTERS LOCAL 537

03/01/2013 \$49.34 \$8.75 \$14.39 \$0.00 \$72.48

Apprentice - PIPEFITTER - Local 537

Effective Date - 03/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.74	\$8.75	\$6.50	\$0.00	\$34.99
2	45	\$22.20	\$8.75	\$14.39	\$0.00	\$45.34
3	60	\$29.60	\$8.75	\$14.39	\$0.00	\$52.74
4	70	\$34.54	\$8.75	\$14.39	\$0.00	\$57.68
5	80	\$39.47	\$8.75	\$14.39	\$0.00	\$62.61

Notes:

** 1:3; 3:15; 1:10 thereafter / Steps are 1 yr.
Refrig/AC Mechanic **1:1;1:2;2:4;3:6;4:8;5:10;6:12;7:14;8:17;9:20;10:23(Max)

Apprentice to Journeyworker Ratio:**

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 28 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
PIPELAYER	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
LABORERS - ZONE 1	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35

For apprentice rates see "Apprentice- LABORER"

PLUMBERS & GASFITTERS	09/01/2013	\$49.06	\$9.82	\$14.04	\$0.00	\$72.92
PLUMBERS & GASFITTERS LOCAL 12	03/01/2014	\$50.06	\$9.82	\$14.04	\$0.00	\$73.92
	09/01/2014	\$51.06	\$9.82	\$14.04	\$0.00	\$74.92
	03/01/2015	\$52.06	\$9.82	\$14.04	\$0.00	\$75.92
	09/01/2015	\$53.06	\$9.82	\$14.04	\$0.00	\$76.92
	03/01/2016	\$54.21	\$9.82	\$14.04	\$0.00	\$78.07
	09/01/2016	\$55.26	\$9.82	\$14.04	\$0.00	\$79.12
	03/01/2017	\$56.26	\$9.82	\$14.04	\$0.00	\$80.12

Apprentice - PLUMBER/GASFITTER - Local 12

Effective Date - 09/01/2013		Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Step	percent					
1	35	\$17.17	\$9.82	\$5.26	\$0.00	\$32.25
2	40	\$19.62	\$9.82	\$5.92	\$0.00	\$35.36
3	55	\$26.98	\$9.82	\$7.95	\$0.00	\$44.75
4	65	\$31.89	\$9.82	\$9.30	\$0.00	\$51.01
5	75	\$36.80	\$9.82	\$10.65	\$0.00	\$57.27

Effective Date - 03/01/2014		Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Step	percent					
1	35	\$17.52	\$9.82	\$5.26	\$0.00	\$32.60
2	40	\$20.02	\$9.82	\$5.92	\$0.00	\$35.76
3	55	\$27.53	\$9.82	\$7.95	\$0.00	\$45.30
4	65	\$32.54	\$9.82	\$9.30	\$0.00	\$51.66
5	75	\$37.55	\$9.82	\$10.65	\$0.00	\$58.02

Notes:

** 1:2; 2:6; 3:10; 4:14; 5:19/Steps are 1 yr
Step4 with lic\$54.16 Step5 with lic\$60.40

Apprentice to Journeyworker Ratio:**

PNEUMATIC CONTROLS (TEMP.)	03/01/2013	\$49.34	\$8.75	\$14.39	\$0.00	\$72.48
PIPEFITTERS LOCAL 537						

For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
PNEUMATIC DRILL/TOOL OPERATOR <i>LABORERS - ZONE 1</i>	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
POWDERMAN & BLASTER <i>LABORERS - ZONE 1</i>	12/01/2013	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	06/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	12/01/2014	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	06/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	12/01/2015	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	06/01/2016	\$38.10	\$7.30	\$12.70	\$0.00	\$58.10
	12/01/2016	\$39.10	\$7.30	\$12.70	\$0.00	\$59.10
For apprentice rates see "Apprentice- LABORER"						
POWER SHOVEL/DERRICK/TRENCHING MACHINE <i>OPERATING ENGINEERS LOCAL 4</i>	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PUMP OPERATOR (CONCRETE) <i>OPERATING ENGINEERS LOCAL 4</i>	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PUMP OPERATOR (DEWATERING, OTHER) <i>OPERATING ENGINEERS LOCAL 4</i>	12/01/2013	\$28.11	\$10.00	\$14.18	\$0.00	\$52.29
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
READY-MIX CONCRETE DRIVER <i>TEAMSTERS LOCAL 25b</i>	05/01/2011	\$28.03	\$7.75	\$5.91	\$0.00	\$41.69
RECLAIMERS <i>OPERATING ENGINEERS LOCAL 4</i>	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
RESIDENTIAL WOOD FRAME (All Other Work) <i>CARPENTERS -ZONE 2 (Residential Wood)</i>	04/01/2011	\$24.24	\$8.67	\$15.51	\$0.00	\$48.42
RESIDENTIAL WOOD FRAME CARPENTER ** ** The Residential Wood Frame Carpenter classification applies only to the construction of new, wood frame residences that do not exceed four stories including the basement. <i>CARPENTERS -ZONE 2 (Residential Wood)</i> As of 9/1/09 Carpentry work on wood-frame residential WEATHERIZATION projects shall be paid the RESIDENTIAL WOOD FRAME CARPENTER rate.	05/01/2011	\$24.24	\$6.34	\$6.23	\$0.00	\$36.81

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - CARPENTER (Residential Wood Frame) - Zone 2

Effective Date - 05/01/2011

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$14.54	\$6.34	\$0.00	\$0.00	\$20.88
2	60	\$14.54	\$6.34	\$6.23	\$0.00	\$27.11
3	65	\$15.76	\$6.34	\$6.23	\$0.00	\$28.33
4	70	\$16.97	\$6.34	\$6.23	\$0.00	\$29.54
5	75	\$18.18	\$6.34	\$6.23	\$0.00	\$30.75
6	80	\$19.39	\$6.34	\$6.23	\$0.00	\$31.96
7	85	\$20.60	\$6.34	\$6.23	\$0.00	\$33.17
8	90	\$21.82	\$6.34	\$6.23	\$0.00	\$34.39

Notes:

Apprentice to Journeyworker Ratio:1:5

RIDE-ON MOTORIZED BUGGY OPERATOR	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
LABORERS - ZONE 1	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
For apprentice rates see "Apprentice- LABORER"						
ROLLER/SPREADER/MULCHING MACHINE	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
OPERATING ENGINEERS LOCAL 4						
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
ROOFER (Inc.Roofing Waterproofing &Roofing Damproofg)	02/01/2014	\$39.21	\$10.50	\$10.70	\$0.00	\$60.41
ROOFERS LOCAL 33	08/01/2014	\$40.11	\$10.50	\$10.70	\$0.00	\$61.31
	02/01/2015	\$41.01	\$10.50	\$10.70	\$0.00	\$62.21
	08/01/2015	\$41.91	\$10.50	\$10.70	\$0.00	\$63.11
	02/01/2016	\$42.81	\$10.50	\$10.70	\$0.00	\$64.01

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 31 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - ROOFER - Local 33

Effective Date - 02/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.61	\$10.50	\$3.38	\$0.00	\$33.49
2	60	\$23.53	\$10.50	\$10.70	\$0.00	\$44.73
3	65	\$25.49	\$10.50	\$10.70	\$0.00	\$46.69
4	75	\$29.41	\$10.50	\$10.70	\$0.00	\$50.61
5	85	\$33.33	\$10.50	\$10.70	\$0.00	\$54.53

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.06	\$10.50	\$3.38	\$0.00	\$33.94
2	60	\$24.07	\$10.50	\$10.70	\$0.00	\$45.27
3	65	\$26.07	\$10.50	\$10.70	\$0.00	\$47.27
4	75	\$30.08	\$10.50	\$10.70	\$0.00	\$51.28
5	85	\$34.09	\$10.50	\$10.70	\$0.00	\$55.29

Notes: ** 1:5, 2:6-10, the 1:10; Reroofing: 1:4, then 1:1
Step 1 is 2000 hrs.; Steps 2-5 are 1000 hrs.

Apprentice to Journeyworker Ratio:**

ROOFER SLATE / TILE / PRECAST CONCRETE	02/01/2014	\$39.46	\$10.50	\$10.70	\$0.00	\$60.66
ROOFERS LOCAL 33	08/01/2014	\$40.36	\$10.50	\$10.70	\$0.00	\$61.56
	02/01/2015	\$41.26	\$10.50	\$10.70	\$0.00	\$62.46
	08/01/2015	\$42.16	\$10.50	\$10.70	\$0.00	\$63.36
	02/01/2016	\$43.06	\$10.50	\$10.70	\$0.00	\$64.26

For apprentice rates see "Apprentice- ROOFER"

SHEETMETAL WORKER	02/01/2014	\$42.76	\$9.82	\$19.74	\$2.17	\$74.49
SHEETMETAL WORKERS LOCAL 17 - A	08/01/2014	\$43.61	\$9.82	\$19.74	\$2.17	\$75.34
	02/01/2015	\$44.51	\$9.82	\$19.74	\$2.17	\$76.24
	08/01/2015	\$45.51	\$9.82	\$19.74	\$2.17	\$77.24
	02/01/2016	\$46.51	\$9.82	\$19.74	\$2.17	\$78.24
	08/01/2016	\$47.66	\$9.82	\$19.74	\$2.17	\$79.39
	02/01/2017	\$48.76	\$9.82	\$19.74	\$2.17	\$80.49
	08/01/2017	\$49.86	\$9.82	\$19.74	\$2.17	\$81.59
	02/01/2018	\$51.01	\$9.82	\$19.74	\$2.17	\$82.74

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 32 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - SHEET METAL WORKER - Local 17-A

Effective Date - 02/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.10	\$9.82	\$4.28	\$0.00	\$31.20
2	40	\$17.10	\$9.82	\$4.28	\$0.00	\$31.20
3	45	\$19.24	\$9.82	\$8.70	\$1.13	\$38.89
4	45	\$19.24	\$9.82	\$8.70	\$1.13	\$38.89
5	50	\$21.38	\$9.82	\$9.49	\$1.22	\$41.91
6	50	\$21.38	\$9.82	\$9.74	\$1.23	\$42.17
7	60	\$25.66	\$9.82	\$11.05	\$1.40	\$47.93
8	65	\$27.79	\$9.82	\$11.84	\$1.48	\$50.93
9	75	\$32.07	\$9.82	\$13.41	\$1.66	\$56.96
10	85	\$36.35	\$9.82	\$14.48	\$1.82	\$62.47

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.44	\$9.82	\$4.28	\$0.00	\$31.54
2	40	\$17.44	\$9.82	\$4.28	\$0.00	\$31.54
3	45	\$19.62	\$9.82	\$8.70	\$1.13	\$39.27
4	45	\$19.62	\$9.82	\$8.70	\$1.13	\$39.27
5	50	\$21.81	\$9.82	\$9.49	\$1.22	\$42.34
6	50	\$21.81	\$9.82	\$9.74	\$1.23	\$42.60
7	60	\$26.17	\$9.82	\$11.05	\$1.40	\$48.44
8	65	\$28.35	\$9.82	\$11.84	\$1.48	\$51.49
9	75	\$32.71	\$9.82	\$13.41	\$1.66	\$57.60
10	85	\$37.07	\$9.82	\$14.48	\$1.82	\$63.19

Notes:

Steps are 6 mos.

Apprentice to Journeyworker Ratio:1:4

SIGN ERECTOR PAINTERS LOCAL 35 - ZONE 2	06/01/2013	\$25.81	\$7.07	\$7.05	\$0.00	\$39.93
--	------------	---------	--------	--------	--------	---------

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 33 of 40

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - *SIGN ERECTOR - Local 35 Zone 2*

Effective Date - 06/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$12.91	\$7.07	\$0.00	\$0.00	\$19.98
2	55	\$14.20	\$7.07	\$2.45	\$0.00	\$23.72
3	60	\$15.49	\$7.07	\$2.45	\$0.00	\$25.01
4	65	\$16.78	\$7.07	\$2.45	\$0.00	\$26.30
5	70	\$18.07	\$7.07	\$7.05	\$0.00	\$32.19
6	75	\$19.36	\$7.07	\$7.05	\$0.00	\$33.48
7	80	\$20.65	\$7.07	\$7.05	\$0.00	\$34.77
8	85	\$21.94	\$7.07	\$7.05	\$0.00	\$36.06
9	90	\$23.23	\$7.07	\$7.05	\$0.00	\$37.35

Notes:

Steps are 4 mos.

Apprentice to Journeyworker Ratio:1:1

SPECIALIZED EARTH MOVING EQUIP < 35 TONS
TEAMSTERS JOINT COUNCIL NO. 10 ZONE A

12/01/2013	\$32.34	\$9.41	\$8.80	\$0.00	\$50.55
06/01/2014	\$32.69	\$9.41	\$8.80	\$0.00	\$50.90
08/01/2014	\$32.69	\$9.91	\$8.80	\$0.00	\$51.40
12/01/2014	\$32.69	\$9.91	\$9.33	\$0.00	\$51.93
06/01/2015	\$33.04	\$9.91	\$9.33	\$0.00	\$52.28
08/01/2015	\$33.04	\$10.41	\$9.33	\$0.00	\$52.78
12/01/2015	\$33.04	\$10.41	\$10.08	\$0.00	\$53.53
06/01/2016	\$33.54	\$10.41	\$10.08	\$0.00	\$54.03
08/01/2016	\$33.54	\$10.91	\$10.08	\$0.00	\$54.53
12/01/2016	\$33.54	\$10.91	\$10.89	\$0.00	\$55.34

SPECIALIZED EARTH MOVING EQUIP > 35 TONS
TEAMSTERS JOINT COUNCIL NO. 10 ZONE A

12/01/2013	\$32.63	\$9.41	\$8.80	\$0.00	\$50.84
06/01/2014	\$32.98	\$9.41	\$8.80	\$0.00	\$51.19
08/01/2014	\$32.98	\$9.91	\$8.80	\$0.00	\$51.69
12/01/2014	\$32.98	\$9.91	\$9.33	\$0.00	\$52.22
06/01/2015	\$33.33	\$9.91	\$9.33	\$0.00	\$52.57
08/01/2015	\$33.33	\$10.41	\$9.33	\$0.00	\$53.07
12/01/2015	\$33.33	\$10.41	\$10.08	\$0.00	\$53.82
06/01/2016	\$33.83	\$10.41	\$10.08	\$0.00	\$54.32
08/01/2016	\$33.83	\$10.91	\$10.08	\$0.00	\$54.82
12/01/2016	\$33.83	\$10.91	\$10.89	\$0.00	\$55.63

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 34 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
SPRINKLER FITTER	01/01/2014	\$53.33	\$8.42	\$12.85	\$0.00	\$74.60
SPRINKLER FITTERS LOCAL 550 - (Section A) Zone 1	03/01/2014	\$54.58	\$8.42	\$12.85	\$0.00	\$75.85
	10/01/2014	\$55.73	\$8.42	\$12.85	\$0.00	\$77.00
	01/01/2015	\$55.73	\$8.42	\$13.00	\$0.00	\$77.15
	03/01/2015	\$56.73	\$8.42	\$13.00	\$0.00	\$78.15
	10/01/2015	\$57.88	\$8.42	\$13.00	\$0.00	\$79.30
	01/01/2016	\$57.88	\$8.67	\$13.15	\$0.00	\$79.70
	03/01/2016	\$58.88	\$8.67	\$13.15	\$0.00	\$80.70
	10/01/2016	\$60.03	\$8.67	\$13.15	\$0.00	\$81.85
	03/01/2017	\$61.03	\$8.67	\$13.15	\$0.00	\$82.85

Apprentice - SPRINKLER FITTER - Local 550 (Section A) Zone 1

Effective Date - 01/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	35	\$18.67	\$8.42	\$8.25	\$0.00	\$35.34
2	40	\$21.33	\$8.42	\$8.25	\$0.00	\$38.00
3	45	\$24.00	\$8.42	\$8.25	\$0.00	\$40.67
4	50	\$26.67	\$8.42	\$8.25	\$0.00	\$43.34
5	55	\$29.33	\$8.42	\$8.25	\$0.00	\$46.00
6	60	\$32.00	\$8.42	\$8.25	\$0.00	\$48.67
7	65	\$34.66	\$8.42	\$8.25	\$0.00	\$51.33
8	70	\$37.33	\$8.42	\$8.25	\$0.00	\$54.00
9	75	\$40.00	\$8.42	\$8.25	\$0.00	\$56.67
10	80	\$42.66	\$8.42	\$8.25	\$0.00	\$59.33

Effective Date - 03/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	35	\$19.10	\$8.42	\$8.25	\$0.00	\$35.77
2	40	\$21.83	\$8.42	\$8.25	\$0.00	\$38.50
3	45	\$24.56	\$8.42	\$8.25	\$0.00	\$41.23
4	50	\$27.29	\$8.42	\$8.25	\$0.00	\$43.96
5	55	\$30.02	\$8.42	\$8.25	\$0.00	\$46.69
6	60	\$32.75	\$8.42	\$8.25	\$0.00	\$49.42
7	65	\$35.48	\$8.42	\$8.25	\$0.00	\$52.15
8	70	\$38.21	\$8.42	\$8.25	\$0.00	\$54.88
9	75	\$40.94	\$8.42	\$8.25	\$0.00	\$57.61
10	80	\$43.66	\$8.42	\$8.25	\$0.00	\$60.33

Notes: Apprentice entered prior 9/30/10:
40/45/50/55/60/65/70/75/80/85
Steps are 850 hours

Apprentice to Journeyworker Ratio:1:3

STEAM BOILER OPERATOR	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
OPERATING ENGINEERS LOCAL 4						
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 35 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TAMPERS, SELF-PROPELLED OR TRACTOR DRAWN OPERATING ENGINEERS LOCAL 4	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TELECOMMUNICATION TECHNICIAN ELECTRICIANS LOCAL 103	09/01/2013	\$32.97	\$13.00	\$12.77	\$0.00	\$58.74
	03/01/2014	\$33.44	\$13.00	\$13.03	\$0.00	\$59.47
	09/01/2014	\$33.84	\$13.00	\$13.05	\$0.00	\$59.89
	03/01/2015	\$34.38	\$13.00	\$13.06	\$0.00	\$60.44
	09/01/2015	\$35.10	\$13.00	\$13.08	\$0.00	\$61.18
	03/01/2016	\$35.81	\$13.00	\$13.10	\$0.00	\$61.91

Apprentice - TELECOMMUNICATION TECHNICIAN - Local 103

Effective Date - 09/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$13.19	\$13.00	\$0.40	\$0.00	\$26.59
2	40	\$13.19	\$13.00	\$0.40	\$0.00	\$26.59
3	45	\$14.84	\$13.00	\$10.04	\$0.00	\$37.88
4	45	\$14.84	\$13.00	\$10.04	\$0.00	\$37.88
5	50	\$16.49	\$13.00	\$10.29	\$0.00	\$39.78
6	55	\$18.13	\$13.00	\$10.53	\$0.00	\$41.66
7	60	\$19.78	\$13.00	\$10.78	\$0.00	\$43.56
8	65	\$21.43	\$13.00	\$11.03	\$0.00	\$45.46
9	70	\$23.08	\$13.00	\$11.28	\$0.00	\$47.36
10	75	\$24.73	\$13.00	\$11.53	\$0.00	\$49.26

Effective Date - 03/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$13.38	\$13.00	\$0.40	\$0.00	\$26.78
2	40	\$13.38	\$13.00	\$0.40	\$0.00	\$26.78
3	45	\$15.05	\$13.00	\$10.29	\$0.00	\$38.34
4	45	\$15.05	\$13.00	\$10.29	\$0.00	\$38.34
5	50	\$16.72	\$13.00	\$10.54	\$0.00	\$40.26
6	55	\$18.39	\$13.00	\$10.79	\$0.00	\$42.18
7	60	\$20.06	\$13.00	\$11.04	\$0.00	\$44.10
8	65	\$21.74	\$13.00	\$11.29	\$0.00	\$46.03
9	70	\$23.41	\$13.00	\$11.54	\$0.00	\$47.95
10	75	\$25.08	\$13.00	\$11.79	\$0.00	\$49.87

Notes:

Apprentice to Journeyworker Ratio:1:1

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TERRAZZO FINISHERS <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2014	\$47.00	\$10.18	\$18.15	\$0.00	\$75.33
	08/01/2014	\$47.90	\$10.18	\$18.22	\$0.00	\$76.30
	02/01/2015	\$48.46	\$10.18	\$18.22	\$0.00	\$76.86
	08/01/2015	\$49.36	\$10.18	\$18.29	\$0.00	\$77.83
	02/01/2016	\$49.93	\$10.18	\$18.29	\$0.00	\$78.40
	08/01/2016	\$50.83	\$10.18	\$18.37	\$0.00	\$79.38
	02/01/2017	\$51.40	\$10.18	\$18.37	\$0.00	\$79.95

Apprentice - TERRAZZO FINISHER - Local 3 Marble & Tile

Effective Date - 02/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.50	\$10.18	\$18.15	\$0.00	\$51.83
2	60	\$28.20	\$10.18	\$18.15	\$0.00	\$56.53
3	70	\$32.90	\$10.18	\$18.15	\$0.00	\$61.23
4	80	\$37.60	\$10.18	\$18.15	\$0.00	\$65.93
5	90	\$42.30	\$10.18	\$18.15	\$0.00	\$70.63

Effective Date - 08/01/2014

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.95	\$10.18	\$18.22	\$0.00	\$52.35
2	60	\$28.74	\$10.18	\$18.22	\$0.00	\$57.14
3	70	\$33.53	\$10.18	\$18.22	\$0.00	\$61.93
4	80	\$38.32	\$10.18	\$18.22	\$0.00	\$66.72
5	90	\$43.11	\$10.18	\$18.22	\$0.00	\$71.51

Notes:

Apprentice to Journeyworker Ratio:1:3

TEST BORING DRILLER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2013	\$34.70	\$7.30	\$12.90	\$0.00	\$54.90
	06/01/2014	\$35.45	\$7.30	\$12.90	\$0.00	\$55.65
	12/01/2014	\$36.20	\$7.30	\$12.90	\$0.00	\$56.40
	06/01/2015	\$36.95	\$7.30	\$12.90	\$0.00	\$57.15
	12/01/2015	\$37.70	\$7.30	\$12.90	\$0.00	\$57.90
	06/01/2016	\$38.45	\$7.30	\$12.90	\$0.00	\$58.65
	12/01/2016	\$39.45	\$7.30	\$12.90	\$0.00	\$59.65

For apprentice rates see "Apprentice- LABORER"

TEST BORING DRILLER HELPER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2013	\$33.42	\$7.30	\$12.90	\$0.00	\$53.62
	06/01/2014	\$34.17	\$7.30	\$12.90	\$0.00	\$54.37
	12/01/2014	\$34.92	\$7.30	\$12.90	\$0.00	\$55.12
	06/01/2015	\$35.67	\$7.30	\$12.90	\$0.00	\$55.87
	12/01/2015	\$36.42	\$7.30	\$12.90	\$0.00	\$56.62
	06/01/2016	\$37.17	\$7.30	\$12.90	\$0.00	\$57.37
	12/01/2016	\$38.17	\$7.30	\$12.90	\$0.00	\$58.37

For apprentice rates see "Apprentice- LABORER"

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 37 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TEST BORING LABORER	12/01/2013	\$33.30	\$7.30	\$12.90	\$0.00	\$53.50
LABORERS - FOUNDATION AND MARINE	06/01/2014	\$34.05	\$7.30	\$12.90	\$0.00	\$54.25
	12/01/2014	\$34.80	\$7.30	\$12.90	\$0.00	\$55.00
	06/01/2015	\$35.55	\$7.30	\$12.90	\$0.00	\$55.75
	12/01/2015	\$36.30	\$7.30	\$12.90	\$0.00	\$56.50
	06/01/2016	\$37.05	\$7.30	\$12.90	\$0.00	\$57.25
	12/01/2016	\$38.05	\$7.30	\$12.90	\$0.00	\$58.25
For apprentice rates see "Apprentice- LABORER"						
TRACTORS/PORTABLE STEAM GENERATORS	12/01/2013	\$40.11	\$10.00	\$14.18	\$0.00	\$64.29
OPERATING ENGINEERS LOCAL 4						
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TRAILERS FOR EARTH MOVING EQUIPMENT	12/01/2013	\$32.92	\$9.41	\$8.80	\$0.00	\$51.13
TEAMSTERS JOINT COUNCIL NO. 10 ZONE A	06/01/2014	\$33.27	\$9.41	\$8.80	\$0.00	\$51.48
	08/01/2014	\$33.27	\$9.91	\$8.80	\$0.00	\$51.98
	12/01/2014	\$33.27	\$9.91	\$9.33	\$0.00	\$52.51
	06/01/2015	\$33.62	\$9.91	\$9.33	\$0.00	\$52.86
	08/01/2015	\$33.62	\$10.41	\$9.33	\$0.00	\$53.36
	12/01/2015	\$33.62	\$10.41	\$10.08	\$0.00	\$54.11
	06/01/2016	\$34.12	\$10.41	\$10.08	\$0.00	\$54.61
	08/01/2016	\$34.12	\$10.91	\$10.08	\$0.00	\$55.11
	12/01/2016	\$34.12	\$10.91	\$10.89	\$0.00	\$55.92
TUNNEL WORK - COMPRESSED AIR	12/01/2013	\$45.58	\$7.30	\$13.30	\$0.00	\$66.18
LABORERS (COMPRESSED AIR)	06/01/2014	\$46.33	\$7.30	\$13.30	\$0.00	\$66.93
	12/01/2014	\$47.08	\$7.30	\$13.30	\$0.00	\$67.68
	06/01/2015	\$47.83	\$7.30	\$13.30	\$0.00	\$68.43
	12/01/2015	\$48.58	\$7.30	\$13.30	\$0.00	\$69.18
	06/01/2016	\$49.33	\$7.30	\$13.30	\$0.00	\$69.93
	12/01/2016	\$50.33	\$7.30	\$13.30	\$0.00	\$70.93
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - COMPRESSED AIR (HAZ. WASTE)	12/01/2013	\$47.58	\$7.30	\$13.30	\$0.00	\$68.18
LABORERS (COMPRESSED AIR)	06/01/2014	\$48.33	\$7.30	\$13.30	\$0.00	\$68.93
	12/01/2014	\$49.08	\$7.30	\$13.30	\$0.00	\$69.68
	06/01/2015	\$49.83	\$7.30	\$13.30	\$0.00	\$70.43
	12/01/2015	\$50.58	\$7.30	\$13.30	\$0.00	\$71.18
	06/01/2016	\$51.33	\$7.30	\$13.30	\$0.00	\$71.93
	12/01/2016	\$52.33	\$7.30	\$13.30	\$0.00	\$72.93
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR	12/01/2013	\$37.65	\$7.30	\$13.30	\$0.00	\$58.25
LABORERS (FREE AIR TUNNEL)	06/01/2014	\$38.40	\$7.30	\$13.30	\$0.00	\$59.00
	12/01/2014	\$39.15	\$7.30	\$13.30	\$0.00	\$59.75
	06/01/2015	\$39.90	\$7.30	\$13.30	\$0.00	\$60.50
	12/01/2015	\$40.65	\$7.30	\$13.30	\$0.00	\$61.25
	06/01/2016	\$41.40	\$7.30	\$13.30	\$0.00	\$62.00
	12/01/2016	\$42.40	\$7.30	\$13.30	\$0.00	\$63.00
For apprentice rates see "Apprentice- LABORER"						

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 38 of 40

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TUNNEL WORK - FREE AIR (HAZ. WASTE) <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2013	\$39.65	\$7.30	\$13.30	\$0.00	\$60.25
	06/01/2014	\$40.40	\$7.30	\$13.30	\$0.00	\$61.00
	12/01/2014	\$41.15	\$7.30	\$13.30	\$0.00	\$61.75
	06/01/2015	\$41.90	\$7.30	\$13.30	\$0.00	\$62.50
	12/01/2015	\$42.65	\$7.30	\$13.30	\$0.00	\$63.25
	06/01/2016	\$43.40	\$7.30	\$13.30	\$0.00	\$64.00
	12/01/2016	\$44.40	\$7.30	\$13.30	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						
VAC-HAUL <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE A</i>	12/01/2013	\$32.34	\$9.41	\$8.80	\$0.00	\$50.55
	06/01/2014	\$32.69	\$9.41	\$8.80	\$0.00	\$50.90
	08/01/2014	\$32.69	\$9.91	\$8.80	\$0.00	\$51.40
	12/01/2014	\$32.69	\$9.91	\$9.33	\$0.00	\$51.93
	06/01/2015	\$33.04	\$9.91	\$9.33	\$0.00	\$52.28
	08/01/2015	\$33.04	\$10.41	\$9.33	\$0.00	\$52.78
	12/01/2015	\$33.04	\$10.41	\$10.08	\$0.00	\$53.53
	06/01/2016	\$33.54	\$10.41	\$10.08	\$0.00	\$54.03
	08/01/2016	\$33.54	\$10.91	\$10.08	\$0.00	\$54.53
WAGON DRILL OPERATOR <i>LABORERS - ZONE 1</i>	12/01/2016	\$33.54	\$10.91	\$10.89	\$0.00	\$55.34
	12/01/2013	\$33.60	\$7.30	\$12.70	\$0.00	\$53.60
	06/01/2014	\$34.35	\$7.30	\$12.70	\$0.00	\$54.35
	12/01/2014	\$35.10	\$7.30	\$12.70	\$0.00	\$55.10
	06/01/2015	\$35.85	\$7.30	\$12.70	\$0.00	\$55.85
	12/01/2015	\$36.60	\$7.30	\$12.70	\$0.00	\$56.60
	06/01/2016	\$37.35	\$7.30	\$12.70	\$0.00	\$57.35
WASTE WATER PUMP OPERATOR <i>OPERATING ENGINEERS LOCAL 4</i>	12/01/2016	\$38.35	\$7.30	\$12.70	\$0.00	\$58.35
	For apprentice rates see "Apprentice- LABORER"					
	12/01/2013	\$40.49	\$10.00	\$14.18	\$0.00	\$64.67
	For apprentice rates see "Apprentice- OPERATING ENGINEERS"					
WATER METER INSTALLER <i>PLUMBERS & GASFITTERS LOCAL 12</i>	09/01/2013	\$49.06	\$9.82	\$14.04	\$0.00	\$72.92
	03/01/2014	\$50.06	\$9.82	\$14.04	\$0.00	\$73.92
	09/01/2014	\$51.06	\$9.82	\$14.04	\$0.00	\$74.92
	03/01/2015	\$52.06	\$9.82	\$14.04	\$0.00	\$75.92
	09/01/2015	\$53.06	\$9.82	\$14.04	\$0.00	\$76.92
	03/01/2016	\$54.21	\$9.82	\$14.04	\$0.00	\$78.07
	09/01/2016	\$55.26	\$9.82	\$14.04	\$0.00	\$79.12
	03/01/2017	\$56.26	\$9.82	\$14.04	\$0.00	\$80.12
For apprentice rates see "Apprentice- PLUMBER/PIPEFITTER" or "PLUMBER/GASFITTER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Additional Apprentice Information:

Minimum wage rates for apprentices employed on public works projects are listed above as a percentage of the pre-determined hourly wage rate established by the Commissioner under the provisions of the M.G.L. c. 149, ss. 26-27D. Apprentice ratios are established by the Division of Apprenticeship Training pursuant to M.G.L. c. 23, ss. 11E-11L.

All apprentices must be registered with the Division of Apprenticeship Training in accordance with M.G.L. c. 23, ss. 11E-11L.

All steps are six months (1000 hours) unless otherwise specified.

* Ratios are expressed in allowable number of apprentices to journeymen or fraction thereof.

** Multiple ratios are listed in the comment field.


*** APP to JM; 1:1, 2:2, 2:3, 3:4, 4:4, 4:5, 4:6, 5:7, 6:7, 6:8, 6:9, 7:10, 8:10, 8:11, 8:12, 9:13, 10:13, 10:14, etc.

**** APP to JM; 1:1, 1:2, 2:3, 2:4, 3:5, 4:6, 4:7, 5:8, 6:9, 6:10, 7:11, 8:12, 8:13, 9:14, 10:15, 10:16, etc.

Issue Date: 02/12/2014

Wage Request Number: 20140212-036

Page 40 of 40



THE COMMONWEALTH OF MASSACHUSETTS
DEPARTMENT OF LABOR
DIVISION OF OCCUPATIONAL SAFETY
PREVAILING WAGE PROGRAM
www.mass.gov/dos/pw

NOTICE: TO AWARDING AUTHORITIES AND CONTRACTORS

ISSUED: SEPTEMBER 1, 2006

DRIVERS WHO HAUL BITUMINOUS CONCRETE (ASPHALT)

The Massachusetts Supreme Judicial Court recently affirmed that drivers who haul bituminous concrete to public construction projects are not covered by the Prevailing Wage Law while off-site, including time spent over-the-road and picking-up materials. These drivers are covered by the Prevailing Wage Law only while on-site at the public construction project.

In Teamsters Joint Council No. 10 v. Department of Labor, et al., 447 Mass. 100 (2006), the SJC upheld a 2001 administrative decision limiting the applicability of prevailing wage rates to the time bituminous drivers spend at the public construction site. This most recent decision of the SJC followed a 1989 ruling that had upheld an earlier Department of Labor (and Industries') policy that had deemed this category of drivers to be "teamsters" under the Law and, therefore, entitled to prevailing wage rates. See Construction Industries of Massachusetts v. Commissioner of Labor and Industries, 406 Mass. 162 (1989). However, the earlier court case had left open the question of whether this entitled these bituminous drivers to prevailing wage rates for their over-the-road time as well as their on-site time. This most recent decision has now answered that question.

All of the requirements of the Prevailing Wage Law, including certified weekly payroll requirements, apply to bituminous drivers for all time spent at the public construction site.

DRIVERS WHO HAUL READY-MIX CONCRETE (CEMENT)

Drivers who haul ready-mix concrete to public construction projects are not covered by the Prevailing Wage Law while off-site, including time spent over-the-road and picking-up materials. These drivers are covered by the Prevailing Wage Law while on-site at the public construction project. This applicability determination was established by a 2001 administrative decision of the Department of Labor's Division of Occupational Safety.

All of the requirements of the Prevailing Wage Law, including certified weekly payroll requirements, apply to ready-mix drivers for all time spent at the public construction site.

Please feel free to contact the Division of Occupational Safety at 617-626-6953 if you have any questions. Questions about enforcement of the Prevailing Wage Law may be directed to the Attorney General's Fair Labor and Business Practices Division at 617-727-3465

The Massachusetts Prevailing Wage Law

M.G.L. ch. 149, §§ 26 – 27

NOTICE TO AWARDING AUTHORITIES

- 'The enclosed wage schedule applies only to the specific project listed at the top and will be updated for any public construction project lasting longer than one (1) year.
- 'You should request an updated wage schedule from the Division of Occupational Safety if you have not opened bids or selected a contractor within 90 days of the date of issuance of the enclosed wage schedule.
- 'The wage schedule shall be incorporated in any advertisement or call for bids for the project for which it has been issued.
- 'Once a contractor has been selected by the awarding authority, the wage schedule shall be made a part of the contract for that project.

NOTICE TO CONTRACTORS

- The enclosed wage schedule, and any updated schedule, must be posted in a conspicuous place at the work site during the life of the project.
- The wages listed on the enclosed wage schedule must be paid to employees on public works projects regardless of whether they are employed by the prime contractor, a filed sub-bidder, or any sub-contractor.
- The enclosed wage schedule applies to all phases of the project including the final clean-up. Contractors whose only role is to perform final clean-up must pay their employees according to this wage schedule.
- All apprentices must be registered with the Massachusetts Division of Apprentice Training in order to be paid at the reduced apprentice rates. If a worker is not registered with the Division of Apprentice Training, they must be paid the “total rate” listed on the wage schedule regardless of experience or skill level. For further information, please call (617) 727-3486 or write to the Division of Apprentice Training, 399 Washington Street, 4th Floor, Boston, MA 02108

WEEKLY PAYROLL RECORDS REPORT & STATEMENT OF COMPLIANCE

In accordance with Massachusetts General Law c149, §27B, a true and accurate record must be kept of all persons employed on the public works project for which the enclosed rates have been provided. A Payroll Form has been printed on the reverse of this page and includes all the information required to be kept by law. Every contractor or subcontractor is required to keep these records and preserve them for a period of three years from the date of completion of the contract.

In addition, every contractor and subcontractor is required to submit a copy of their weekly payroll records to the awarding authority. This is required to be done on a weekly basis. Once collected, the awarding authority is also required to preserve those records for three years.

In addition, each such contractor, subcontractor or public body shall furnish to the Department of Labor & Workforce Development/Division of Occupational Safety within fifteen days after completion of its portion of the work a statement, executed by the contractor, subcontractor or public body who supervises the payment of wages, in the following form:

STATEMENT OF COMPLIANCE

_____, 2014

I, _____,
(Name of signatory party) (Title)

do hereby state:

That I pay or supervise the payment of the persons employed by
_____ on the _____

(Contractor, subcontractor or public body) (Building or project)

and that all mechanics and apprentices, teamsters, chauffeurs and laborers employed on said project have been paid in accordance with wages determined under the provisions of sections twenty-six and twenty-seven of chapter one hundred and forty nine of the General Laws.

Signature _____

Title _____

DIVISION OF OCCUPATIONAL SAFETY, 399 WASHINGTON STREET, 5TH FL., BOSTON, MA. 02108

CITY OF NEWTON

SUMMARY OF WORK AND SPECIFIC REQUIREMENTS OF THE CONTRACT FOR PUBLIC WORKS CONSTRUCTION

A. SUMMARY OF WORK

1.

The work under this contract is for the removal and immediate off-site disposal of 1-1/2" to 2" of bituminous concrete by cold-planing methods. The work shall be performed at multiple municipal roadway locations situated throughout the City of Newton yielding a collective total surface area of approximately ninety three thousand (93,000) square yards [*].

***[Notice #1:** The quantities represented in this Invitation For Bid are dependent on Mass D.O.T. Chapter 90 funding. These monies are traditionally allotted, and subsequently apportioned by the City of Newton, on or about April 1 of each calendar year. **Therefore the quantities listed in this Invitation For Bid may be revised at the time of the bid award.**

***[Notice #2:** The work under this contract is to be performed in conjunction with a separately issued paving contract and an in-house DPW site preparation program, therefore the scheduling of this work shall be at the discretion of the Engineer. The intent is to ensure that the work under this contract is performed immediately before the aforementioned paving process. The successful bidder must be ready, willing and able to accommodate the City of Newton in the scheduling and/or coordination of this work.

2. All other work described in the Project Manual and/or shown on the Plan(s) unless specifically indicated as not to be done.

B. In addition the work under the contract includes:

1. Work outside the Project Site as called for in the Project Manual and/or Plan(s) and as required for the performance of the work.
2. The restoration of any items damaged or destroyed by encroaching upon areas outside the Project Site.
3. All labor, materials, tools, and equipment necessary to do all the work required for the completion of each item as specified, which shall limited not only to the exact intent mentioned, but shall include incidental work necessary or customarily performed for the completion of that item.
4. All items not specifically mentioned or noted in the Project Manual and/or Plan(s), but which are obviously necessary to make a complete working installation.

C. The Proposed Contract Price shall be complete costs, including overhead, profit, insurance, transportation, and all other costs connected with, or incidental to the work described.

II. TIME FOR COMPLETION AND LIQUIDATED DAMAGES

A. Upon notification the Contractor shall commence the work specified in the Project Manual as directed by the City. The work shall proceed in a continuous uninterrupted fashion with adequately staffed crews, in a satisfactory manner, which will assure that the work is completed in a timely manner to the satisfaction of the City.

- B. The time for substantial completion pursuant to Article 2 of the Contract :

NOTICE: * TIME IS OF THE ESSENCE *

Within five (5) business days of the Notice Of Award the Contractor shall submit to the Purchasing Department:

- **A signed contract.**
- **A Certificate of Insurance (naming the City as an additional insured)**
- **A Labor and Materials Payment Bond in the amount of 50% of the contract total.**

Anticipated start date is April 1, 2014. Time for completion is one hundred sixty (160) calendar days from the Notice To Proceed. This work is to be performed in conjunction with a separately issued paving contract. The successful bidder must be able to accommodate the City of Newton in the scheduling and/or coordination of this work.

Time is of the essence for the completion of this contract. If the Contractor fails to achieve substantial or final completion of the Work within the time required by the contract, and unless an extension of time is granted, the Contractor shall pay to the City as liquidated damages, the applicable amount specified in Article 6A of the General Conditions for each day of delay. If different completion dates are specified in the Contract for separate parts or stages of the work, the amount of liquidated damages shall be assessed on those parts or stages which are delayed. To the extent that the Contractor's delay or nonperformance is excused under another section in this Contract, liquidated damages shall not be due the City. The Contractor remains liable for damages caused other than by delay.

III. INSURANCE REQUIREMENTS

- A. The Contractor shall carry and maintain until acceptance of the work such Workmen's Compensation, Automobile Liability, Public Liability, Contingent Public Liability, Property Damage and Contingent Property Damage Insurance, each including blasting coverage, as shall protect him and any sub-contractor performing work covered by this contract from all claims and liability for damages for personal injury, including accidental death, and for property damage which may arise from operations under this contract, whether such operations be by himself or by any sub-contractor or by any one directly or indirectly employed by either of them.
- B. The City shall be named as an additional insured on such policy.
- C. The amounts of such insurance shall be as follows:
1. Workmen's Compensation Insurance as required by Massachusetts General Law.
 2. Automobile Liability Insurance on all vehicles owned or hired for a.) Bodily Injury in an amount not less than \$500,000.00 for each occurrence, and not less than \$1,000,000.00 aggregate; b.) Property Damage in an amount not less than \$300,000.00 each occurrence, and not less than \$500,000.00 aggregate.
 3. Public Liability Insurance and Contingent Public Liability Insurance in an amount not less than \$500,000.00 for injuries, including accidental death to any one person, and subject to the same limit for each person, in an amount not less than \$1,000,000.00 on account of one accident.

4. Property Damage Insurance and Contingent Property Damage Insurance in an amount not less than \$300,000.00 on account of one accident, and in an amount of not less than \$500,000.00 on account of all accidents.
 5. General Liability Insurance shall include Contractual Liability Insurance.
- D. Before any work is started, the successful bidder shall be required to file with the Chief Procurement Officer certificates of insurance coverage as detailed above, with policy numbers and dates of expiration.
- E. The Contractor shall indemnify, hold harmless and defend the City and its departments, officers, employees, servants, and agents from and against all actions, causes of actions, claims, demands, damages, costs, loss of services, expenses and compensation, including attorney's fees and interest arising out of or resulting directly or indirectly from the services rendered pursuant to this Contract, provided that any such action, cause of action, claim, demand, damage, cost, loss of service, expense, compensation (1) in any way grows out of bodily injury, sickness, disease or death, or to injury to or destruction of tangible property, which (2) is caused in whole or in part by any act or omission of the Contractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by a party indemnified hereunder.

END OF SECTION

CITY OF NEWTON

GENERAL CONDITIONS OF THE CONTRACT

FOR PUBLIC WORKS CONSTRUCTION

ARTICLE 1

(DELETED)

ARTICLE 2

Definitions

The word "Commissioner" shall mean the official duly authorized to act for the City of Newton in the execution of the work of this contract, acting directly or through properly authorized agents.

The word "Engineer," or "City Engineer," shall mean the City Engineer of the City of Newton, acting directly or through properly authorized agents, such agents acting within the scope of the particular duties entrusted to them.

The word "Contractor" shall mean the party or parties contracting to perform the work covered by this contract or his, or their, legal representatives, successors or assigns.

The word "Plan" shall mean plans referred to and included in the Project Manual for this contract. The word "City" shall mean the City of Newton.

ARTICLE 3

Plans, Drawings, Profiles

1. The work shall be done in accordance with plans referred to in Article 1 and such further working and detail plans, drawings and profiles as may be furnished from time to time by the Engineer. All said plans, general and detail, are to be deemed a part of this contract, and the said plans, specifications and contract are to be considered together, so that any work mentioned in the contract, though not shown on the plans, and any work shown on the plans though not mentioned in the contract, is to be executed by the Contractor as a part of this contract. Figured dimensions are to prevail over scale. All things which in the opinion of the Engineer may fairly be inferred from the contract, plans and specifications, are to be executed by the Contractor as a part of the contract; and the Engineer shall be sole judge as to whether detail plans, drawings and profiles conform to the general plans and the contract.

Discrepancy in Plans

2. The Contractor shall carefully examine all said plans, profiles, drawings, specifications and orders; all figures, dimensions, lines, marks and scales thereof, and all directions of the Commissioner and the Engineer relating to the work, and conform to those in relation to which there is no doubt or discrepancy, but at once submit all cases of doubt or discrepancy to the Engineer for adjustment. Anything done on any part of the work for which special information or drawing should be procured, unless done in accordance with such information or drawing, or anything done in relation to which there is doubt or discrepancy, except in accordance with the adjustment thereof, or done in violation of law or public authority, is to be redone if the Commissioner shall so direct.

ARTICLE 4

Inspection

1. The Contractor in carrying on the contract shall conform to all determinations and directions of the Engineer relating to the proper interpretation of the plans, specifications, profiles or drawings, the fitness of persons employed on the work or the number thereof, or the suitability, amount, quality, and value of anything done or any materials used, and the Contractor shall permit the Commissioner and the Engineer and persons designated by them to enter upon the work and inspect the same at all times and in all places, and shall provide safe and convenient facilities for making such entry and inspection.

ARTICLE 5

Change in Plans and Work

1. The City, acting through the Commissioner and upon his written order only, from time to time given to the Contractor or his foreman, may change, increase or take away any part of the work, or change the specifications, plans, drawings, form or materials thereof. Any deduction or addition thereto is to be allowed, or paid for at a price to be determined, within not more than 15 days of the completion of the change, by the City Engineer acting in the same capacity as an architect in a building contract as between owner and contractor. Any demand for addition or deduction must be made in writing to the City Engineer within seven (7) days of the time change was ordered.

ARTICLE 6

Time and Manner of Doing the work - Beginning and Completion

1. The Contractor shall begin work upon receipt of written Notice to Proceed. Once begun the work shall be carried out in a continuous and uninterrupted fashion with sufficient workforce and resources to assure completion by the date for completion established by the Contract Documents.

2. The Contractor shall carry on the work in accordance with the requirements of law and of all other public authorities, and to the satisfaction of the Commissioner; he shall give all notices, take out all permits, pay all charges and fees, give personal supervision to the work and keep thereon a competent foreman and sufficient employees, skilled in the several parts which are given them to do.

Maintenance of Travel

3. The Contractor shall conduct his work so as to interfere as little as possible with public travel, and shall give property owners proper means of access to their property where existing access has been cut off by the work. The Contractor shall keep the streets open for through travel except where, in the opinion of the Commissioner, it is necessary to close the street. The continuous length of the street occupied for the work shall be kept as short as possible, and no part of the work shall be unnecessarily delayed. Wherever the Commissioner shall direct, trenches shall be bridged by the Contractor in a proper and secure manner so as not to interrupt travel. Free access shall be maintained at all times to all water gates, gas gates, and fire hydrants.

Abandonment of Work by Contractor

4. In the event the City Engineer certifies to the Commissioner that the work is not being so carried forward or if the Contractor at any time is not carrying on the work to the satisfaction of the Commissioner, or is not observing any of the provisions of the contract, or has abandoned the work, or become insolvent or assigned his property, the City, acting by the Commissioner and at his discretion, may, with or without notice to the Contractor, or advertising for doing the work, and by contract, day labor or otherwise, do any part of the work which the Contractor has failed to do or replace any part not done to the satisfaction of the Commissioner, or take possession of the work and complete the same, and in doing so may use any implements, machinery or materials on or about the work which are the property of the Contractor, charging the Contractor any excess cost for completing the work, which excess cost the Contractor agrees to pay.

ARTICLE 6A

Liquidated Damages

1. In case the work embraced in the contract shall not have been completed by the date stipulated therein, the Contractor shall pay to the City of Newton as liquidated damages a designated sum per calendar day for the entire period of overrun in accordance with the following Schedule of Deductions, and in addition, the Contractor shall pay without reimbursement the entire cost of all traffic officers, railroad flagmen, inspectors, or other personnel the City Engineer and/or the Chief Engineer of the railroad determines to be necessary during the period of overrun of time.

SCHEDULE OF DEDUCTIONS

Daily Charge
Per Calendar Day

\$500.00

2. Whatever sum of money may become due and payable to the City of Newton by the Contractor under this Article may be retained out of money belonging to the Contractor in the hands and possession of the City of Newton. It is agreed that this Article shall be construed and treated by the parties to the contract not as imposing a penalty upon said Contractor for failing fully to complete said work as agreed on or before the time specified in the proposal, but as liquidated damages to compensate said City of Newton for all additional costs incurred by it because of the failure of the Contractor fully to complete said work on or before the date of completion specified in the proposal.

ARTICLE 6B

Delays and Extensions of Time

1. If the Contractor is delayed at any time in the progress of the work by an act or neglect of the City, or by changes in the work ordered by the City, or by unseasonably inclement weather, or by other causes deemed by the City Engineer to be beyond the Contractor's control, and which the City Engineer determines may justify delay, then the time for completion may be extended for such reasonable time as the City Engineer may determine.

2. No such extension of time will be allowed unless the Contractor submits a written request for an extension to the City Engineer no later than 10 calendar days of the start of the occurrence or event giving rise thereto. Each such request must describe the occurrence or event and specify the manner and extent that such occurrence or event is causing or has caused a delay in the work. The City Engineer shall promptly investigate each request and make his written determination to the Commissioner and the Contractor within 10 days after receipt of the request. In his determination the City Engineer may either grant, deny, or modify the length of the requested extension.

3. If the City Engineer's determination so warrants, the Commissioner shall authorize a written Change Order to the Contract extending the time for completion. No extension of time shall be deemed as granted until said Change Order has been duly executed by the parties.

4. Change Orders which may be executed by the City and the Contractor in connection with additions, extra labor and/or extra materials shall not be considered as allowing extensions of the time for completion unless the change order expressly specifies that additional time is allowed in connection with the work under the change order. Once a Change Order has been executed by the parties, any request by the Contractor for an extension of time based solely on the fact that additions, extra labor and/or extra materials are required by the Change Order will be denied by the City Engineer.

5. Permitting the Contractor to continue and finish the work or any part of it after the times fixed for its completion, or after the date to which the time for completion may have been extended, shall in no way operate as a waiver on the part of the City of Newton of any of its rights under the contract. The Contractor remains liable for damages caused other than by delay.

ARTICLE 7

Lines and Grades

1. The Contractor shall retain a Registered Land Surveyor who shall furnish such boards and stakes and cause to be placed thereon, such lines, marks and directions relating to the work as the Commissioner or City Engineer shall from time to time direct.

ARTICLE 8

Public Service Pipes and Conduits

1. The Contractor shall maintain such pipes or conduits of public service corporations or of the City as are across or within the lines of the work until such time as said public service corporations or the City assume the maintenance or removal of said pipes or conduits. The Commissioner will notify such public service corporations to that effect on the existence of such obstructions to the work being brought to his notice by the Contractor. The City will relocate either

temporarily or permanently all water mains and water service pipes, or hydrants, and drains or sewers which may interfere with the work contemplated in this contract. (This clause is not to be construed as applying to such pipes as may be readily supported and protected during the progress of the work.) The cost of shutting off and turning on water in water mains during blasting shall be assumed by the City.

Protection of Existing Structures

2. All existing gas pipes, water pipes, sewers, drains, conduits, or other structures which are uncovered by the excavation shall be carefully supported and protected from injury by the Contractor, and, in case of injury, they shall be restored by him, without compensation therefor, to as good condition as that in which they were found, and shall be kept in repair until 6 months after the completion of the work. The Contractor shall provide suitable temporary channels for water at all water courses. Wherever the work passes under or adjacent to street railway tracks, the Contractor shall make all necessary arrangements with the railway company for doing any work which may affect the property of the company or interfere with the operating of the railway, and he shall be liable for any damage that may be caused by any act, omission or neglect on his part, and shall pay all expenses of every kind incidental to this work.

Changing the Location of Existing Structures

3. Whenever it becomes necessary to change the location of any water or gas pipes, sewers, drains, conduits or other structures not otherwise provided for in these specifications, the Contractor shall do the whole or such portions of the work of making such changes as the Commissioner may require, and shall receive in payment therefor the reasonable cost of the work done as determined by the Commissioner plus 15 per cent of such cost. In estimating such cost, no allowance shall be made to the Contractor for the use of tools not especially provided for this work, for general superintendence, or for any overhead expenses except liability insurance.

ARTICLE 9

Co-operation with Other Contractors

1. The Contractor shall conduct the work in such manner as not to interfere with other work being done by the City, by contract or otherwise, and if deemed necessary by the Commissioner, the work under this contract shall conform to the progress of said other work; shall co-operate with other contractors or employees who may be doing work for the City, and with public service corporations affected by the work, in arranging for storage places, connections, bracings, temporary support for structures, repairs, etc.

ARTICLE 10

Subcontracts

1. The Contractor, in any contract with a Subcontractor, shall provide that the Subcontractor shall be subject to all specifications, terms, provisions, conditions, requirements and liabilities set forth in this contract so far as such specifications, terms, provisions, conditions, requirements and liabilities are applicable to the work to be done under such Subcontract, and shall also provide that such Subcontract shall be terminated by the Contractor whenever the Commissioner shall certify to him in writing that in his opinion the work of the Subcontractor is unnecessarily or unreasonably delayed or that the Subcontractor has violated any of the provisions of this contract. The Contractor shall at once terminate such subcontract if the Commissioner, after certifying as aforesaid, shall in writing direct the Contractor to make such termination.

2. Subcontracts shall be made in writing and the Contractor shall furnish the Commissioner with a copy of his subcontracts on demand.

3. Pursuant to the provisions of M.G.L. Ch. 30, Sec. 39F (1), the following provisions are included in the General Conditions:

(a) Forthwith after the general contractor receives payment on account of a periodic estimate, the general contractor shall pay to each subcontractor the amount paid for the labor performed and the materials furnished by that subcontractor, less any amount specified in any court proceedings barring such payment and also less any amount claimed due from the subcontractor by the general contractor.

(b) Not later than the sixty-fifth day after each subcontractor substantially completes his work in accordance with the plans and specifications, the entire balance due under the subcontract less amounts retained by the awarding authority as the estimated cost of completing the incomplete and unsatisfactory items of work, shall be due the subcontractor; and the awarding authority shall pay that amount to the general contractor. The general contractor shall forthwith pay to the subcontractor the full amount received from the awarding authority less any amount specified in any court proceedings barring the payment and also less any amount claimed due from the subcontractor by the general contractor.

(c) Each payment made by the awarding authority to the general contractor pursuant to subparagraphs (a) and (b) of this paragraph for the labor performed and the materials furnished by a subcontractor shall be made to the general contractor for the account of the subcontractor; and the awarding authority shall take reasonable steps to compel the general contractor to make each such payment to each such subcontractor. If the awarding authority has received a demand for direct payment from a subcontractor for any amount which has already been included in a payment to the general contractor or which is to be included in a payment to the general contractor for payment to the subcontractor as provided in subparagraphs (a) and (b), the awarding authority shall act upon the demand as provided in this section.

(d) If, within seventy days after the subcontractor has substantially completed the subcontract work, the subcontractor has not received from the general contractor the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor, less any amount retained by the awarding authority, the demand shall be by a sworn statement delivered to or sent by certified mail to the awarding authority, and a copy shall be delivered to or sent by certified mail to the general contractor at the same time. The demand shall contain a detailed breakdown of the balance due under the subcontract and also a statement of the status of the completion of the subcontract work shall be valid even if delivered or mailed prior to the seventieth day after which the subcontractor has substantially completed the subcontract work. Within ten days after the subcontractor has delivered or so mailed the demand to the awarding authority and delivered or so mailed a copy to the general contractor, the general contractor may reply to the demand. The reply shall be by a sworn statement delivered to or sent by certified mail to the awarding authority and a copy shall be delivered to or sent by certified mail to the subcontractor at the same time. The reply shall contain a detailed breakdown of the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor and of the amount due for each claim made by the general contractor against the subcontractor.

(e) Within fifteen days after receipt of the demand by the awarding authority, but in no event prior to the seventieth day after substantial completion of the subcontract work, the awarding authority shall make direct payment to the subcontractor of the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor, less any amount (i) retained by the awarding authority as the estimated cost of completing the incomplete or unsatisfactory items of work (ii) specified in any court proceedings barring such payment, or, (iii) if the reply shall not deduct from a direct payment any amount as provided in part (iii) if the reply is not sworn to, or for which the sworn reply does not contain the detailed breakdown required by subparagraph (d). The awarding authority shall make further direct payments to the subcontractor forthwith after the removal of the basis for deductions from direct payments made as provided in parts (i) and (ii) of this subparagraph.

(f) The awarding authority shall forthwith deposit the amount deducted from a direct payment as provided in part (iii) of subparagraph (e) in an interest-bearing joint account in the names of the general contractor and the subcontractor in a bank in Massachusetts selected by the awarding authority or agreed upon by the general contractor and the subcontractor and shall notify the general contractor and the subcontractor of the date of the deposit and the bank receiving the deposit. The bank shall pay the amount in the account, including accrued interest, as provided in an agreement between the general contractor and the subcontractor or as determined by decree of a court of competent jurisdiction.

(g) All direct payments and all deductions from demands for direct payments deposited in an interest-bearing account or accounts in a bank pursuant to subparagraph (f) shall be made out of amounts payable to the general contractor at the time of receipt of a demand for direct payment from a subcontractor and out of amounts which later become payable to the general contractor and in the order of receipt of such demands from subcontractors. All direct payments shall discharge the obligation of the awarding authority to the general contractor to the extent of such payment.

(h) The awarding authority shall deduct from payments to a general contractor amounts which, together with deposits in interest-bearing accounts pursuant to subparagraph (f), are sufficient to satisfy all unpaid balances of demands for direct payment received from subcontractors. All such amounts shall be earmarked for such direct payments, and the subcontractors shall have a right in such deductions prior to any claims against such amounts by creditors of the general contractor.

ARTICLE 11

Compensation for Work

1. Subject to any provisions in Paragraph 7, the price named in the proposal and accepted by the City shall be paid by the City and received by the Contractor as full compensation for furnishing materials and for use of tools, forms, machinery and other implements, and for labor in moving materials and executing all the work contemplated in this contract, also for loss or damage arising from delay however occasioned, or out of the nature of the work aforesaid or from the action of the elements, from floods, or from any unforeseen obstructions or difficulties which may be encountered in the prosecution of the same and for all risks of every description connected with the work and for well and faithfully completing the work in the proper manner and according to the plans and specifications and requirements of the Commissioner under them.

2. During the first week of each calendar month, the City Engineer shall cause all work done by the Contractor during the previous month to be measured and shall estimate the value thereof and, on or before the 10th of each month issue a certificate to the Commissioner of the measurements and the amount due the Contractor according to the terms of his contract.

3. The City shall pay the Contractor on approval of the Commissioner monthly on or before the 18th of each month for all work done during the preceding month according to the aforementioned certificate of the City Engineer, less 5 per cent of the amount of such work and less any amounts due the City by the Contractor.

4. Within ten days after the completion of the work as determined by the Commissioner, the City Engineer shall issue to the Commissioner a final certificate of the total amount of work done and the money due the Contractor therefor, crediting thereon the amounts of the previous payments. In making the final certificate, the City Engineer shall not be bound by any preceding certificate or estimate of the amount of work done or materials furnished.

Final Payment--Claims Against Contractor

5. At the expiration of 65 days after the completion of the work as determined by the Commissioner, the City shall, unless claims are made or notice of liability against the City is given, pay the Contractor, on the approval of the Commissioner, the percentages retained and the balance due the Contractor according to the aforementioned final certificate of the City Engineer less any indebtedness of the Contractor to the City. If a claim or claims are made, or notice of liability given, such amounts due the Contractor may be paid upon satisfaction of such claims or upon furnishing of indemnity to said City against all loss, cost, damage or expense by reason of such claims. In the event of no known claims or liens the City may, at its option, pay within 35 days.

6. The City, on making any payment after the completion of the work, shall be released from all claim or liability to the Contractor for anything done or used, or for any loss or injury sustained in carrying on the contract, or for any act, omission, neglect or mistake of the City or any person relating to or affecting the contract, except for the balance of any sum retained as aforesaid.

Extra Work

7. The Contractor shall be paid for any additions, or deductions as provided in Article 5, paragraph 1, and for extra labor done by, and for extra materials furnished by him in compliance with the written order only of the Commissioner, calling for work not similar in character to that covered by the items given in the proposal, and for which no price is set in the said written order, the direct (not including consequential) cost to the Contractor, as determined to be reasonable by the Commissioner, plus fifteen per cent of said costs as so determined in regard to labor only. For teams or trucks so furnished, no payment shall be made to the Contractor beyond the current local rate as determined by the Commissioner in each case. The direct cost of labor may include the cost of mechanics and laborers furnished and a reasonable proportion of the time of the foreman and timekeeper, but it shall in no case include any charge for the use of tools, for establishment charges or for time spent by the Contractor. The actual cost of insurance on extra pay rolls and of materials furnished for extra work, shall be paid without any addition. The labor and materials so ordered shall constitute a part of the work to be done under the contract; and all and singular the provisions of the contract shall apply to said labor and materials as if the same were specified therein. The Contractor shall have no claim for the above mentioned extra labor and materials unless he furnishes the details and bills therefor within one week after doing any such labor or furnishing any such materials.

8. No claim of the Contractor against the City under this contract shall be deemed valid unless such claim is presented to the Commissioner within ten days from the time when the Contractor first knows of, or has opportunity to know of, the acts and circumstances on which such claim is based.

9. A payment or payments to the Contractor, in cases where these provisions or any of them, are not complied with, shall not be construed as a waiver of said provisions or any part thereof.

Contract Made Subject to Appropriations

10. This contract is made subject to appropriation heretofore made and shall not be altered unless the Contractor, the sureties on the bond, if any, the officer making the contract and the Mayor shall in writing agree thereto.

ARTICLE 12

Responsibility for Work--Contractor's Responsibility

1. The Contractor has made his proposal from his own examinations and estimates, and shall not hold the City, its agents, or employees, responsible for or bound by, any schedule, estimate, sounding, boring, or any plan of any part of the work; shall, if any error in any plan, drawing, specification or direction relating to anything to be done under the contract come to his knowledge, report it at once to the Commissioner; shall not, except as the Commissioner shall authorize in writing, assign or sublet any part of the contract except for the supply of materials and plant, or of anything to be done thereunder; shall, subject to the provisions of the contract take all responsibility of, and bear all losses resulting to him in carrying on the contract, and shall assume the defense of, and hold the City, its agents and employees harmless from all suits and claims against them, or any of them, arising from the use of any invention, patent or patent right, material, labor or implement, by or from any act or omission or neglect of the Contractor, his Subcontractor, his agents or employees, in carrying on the contract, or for any liability of any nature arising under the contract. The Contractor shall be solely responsible and liable for, and shall fully protect and indemnify the City against all claims for damages to persons or property occasioned by or resulting from blasting or other methods or processes in the work of construction, whether such damages be attributable to negligence of the Contractor, his employees or his Subcontractor or otherwise.

ARTICLE 13

Lights--Guards

1. The Contractor shall assume all responsibilities of the work and take all proper precautions to protect persons and property from injury and unnecessary interference; leave a reasonably unobstructed way along public and private places for pedestrians, teams, and vehicles, and for access to hydrants; provide proper walks over or around any obstruction made in a public or private place in carrying on the contract, and maintain from the beginning of twilight through the whole of every night, on or near the obstruction sufficient lights and guards to protect travelers from injury thereby, and if, after one notification from the Commissioner that said lights and guards are not sufficient, the Contractor has not placed additional lights and guards to the satisfaction of the Commissioner, the Commissioner shall have the right to take charge of that part of the work at the expense of the Contractor. While the work is suspended he shall keep all roadways and sidewalks in proper condition, and when the work is completed put the place and vicinity in proper condition and so leave them.

The Contractor shall provide proper means of access to property where the existing access is cut off by the Contractor and replace or put in good condition every conduit, catch-basin, tree, wall, fence, or other thing injured by the Contractor in carrying on the contract, unless the same has been permanently done away with, on approval of the Commissioner, as being necessary to the proper carrying on of the contract.

ARTICLE 14

Guaranty

1. Any settlement or other defect, or the failure of any part of the structure or the work due to defective materials or workmanship, that occurs within one year after the work is completed, is to be immediately repaired by the Contractor. In the event of any such settlement, defect, or failure causing liability to the City for damage to persons or property, the Contractor does by this clause agree to hold the City harmless and to assume the defense of any claims therefor.

2. Responsibility under this guaranty for the adequacy of the work does not relieve the Contractor of his obligation to comply with the terms of the contract and to conform to all the requirements of the plans and specifications, nor does it give him the right to deviate in any way from the details of design of the structure or the work.

ARTICLE 15
Defective Work and Materials

1. The inspection of the work shall not relieve the Contractor of any of his obligations to fulfill his contract as herein described, and defective work shall be made good and unsuitable materials may be rejected, notwithstanding that such work and materials have been previously overlooked by the Engineer and accepted or estimated for payment. If the work or materials, or any part thereof shall be found defective at any time before the final acceptance of the whole work, the Contractor shall forthwith make good such defect in a manner satisfactory to the Engineer, and if any material brought upon the ground for use in the work or selected for the same, shall be condemned by the Engineer as unsuitable or not in conformity with the specifications, the Contractor shall forthwith remove such materials from the vicinity of the work. Nothing in this contract shall be construed as vesting in the Contractor any right of property in the materials used after they have been attached or affixed to the work or the soil, but all materials shall, upon being so attached or affixed, become the property of the City of Newton.

ARTICLE 16
Employment of Labor


1. The Contractor shall give preference in employment, first to citizens of Massachusetts, second, to other citizens of the United States; and shall allow all employees on said work to lodge, board and trade where they choose, and shall not obstruct any other person in doing work for the City; and shall conform to all labor laws of the Commonwealth; and no laborer or teamster, workman or mechanic working within this Commonwealth in the employ of the Contractor or Subcontractor or other person doing or contracting to do the whole or a part of the work contemplated by the Contractor shall be requested to, or required to, or work more than eight hours in any one calendar day. This contract is subject to all the laws of the Commonwealth, and ordinances of the City and if any clause thereof does not conform to such laws and ordinances, such clause shall be void and such laws and ordinances operated in lieu thereof.

ARTICLE 17
Laws and Regulations--Contractor to Comply with Law

1. The Contractor shall keep fully informed of all existing or future acts of the legislature, and of all municipal ordinances, prohibitions, rules and regulations in any manner affecting the conduct of the work, and of all orders or decrees of any body or tribunal having any jurisdiction or authority over the materials, times, places and actions of those employed in the work embraced in the contract. The Contractor shall at all times observe and comply with all existing and future acts, ordinances, prohibitions, rules, regulations, orders and decrees; and shall protect and indemnify the city and its employees against any and all claims arising from or based on any violation of such acts, ordinances, prohibitions, rules, regulations, orders or decrees, and against all violations of law by the Contractor or his agents or employees.

END OF SECTION

Locus Plan of Target Sites



STREETS SCHEDULED TO BE DONE UNDER THIS COLD-PLANING PROGRAM:

- The scheduling of this work shall be solely at the discretion of the Engineer.
- The scope of the work is subject to modification as the operations progress. In addition, the day-to-day operational aspects may also be subject to modification as the Engineer shall so direct
(i.e. final depth, dates & scheduled periods, length of lanes, lengths & breadth of cold-planing areas).
- The Engineer reserves the right to designate any street and/or roadway as arterial corridors as the field conditions may warrant and/or at the time the cold-planing operation is performed.
- Cold-planing shall typically include the portions of the intersecting roadways up to the PC or as otherwise directed.
- MBT = Estimated Linear Feet of 'Monolithic Berm Table' to be installed along this roadway, however the cold-planing work shall ultimately be paid by the Square Yard under the cold-planing bid price. (Refer to Item Sheet 3 and the Special Provisions for further information)

STREET	ARTERIAL	LIMITS	ESTIMATED SQUARE YARDS
Cottage Street	N	Thurston Road to Elliot Street	2841
Bowdoin Street	N	Lincoln Street to Erie Avenue	812
Carlson Avenue	N	Dedham Street to Parking Lot	2200
Freeman Street	N	Staniford Street to Lexington Street	4119
Christina Street	N	230' West of Bernard Street to Wallace Street	3889
Lee Road	N	Reservoir Avenue to Lawrence Avenue	3043
Wallace Street	N	Winchester Street to 130' West of Bernard Street	3850
Bound Brook Road	N	Dedham Street to Upland Avenue	3713
Street List Continued on the Next Page			

STREET	ARTERIAL	LIMITS	ESTIMATED SQUARE YARDS
Goddard Street	N	Winchester Street to Christina Street	3161
Melrose Street	N	West Pine Street to Commonwealth Avenue	4029
Elinor Road*	N	Kendall Road to Walnut Street	4364
Temple Street*	N	Highland Avenue to Carriage Road	9574
Walnut Street*	Y	As Directed by the Engineer	12800
Oak Street*	N	Elliot Street to Needham Street	3286
Pettee Street*	N	Thurston Road to High Street	800
Berkeley Street*	N	Temple Street to Chestnut Street	6249
Staniford Street*	N	West Pine Street to Lexington Street	1483
West Pine Street*	N	Melrose Street to Freeman Street	1293
Hillside Avenue	N	Austin Street to Otis Street	3360
Dedham Street	Y	100' North of Longmeadow Road to Broken Tree Road	1818

***Cold Planing of these streets shall not start until June 26th 2014 and shall be finalized by August 26th 2014.**

The Contractor shall insert prices for each item in ink, in both words and figures, and is to show a total bid price. In the event a discrepancy between the written words and figures, the written words shall govern. In the event an error in the bidders total bid price, the corrected total bid obtained by the summation of the products of the unit prices multiplied by the respective quantities shall stand as the bidder's total bid price.

The estimated quantities shown here are based solely upon a reasonable assessment of the project parameters, thus the Contractor is advised that the actual quantities may vary substantially as field conditions, scheduling, monetary constraints (due to cost adjustments) and/or final funding amounts necessitate.

NOTICE: In accordance with MGL Chapter 303 of the Acts of 2008 this bid contains price adjustments for Fuel (combination of Gasoline & Diesel). It is the bidder's responsibility to familiarize themselves with this price adjustment program prior to entering a bid.

ITEM DESCRIPTION & BID PRICE	ESTIMATED QUANTITIES	UNIT	TOTAL COST
<p>ITEM: 0.303FC - FUEL COSTS*</p> <ul style="list-style-type: none"> * Bidder's may elect NOT to bid the cost of fuel(s) separately by inserting the term N/A (<i>i.e. Not Applicable</i>) in all <u>entry lines</u> of this Item 0.303FC. This is a mandatory requirement to verify the Contractor has waived their option to bid the cost of fuel(s) separately and has instead elected to factor their <u>collective fuel costs for the cold-planing & disposal operations</u> into the bid price of Item 1D, Item W and Item 1N. Contractor's choosing to bid this line item must NOT include the cost of fuel in Item 1D, Item W and Item 1N. The City of Newton reserves the right to validate the Contractor's fuel consumption information before and after awarding the bid. <p>-----</p> <p>0.303FC = total combined number of gallons of Fuel (Diesel & Gasoline) to cold-plane & dispose of <u>One Square Yard</u> of 1 ½"-2" Bituminous Concrete:</p> <p>(IN WORDS) _____ Gallons Per Square Yard</p> <p>(IN FIGURES) _____ Gallons Per Square Yard</p> <p>(_____ Gallons per S.Y.) x (\$ <u>3.335</u> /Gallon) x ^{^ Base Price^} <i>of diesel and gasoline = BPF</i> <i>Per Mass Highway</i></p>	77,000	S.Y.	<p>Note: This factored value is for the <u>Comparison of Bids</u> <u>Only.</u> (See Spec. Prov.)</p> <p>\$ _____</p>

(Items continued on next page)

ITEM DESCRIPTION & BID PRICE	ESTIMATED QUANTITIES	UNIT	TOTAL COST
<p>Item: 1 D - COLD-PLANING OF BITUMINOUS CONCRETE ROADWAYS WITH THE IMMEDIATE DISPOSAL OF MATERIAL IN THE DAYTIME</p> <p>DO NOT INCLUDE FUEL COSTS UNLESS WAIVED (See Item 0.303FC) *</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER SQUARE YARD</p>	67,000	S.Y.	\$ _____
<p>Item: 1 N - COLD-PLANING OF BITUMINOUS CONCRETE ROADWAYS WITH THE IMMEDIATE DISPOSAL OF MATERIAL IN THE NIGHTTIME</p> <p>DO NOT INCLUDE FUEL COSTS UNLESS WAIVED (See Item 0.303FC) *</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER SQUARE YARD</p>	5,000	S.Y.	\$ _____
<p>Item: 1 W - COLD-PLANING OF BITUMINOUS CONCRETE ROADWAYS WITH THE IMMEDIATE DISPOSAL OF MATERIAL ON THE WEEKEND</p> <p>DO NOT INCLUDE FUEL COSTS UNLESS WAIVED (See Item 0.303FC) *</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER SQUARE YARD</p>	5,000	S.Y.	\$ _____
<p>Item: 2 - RETRIEVE & DEPLOY A CITY OWNED (GATE-BOX OR MANHOLE) PROTECTOR RING</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER RING</p>	300	RING	\$ _____

ITEM DESCRIPTION & BID PRICE	ESTIMATED QUANTITIES	UNIT	TOTAL COST
Item: 3.10 - FURNISH & INSTALL A <u>TEN INCH</u> (INSIDE DIAMETER) GATE-BOX PROTECTOR RING THE SUM OF: _____ DOLLARS AND _____ CENTS (\$ _____) PER EACH	50	EA.	\$ _____
Item: 3.28 - FURNISH & INSTALL A <u>TWENTY-EIGHT INCH</u> (INSIDE DIAMETER) MANHOLE PROTECTOR RING THE SUM OF: _____ DOLLARS AND _____ CENTS (\$ _____) PER EACH	25	EA.	\$ _____
Item: 3.31 - FURNISH & INSTALL A <u>THIRTY-ONE INCH</u> (INSIDE DIAMETER) MANHOLE PROTECTOR RING THE SUM OF: _____ DOLLARS AND _____ CENTS (\$ _____) PER EACH	25	EA.	\$ _____
Item: 4 – ALLOWANCE FOR PAYMENT OF POLICE OFFICERS (THESE MONIES ARE TO BE PAID DIRECTLY THRU AN INTER-DEPARTMENTAL BILLING PROGRAM) THE SUM OF: _____ SIXTY THOUSAND DOLLARS AND _____ NO CENTS (\$ 60,000.00) PER ALLOWANCE	1	ALL.	\$60,000

ITEM DESCRIPTION & BID PRICE	ESTIMATED QUANTITIES	UNIT	TOTAL COST
<p>ITEM: 5 – 8" CEMENT CONCRETE HANDICAP RAMP / CURB CUTS</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER SQUARE YARD</p>	850	S.Y.	\$ _____
<p>ITEM: 6 – DETECTABLE TILE SURFACE FOR HANDICAP RAMP / CURB CUT LOCATIONS</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER EACH</p>	70	EA.	\$ _____
<p>Item 7 – RESET EXISTING CURB (WITH CONCRETE MORTAR EMBEDMENT) (INCLUDES CURB WORK REQ'D FOR HANDICAP RAMPS)</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER LINEAR FOOT</p>	200	LF.	\$ _____
<p>Item 8 - FURNISH & INSTALL STRAIGHT GRANITE VA-4 CURB (WITH CEMENT MORTAR EMBEDMENT) (INCLUDES 'ISOLATED' INSTALLATIONS & HANDICAP RAMP WORK)</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER LINEAR FOOT</p>	700	LF.	\$ _____
<p>Item 9 - FURNISH & INSTALL CURVED VA-4 GRANITE CURB (WITH CEMENT MORTAR EMBEDMENT) (INCLUDES HANDICAP RAMP WORK)</p> <p>THE SUM OF: _____ DOLLARS</p> <p>AND _____ CENTS</p> <p>(\$ _____) PER LINEAR FOOT</p>	700	LF.	\$ _____

ITEM DESCRIPTION & BID PRICE	ESTIMATED QUANTITIES	UNIT	TOTAL COST
ITEM 10 - 4" BITUMINOUS CONCRETE FOR 'PERMANENT' TRENCH RESURFACING THE SUM OF: _____ DOLLARS AND _____ CENTS (\$ _____) PER SQUARE YARD	250	SY.	\$ _____
ITEM 11 – ADJUSTMENT OF EXISTING STRUCTURES (LESS THAN OR EQUAL TO 12" INCH) THE SUM OF: _____ DOLLARS AND _____ CENTS (\$ _____) PER EACH	50	EA	\$ _____
ITEM 12 – ADJUSTMENT OF EXISTING STRUCTURES (GREATER THAN 12" INCH) THE SUM OF: _____ DOLLARS AND _____ CENTS (\$ _____) PER EACH	50	EA	\$ _____
Item: 13 - MISCELLANEOUS WORK ALLOWANCE (ENGINEER'S DISCRETIONARY FUND) THE SUM OF: _____ FIVE HUNDRED _____ DOLLARS AND _____ NO _____ CENTS (\$ _____ 500.00 _____) PER ALLOWANCE	1	ALL.	\$500

TOTAL BID PRICE :

\$

(Total Bid Price must be entered in "PARAGRAPH C" of the BID FORM).

END OF SECTION

SPECIAL PROVISIONS

SECTION 0. 303

ITEM: 0.303FC - FUEL COSTS*

Description

*** The Contractor may elect NOT to bid the cost of fuels separately by inserting the term N/A (i.e. *Not Applicable*) in all (4) entry lines of Item 0.303FC on Item Sheet 4. This is a mandatory requirement to verify that the Contractor has formally waived their option to bid the cost of fuel(s) separately and has instead elected to factor the cold-planing & the disposal of materials fuel costs into the separate bid price of Item 1D and Item 1N.**

(a) Under this item the Contractor shall be paid for all the fuel(s) consumed in the performance of this contract.

(b) The intent of this program is to maintain a reasonable and continuous parity with the regional fluctuations that may occur in the cost of petroleum based fuel products. It is important to note that due to the numerous types of; fuel, equipment, vehicles, programs, and efficiency factors related to each of these operational elements and therefore unique to the Contractor's own enterprises, that any fuel adjustments made under this item are intended only to defray and offset extraordinary market trends in petroleum based fuel products.

(c) IMPORTANT NOTE: An adjustment to the cost of fuels may result in an increase of payment if the fuel market has trended upward, or it may otherwise result in a decrease of payment if the fuel market has trended downward.

(d) The City of Newton reserves the right, before awarding the Contract, to request from the Contractor a tabulated accounting of the means and methods upon which the number of gallons bid by the Contractor was derived. The intent of this evaluation is to preserve the fairness of this program by preventing bidders from placing an imbalanced bid that may ultimately cause excessive financial impact to either party. These tabulations will include, but shall not be limited to, an accounting of all **transport and cold-planing** related equipment and their associated manufacturers fuel consumption rates which the Contractor/supplier intends to use to complete the work under this contract. In the event the City of Newton, subsequent to performing an analysis, determines that the Contractor's bid, with regard to the consumption of fuel for **the cold-planing & disposal of the bituminous concrete, is excessive for the type of cold-planing and transport equipment** and traditionally deployed for this type of work then **the City of Newton reserves the right to waive any informalities in any or all bids, or to reject any or all bids, if it be in the public interest to do so.**

(e) The Contractor shall also incorporate into their bid the amounts of fuel required for any work performed by their subcontractors or by their vendors.

Method of Administration

(f) In accordance with Chapter 303 Acts of 2008, the City of Newton shall use the most current 'new' pricing of Diesel and Gasoline fuel as they are indicated on the Mass Highway web site at the time of advertisement.

<http://www.mhd.state.ma.us/default.asp?pgid=content/fuelPrices&sid=about#para24>

The **average** of these two values (Diesel & Gasoline) shall serve as the value basis for determining the **Base Price** of Fuel (BPF) at the time of the advertisement. Subsequently, during the course of the contract, the **Period Price** of Fuel (PPF) shall be determined in the same manner, but at the end of each calendar month, and if the **averaged** Period Price (PPF) has either increased or decreased by more than five percentage points (5%) relative to the **averaged** Base Price of Fuel (BPF), then the cost of fuel(s) for the applicable calendar month shall be paid for at the adjusted rate, otherwise the cost of fuel(s) for the applicable calendar month shall be paid for at the initial Base Price of Fuels.

The Contractor is advised to verify these value standards and citations prior to placing their bid.

Method of Administration

(g) When a cost adjustment is applied it shall be inclusive of the five (5%) variation.

(h) Payments for fuel shall be calculated at the end of **each calendar month** and they shall be based upon the acceptable number of **square yards of bituminous concrete cold-planed and disposed of** within that particular (applicable) calendar month in which the work was performed. **(Program Note: In the event a continuous cold-planing operation spans several days but the cold-planing & disposal activities is performed in two separate months, then two separate fuel payments shall be made).**

(i) At the end of each calendar month the Contractor shall furnish the Engineer with an accurate measured and tabular accounting which clearly shows the **collective amount of square yards cold-planed & disposed of during that particular (applicable) calendar month**. The invoiced accounting shall bear the name of the Contractor and Vendor and shall **be surrendered to the DPW Agent-In-Charge immediately upon the termination of operations at the end of each calendar month**. The City will have no obligation to pay at a higher rate of fuel for any unreported work performed in any calendar month but which is subsequently forwarded after the operations for the month have ceased.

(j) **No upward fuel adjustment will be made for any cold-planing or related activity which takes place beyond the completion date of the contract** unless the Contractor's work has been delayed due to no fault of their own (i.e. Preparation work that must be performed by others before the Contractor can complete their own tasks in the contractually allotted time.) Any such delay must be brought to the attention of the DPW Agent-In-Charge in a timely manner at which time the Agent shall investigate, verify, and document the extenuating circumstances and inform the Contractor of their decision.

Method of Payment

(k) Payment formula:

BPF = The Base Price of Fuel on the bid release date (Averaged cost of Diesel & Gasoline in \$/Gallon)

PPF = The Period Price of Fuel for the applicable calendar month (Averaged cost of Diesel & Gasoline in \$/Gallon)

G = Gallons of fuel bid by the Contractor to Cold-Plane & Dispose of **(1) Square Yard of Bit. Conc.**
(Gallons bid per S.Y. for all cold-planing & disposal services)

SY = The total number of Square Yards of Bit. Conc. Cold-planed & disposed of in the applicable calendar month

If the (PPF) does not exceed +/- 5% relative to the (BPF) then: (BPF) x G x SY = Fuel Payment (\$)

If the (PPF) does exceed +/- 5% relative to the (BPF) then: (PPF) x G x SY = Fuel Payment (\$)

Basis of Payment

*** The Contractor may elect NOT to bid the cost of fuels separately by inserting the term N/A (i.e. Not Applicable) in all (4) entry lines of Item 0.303FC on Item Sheet 3. This is a mandatory requirement to verify that the Contractor has formally waived their option to bid the cost of fuel(s) separately and has instead elected to factor the cold-planing & the disposal of materials fuel costs into the separate bid price of Item 1D and Item 1N.**

Basis of Payment (Continued)

(l) The cost of fuel(s) consumed for the **cold-planing and immediate disposal of one (1) square yard of 1 ½"-2" of bituminous concrete** shall be paid for under **Item 0.303FC (unless waived)**. The cost of fuel used to complete the work under this contract shall be made in accordance with the applicable Period Price for Diesel & Gasoline fuels as posted for each calendar month in which the work was performed and as specified herein.

(m) The Contractor shall be responsible for disbursing fuel cost payments to their subcontractors and/or to their vendors.

(n) No payment shall be made for any fuel(s) consumed to remedy any deficient and/or insufficient work performed by the Contractor, subcontractors and/or their vendors.

SECTION 1

ITEM: 1 D - COLD-PLANING OF BITUMINOUS CONCRETE ROADWAYS WITH THE IMMEDIATE DISPOSAL OF MATERIAL IN THE DAYTIME

ITEM: 1 N - COLD-PLANING OF BITUMINOUS CONCRETE ROADWAYS WITH THE IMMEDIATE DISPOSAL OF MATERIAL IN THE NIGHTTIME

ITEM: 1 W - COLD-PLANING OF BITUMINOUS CONCRETE ROADWAYS WITH THE IMMEDIATE DISPOSAL OF MATERIAL ON THE WEEKEND

DO NOT INCLUDE FUEL COSTS UNLESS WAIVED (See Item 0.303FC) *

Description

*** The Contractor may elect NOT to bid the cost of fuels separately by inserting the term N/A (i.e. Not Applicable) in all (4) item sheet entry lines of Item 0. 303FC. This is a mandatory requirement to verify that the Contractor has formally waived his option to bid the cost of fuel(s) separately and has instead elected to factor his cold-planing & disposal fuel costs into the separate bid price of Item 1D and Item 1N.**

(a) The work to be done under **Item 1D and Item 1N and Item 1W** consists of removing bituminous concrete along designated roadways, from within adjacent intersections, from around various roadway structures, and/or along shoulder areas by self-propelled cold-planers and/or by supplemental cold-planing methods. Where ‘tables’ are created in preparation for the eventual installation of monolithic berm the Contractor shall be further required to perform handwork behind catch basins, around utility poles and/or any other object, which encroaches within the ‘table’ range. The supplemental handwork shall be performed for the purpose of clearing all areas of existing berm/border material which is inaccessible to the cold-planer machinery in order to complete the plane of the proposed ‘table’.

(b) Under **Item 1D and Item 1N and Item 1W** the work requires cold-planing to a **minimum depth of one and one-half (1 1/2) inches up to a maximum depth of two (2) inches across the entire existing bituminous roadway surface, during the daytime, weekend or during the nighttime respectively**, inclusive of the area(s) immediately around and about all existing castings, in addition to adjacent roadway intersection areas as designated and/or as otherwise **pre-approved by the Engineer**. Further, the cold-planing operation shall also be used, from time to time as the Engineer may direct, to re-profile the cross-section of the existing roadway in order to alleviate drainage problems, to transition the pavement surfaces, and/or to eradicate other roadway imperfections.

(c) **All excavated/milled material shall become the property of the Contractor. The Contractor shall be responsible for the immediate removal and subsequent legal disposal of the material. In addition, any such work shall be done in an environmentally proper manner, inclusive of controlling both dust and debris. The Contractor is further advised that no City of Newton sites will be available for either the stockpiling, or for the disposal of any cold planing, or for any other residual roadway material(s).**

(d) **Under this item the Contractor is to work closely with the Engineer to layout, coordinate and schedule the cold-planing operation which shall be determined on a week to week basis in order to best meet the needs of the paving program which shall be done under a separate contract.**

(dd) Under this Section the Contractor is to create and deliver a written notice(s) to each address located along the roadway corridor which he intends to occupy and cold-plane in order to inform all concerned parties that the normal

traffic pattern, unique to each area, will be disrupted during the course of his operations. The notices are to be delivered **by the Contractor's Personnel at least twenty-four (24) hours in advance of each separate site occupation and/or disruption** of the respective traffic patterns in and about the area(s), or as otherwise directed by the Engineer. The notice is to be on a format acceptable to the Engineer and shall contain the time, date and duration of

the expected disruption. **However; in no case shall any daytime operation be posted to occur before the lawful 7:00 A.M. start time, and notwithstanding emergency conditions, nor shall any paving related daytime operation extend beyond 4:30 P.M. of the same day, nor shall any nighttime operation be posted to occur before the lawfully allowed hours as defined on an applicable permit, as directed by the Engineer, or otherwise 8:00 P.M., and all work, inclusive of post-paving activities, shall be completed no later than 5:00 A.M. of the next day (i.e. of the same night). Weekend operations (Saturday and Sunday) shall not begin operations before 9:00 A.M. and all work inclusive of post-paving activities shall be completed no later than 4:30 P.M.** In addition, the notice is to be placed in a conspicuous location and as near to the regular mail delivery as possible such that the notice will be gathered up with that days regular mail. The distribution of notices is to further comply with the directives shown on the plans. In addition the Contractor shall also notify the Engineer, City of Newton Customer Service Division and the City of Newton Fire Department Headquarters at least twenty four (24) hours in advance of a planned event, with a copy of such notice being made to the Engineer. The Engineer shall have the right to request that such advance notifications be made either in writing or by verbal communiqué. Subsequently, upon the restoration of normal traffic patterns the Contractor shall notify the Engineer, City of Newton Customer Service Division and the City of Newton Fire Department Headquarters within twenty-four (24) hours after completing the cold-planing operation(s), in order to keep all interested parties apprised of the current conditions.

- **Special Requirements for Nighttime Paving Operations**

(np01) Under Item 1 N the Contractor shall take every action to ensure that **the nighttime activities are conducted as quietly as possible**. To that end the Engineer reserves the right to disallow the Contractor from using equipment and/or personnel which, in his opinion, are noisy and/or are disruptive to the general peace of the neighborhood in which the work is taking place. In the event the Engineer deems an individual(s) and/or a piece of equipment to be disruptive, noisy or otherwise contrary to the intent of this order then the Contractor shall immediately dismiss the individual(s) and/or replace the non-compliant equipment.

(np02) **Cold-Planing performed at night shall be re-inspected in the daylight for evidence of flaws. Any area(s) which are found to be incomplete or inadequately cold-planed, or is inconsistent with quality workmanship, shall be corrected by the Contractor at no cost to the City of Newton.**

(np03) **Back-up alarms for nighttime operations: Trucks and/or other wheeled equipment used during the nighttime operations shall be equipped with switches which shall disable the back-up alarms while such equipment is on the site. However no alarm is to be disengaged until the watchman, an individual(s) assigned to the solitary task of aiding and guiding each piece of equipment into position as it moves in its rearward direction, has issued the order to do so. To that end no piece of equipment is to reverse its direction unless the watchman assigned to guide it is fully in control of the rearward/reverse motion of the vehicle. Such guidance procedures between the watchman and the driver of the equipment shall be by a positive means, such as two-way communication devices, flashlights or the like, or by a combination of several acceptable means which will ultimately protect both people and property from harm. The intent of this order is to minimize the noise level but never to jeopardize the health and welfare of any party. Upon completion of the rearward movement the watchman shall immediately instruct the driver of the vehicle to reactivate the back-up alarm.**

In the event of a conflict the Contractor shall comply with the latest OSHA requirements which shall take precedence over these instructions.

(np04) **During nighttime operations all workmen shall be outfitted with OSHA approved reflective-type safety vests. In addition the Contractor shall supply working flashlights, of no-less than a ‘two-D battery type’ ,to all Police Officers, and to the Engineer(s), for their use during the course of nighttime operations.**

(np05) **Illumination for nighttime operations:**

- Generators and wiring shall conform to the Massachusetts Electrical Code, OSHA safety standards and each device shall be UL listed.
- All portable lighting shall be positioned along the roadway in such a manner that it does not conflict with the flow of traffic, pedestrian access or with the paving operation(s), but ultimately provides substantial and adequate lighting so that all activities are performed in a safe environment for all parties, while at the same time ensuring that the applied pavement is easily seen and is installed to the satisfaction of the Engineer and in accordance with these specifications.
- Illumination shall be accomplished with metal halide floodlights, firmly mounted to a stable frame, and all floodlights are to be fitted with tempered glass or polycarbonate lenses securely fastened to the housing to prevent personal injury in the event of lamp breakage.
- Illumination for every process shall be by an adequate number of floodlights that allows all areas of the pavement and/or processing areas to be clearly seen. Floodlights may range from 250 watt to 1500 watt metal halide lamps which are aimed in such a manner that shadows are eliminated along the traveled way and glare from the lamps does not interfere with motorists.
- Each cold-planer or skid steer units shall be equipped with a two (2) unit light cluster on both front and back. A single cluster with two units (one wide beam and one narrow beam) aimed towards the front and two (one wide beam and one narrow beam) towards the back may be used. The positioning of these clusters shall provide the driver with a clear and unobstructed view of the roadway surface under construction.
- Two (2) pick-up trucks equipped with a two (2) unit adjustable light cluster on both front and back shall be provided by the Contractor. A single cluster with two units (one wide beam and two narrow beam) aimed towards the front and two (one wide beam and two narrow beam) towards the back may be used. The positioning of these units shall be at the discretion of the Engineer but in the absence of a direct order from the Engineer the Contractor shall keep these portable units in constant use to illuminate the work area(s) to provide a clear and unobstructed view of the roadway surface under construction.
- The cold-planer shall be equipped with a continuous fluorescent bar lamp assembly consisting of enclosed units. In addition a single cluster with two units (one wide beam and one narrow beam) aimed towards the front and two (one wide beam and one narrow beam) towards the back may be used. The positioning of these light clusters on the cold-planer shall provide the driver with a clear and unobstructed view of the roadway surface under construction, however at no time shall these lights be aimed into the mirrors of trucks backing up to the discharge area.
- The Contractor shall ensure that a variety of replacement lamps are readily available on the site and in the event there is a lamp failure the Contractor shall immediately replace the defective device without compromising the safety of people and/or property.
- If in the opinion of the Engineer the illumination is substandard then the Engineer reserves the right to stop work, and his decision shall be final.
- No compensation will be due the Contractor if work is stopped because of substandard illumination and/or defective lighting equipment, generators, and/or any other equipment. ‘Substandard’ and/or ‘defective’ shall include excessive noise, inclusive of personnel.

In the event of a conflict the Contractor shall comply with the latest OSHA requirements which shall take precedence over these instructions.

Equipment

(e) **No cold-planing shall be performed on arterial roadways before 9:00 A.M. nor after 3:30 P.M..** Arterial roadways shall be designated by the Engineer. The Contractor is further advised that the hours of operations are set by law. No machines or equipment are to be activated before **7:00 A.M. & no work is to extend beyond 4:30 P.M..** In addition no weekend or holiday work will be allowed unless special permission is granted.

(f) The cold-planer, and any other motorized vehicular equipment, shall be equipped with taillights, headlights, and necessary reflectors so that they can be operated in traffic with complete safety.

(g) The cold-planing machine shall be designed and built for planing flexible pavement and possess the added ability to plane cement concrete patches when encountered in bituminous pavement. It shall be self-propelled and have the means for planing, without tearing or gouging, the underlying surface, and the cold planing machine shall also have the inherent ability to directly convey the cold planed material into trucks as the operation commences. Variable lacing patterns shall be provided to permit a rough grooved surface, or smooth surface as directed by the Engineer. The machine shall be capable of being operated at speeds from 10 to 40 feet per minute, and designed so that the operator can at all times observe the planing operation without leaving his control area.

(h) The cold-planing machine shall be adjustable as to crown and depth. The equipment shall be demonstrated to have been operated successfully on similar work completed prior to the award of this contract.

(i) The equipment furnished by the Contractor shall be in good repair and shall be maintained so as to produce a clean cut into the pavement at all times.

(j) The cold-planer must be equipped with an elevating device capable of loading planed material directly into dump trucks while operative and with all necessary safety devices such as flashing lights and back-up signals so as to operate in traffic with complete safety.

(k) Supplemental equipment of a smaller scale, capable of performing cold-planing functions around and about roadway structures, and/or other similar areas which are not commonly accessible to the primary cold-planing machinery, shall be utilized by the Contractor to 'detail' the work zone and to ultimately complete the cold-planing operation.

(l) Cold-planers mounted on pneumatic tires will not be employed except for trimming and clean-up operations.

(m) Dust control equipment on the cold-planer must comply with EPA air quality standards. The equipment shall meet the standards set by the Air Quality Act for noise and pollution.

(mm) The Contractor shall comply with the directives of **Paragraph (dd)** pertaining to the distribution of notices.

(n) The Contractor shall demonstrate to the satisfaction of the Engineer that the equipment, crew and construction methods he intends to use are capable of completing the work in accordance with these specifications and within the time allotted.

Method of Construction (Continued)

(o) **The Contractor is advised that under certain conditions (i.e. bus traffic, emergency vehicle access, arterial roadways, etc.) vehicular traffic flow must be maintained,** therefore the Contractor must be prepared to accommodate vehicular travel throughout the project zone for the entire duration of the project while these process' are underway as it shall not be impaired.

(p) No roadway cold-planing is to be undertaken until **the City of Newton has established construction signs and/or safety devices around and about the project zone periphery.** To that end the Contractor shall not commence operations until he has verified that semi-permanent signs (i.e. 'Road Under Construction') and/or daily signing (i.e. 'Detour') has been appropriately established. **However, the Contractor shall be responsible for establishing supplemental signage, and/or safety devices, as he deems necessary in order to further provide for the safety of the pedestrian and the motoring public,** as well as for affording him the opportunity of moving his cold-planing process forward without interruption. Under this clause the Contractor shall work closely with the City of Newton Agent in order to coordinate the signing activities in a timely and reasonable manner. **Said devices shall conform to the Temporary Traffic Control section of the most recent version of the Manual on Uniform Control Devices (MUTCD).** Further, due to the nature of this work, the Contractor shall be required, from time to time, to erect, move, relocate, repair, and/or to remove at days end, any site sign in order to either expedite his work or to otherwise accommodate the safety and/or delineate the project zone and/or its active or inactive detour status and route line, and this work shall be done either at his discretion and/or at the request of a City of Newton Agent(s) or Officer. Non-compliance with any such request, as herein described, shall be grounds for the City to halt work until such remedial measures have been taken, and any such loss of time by the Contractor shall be at his own expense.

(q) **Prior to the cold-planing process, the Contractor is to install an approved geotextile fabric under all catch basin grates, and is to supplementary cover all existing catch basin grates with approved steel plates,** so that no soil and/or milled material enters into the structure, however at no time are the catch basins to be placed fully out of service. In the event milled material does enter into the structure then the Contractor shall immediately clean the unit to the satisfaction of the Engineer. Once the milling has been completed, and the roadway leveled, then the Contractor is to remove the plates from the catch basin structures.

(r) Once the cold-planing process has begun the Contractor is obliged to carry this effort forward without interruption, yet in accordance with all work hour restrictions unless otherwise directed by the Engineer

(s) **Paragraph (e) shall apply @ No cold-planing shall be performed on arterial roadways before 8:30 A.M. nor after 4:00 P.M.. Arterial roadways shall be designated by the Engineer.** The Contractor is further advised that the hours of operations are set by law. No machines or equipment are to be activated before **7:00 A.M. & no work is to extend beyond 4:30 P.M..** In addition no weekend or holiday work will be allowed unless special permission is granted.

(t) **Under this item the Contractor will be responsible for working closely and cooperatively with the City of Newton officials and it's agents as certain elements of these operations shall require a coordinated effort both in scheduling the work and carrying it forward to completion.**

(u) The two (2) inch cut to a pre-determined grade and/or profile, or any other specified lesser depth, shall be made in one pass. To that end the cold-planing machine shall be adjustable with regard to both crown and depth. The equipment shall be demonstrated to have been operated successfully on similar work completed prior to the award of this contract.

Method of Construction (Continued)

(v) Cold-planing operations shall not be limited to just the primary roadway surface, but shall also extend into the adjacent intersections as well. The limit of this work shall be determined 'in the field' by the Engineer so as to best meet the existing conditions and to further provide for a smooth pavement transitioning.

(w) The milled or planed surface shall conform generally to the grade and cross slope required to best meet the prevailing roadway grade conditions and such milled work shall be free from tears, gouges, breaks, or excessive grooves. The surface shall be free of imperfections that will prevent the milled or planed surface from being resurfaced with new pavement subsequent to this operation. Surface texture shall be as specified by the Engineer and shall provide acceptable rideability for traffic in the event that resurfacing is delayed.

(x) **The minimum width of pavement planed in each pass shall be approximately seventy-two (72) inches** except in areas to be trimmed and edged, inclusive of shoulder areas.

(y) The Contractor shall exercise caution while cold-planing in the vicinity of roadway structures and therefore shall not damage any roadway structure and/or casting during the course of these cold-planing operations. Any damage shall be repaired at the Contractors expense and to the satisfaction of the Engineer.

(z) **The milled material (including material removed by other means) shall be immediately removed from the site by means of discharging the milled material directly into trucks.** All residual milled material is to be initially power-broomed from the roadway, followed by a hand-brooming, so that no residual material remains on the roadway surface upon completion of the milling process. When working adjacent to traffic, the Contractor shall immediately remove material that is spilled on the traveled way. The contractor shall be responsible for all clean-up work along gutters, around castings and along the entire roadway.

(aa) Where proposed paving is to be started or ended at the project limits, a cut shall be made to a depth of one and one-half (1 1/2) inches. The end station cut shall be dressed to a clean vertical edge. All loosened material shall be promptly removed prior to returning traffic to the cold-planed surface.

(ab) **Immediately upon completion of the cold planing (i.e., 'detailing') operation performed around and about manholes, catch basins and exposed roadway structures** **THE CONTRACTOR SHALL APPLY A BRIGHT RIBBON OF ORANGE FLUORESCENT PAINT** on the projecting face of the manhole casting, such that oncoming traffic is made aware of the castings presence. In the event the cold-planing operation has caused any casting to project more than one and a half (1 1/2) inches above the milled surface of the roadway then the Contractor shall also minimally provide either a stabilized three foot (3) high traffic cone on the casting, in addition to the paint, until such time as other remedial measures can be taken, or a Manhole Protector Ring is retrieved, deployed and installed under Item 2.

(ab) Where 'tables' are created in preparation for the eventual installation of monolithic berm the Contractor shall perform handwork behind catch basins, around utility poles and/or around and about any other object, which encroaches within the 'table' range. This supplemental handwork shall be performed for the purpose of clearing all areas of existing berm/border material which is deemed to be inaccessible to the cold-planer machinery and is performed in order to complete the plane of the proposed 'table'. All residual material generated by this operation shall be disposed of by the Contractor at no additional cost to the City.

Method of Measurement

(ac) Under **Item 1D and Item 1W and Item 1N** measurement shall be by the **square yard** of roadway and shoulder* surface area actually cold-planed with **no deduction being made for roadway castings**. (*Note: Shoulder areas shall be measured when the cold-planing performed within these extended areas has been performed only upon the direction of the Engineer.)

Basis of Payment

* **The Contractor may elect NOT to bid the cost of fuels separately by inserting the term N/A (i.e. Not Applicable) in all (4) item sheet entry lines of Item 0. 303FC. This is a mandatory requirement to verify that the Contractor has formally waived his option to bid the cost of fuel(s) separately and has instead elected to factor his cold-planing & disposal fuel costs into the separate bid price of Item 1D and Item 1N and Item 1W.**

(ad) Under **Item 1D, Item 1N and Item 1W** the Contractor will be paid the contract unit price per **square yard** for cold-planing the bituminous concrete pavement and shoulder areas in the daytime or the nighttime or the weekend respectively, and for immediately loading the milled and/or hand cleared material onto trucks and disposing of the material(s) at an off-site location, for ‘detailing’ the project zone around and about manholes, curbs etc., and for cleaning the roadway, which unit price shall include full compensation for all labor materials, tools and equipment, and all incidentals necessary to complete the work under this Item, as directed by the Engineer, and as specified herein.

(ae) **The fuel costs associated with the cold-planing of roadways under Item 1 shall NOT include the cost of fuel, which is to be paid separately under Item 0. 303FC, UNLESS the Contractor has formally waived this option, and in doing so opts to include all fuel costs in the bid price of Item 1D and Item 1N, and has verified this choice by inserting the term N/A (i.e. Not Applicable) in all (4) item sheet entry lines for Item 0.303FC (This is a mandatory requirement)**

SECTION 2

ITEM 2 – RETRIEVE & DEPLOY A CITY OWNED (GATE-BOX OR MANHOLE) PROTECTOR RING

Description

(a) Under **Item 2** the Contractor shall retrieve and deploy City of Newton owned manhole protector rings and/or City of Newton owned gate-box protector rings. **These transition rings shall only be deployed at those locations, and only in such quantities, as the Engineer directs, and such work shall be performed immediately and on a continuous basis in harmonic unison with the progression of the cold-planing operation.** The primary purpose of these rings is to prevent tire damage and/or vehicular ‘slaloming’ by providing a ramping means for the purpose of transitioning vehicles over the manholes and water gate boxes which are primarily located in the wheel-path and/or at manhole concentration points such as intersections.

Materials

(b) **The Contractor shall work closely with the Engineer to determine which size protector ring, as well as the number of rings, that will best meet the needs of the project site(s), before the balance of the order is filled.**

(c) The Contractor is advised that each Manhole Protector Ring (a.k.a. manhole safety ramps) typically weigh approximately thirty (30) pounds each and are heavy-duty units that are equal to Part No. MSR10, MSR26 or MSR31, whichever is applicable, as supplied by American Highway Products Ltd.. (<http://www.ahp1.com/safetyramp1.php>)

Method of Administration

(d) The Contractor shall work closely with the Engineer to develop a mutually acceptable plan whereby the number of rings that are retrieved and deployed by the Contractor are most easily and most conveniently documented. However, the Engineer's decision as to the final means and methods concerning the manner in which this program is administered shall take precedence.

(e) When requested by the Engineer to do so the Contractor shall retrieve the designated number of manhole and/or gate-box protector rings from the centralized storage area located at the Elliot St. DPW Yard. **Any rings not pre-approved by the Engineer to be retrieved and deployed shall not be paid under this program but shall be returned to the centralized storage area, and neatly stacked, at no expense to the City.**

(f) At no time shall the Contractor's vehicle(s), used in the performance of these activities, leave the City of Newton while carrying the City owned manhole rings. **Any rings which are lost, due to the negligence of the Contractor to abide by this mandate or otherwise, shall be replaced by the Contractor at no additional expense to the City.**

(g) The Contractor shall be responsible for loading and unloading the rings onto and off of his service vehicle at the time of retrieval, and at the time of the field deployment, where the Contractor shall place each ring directly upon the manhole castings that lie within the designated project zone. However, any rings which have been deployed, but which are subsequently deemed not to best meet the needs and/or the intent of the field operations, shall be removed from the casting and reset somewhere else at no additional expense to the City..

Method of Measurement

(h) The Contractor shall be paid for **each** City owned manhole protector ring, or each City owned gate-box protector ring, retrieved and deployed in accordance with the directives of this Item. Only those protector rings pre-approved by the Engineer to be retrieved and subsequently deployed in the course of performing these activities shall be paid for under this **Item 2**.

Basis of Payment

(i) Under **Item 2** the Contractor will be paid the contract unit price for **each** City owned manhole protector ring, or each City owned gate-box protector ring, retrieved and deployed, and which has been pre-approved, authorized and ultimately verified by the Engineer. This unit price shall include full compensation for all labor materials, tools and equipment, and all incidentals necessary to complete the work under this Item, as directed by the Engineer, and as specified herein.

(j) New protector rings used to supplement the existing City of Newton protector ring stockpile(s) shall be paid for under **Item 3.10, 3.28 or 3.31**.

SECTION 3

ITEM - 3.10 - FURNISH & INSTALL A TEN INCH (INSIDE DIAMETER) GATE-BOX PROTECTOR RING

ITEM - 3.28 - FURNISH & INSTALL A TWENTY-EIGHT INCH (INSIDE DIAMETER) MANHOLE PROTECTOR RING

ITEM - 3.31 - FURNISH & INSTALL A THIRTY-ONE INCH (INSIDE DIAMETER) MANHOLE PROTECTOR RING

Description

(a) Under **Item 3.10** the Contractor shall furnish and install a new ten (10) inch inside diameter gate-box type protector ring or under **Item 3.28 & 3.31** furnish and install a new twenty-eight (28) inch inside diameter or thirty-one (31) inch inside diameter manhole protector ring respectively at those locations, and only in such quantities, as the Engineer shall direct. The primary purpose of these rings is to prevent tire damage and/or vehicular ‘slaloming’ by providing a temporary ramping means for the purpose of transitioning vehicles over the manholes and water gate boxes which are primarily located in the wheel-path at manhole concentration points such as intersections.

(b) The cold-planing contractor shall initially furnish and subsequently install the protector rings in those areas in which the work is being performed and such deployment shall be performed immediately and on a continuous basis in harmonic unison with the progression of the cold-planing operation..

Materials

(c) Only pre-approved protector rings which were delivered as **new** material at the beginning of the project term, are installed, and are subsequently accounted for at the end of the operation, shall be paid for under this Item.

(d) The Contractor shall work closely with the Engineer to determine which size protector ring will best meet the needs of the project site(s) before the balance of the order is filled. To that end the Contractor shall initially supply one ring of 10” inside diameter, 28” inside diameter, and 31” inside diameter, before the commencement of the contract, for the purpose of making a determination as to which ring size, or combination of ring sizes, will best meet the needs of the City of Newton under this program.

(e) The Protector Ring (a.k.a gate-box/manhole safety ramps) shall be equal to Part No. MSR10, MSR26 or MSR31, whichever is applicable, as supplied by American Highway Products Ltd;

<http://www.ahp1.com/safetyramp1.php>

Protector Rings shall be molded of flexible heavy-duty recycled rubber material and shall have the following characteristics:

- The rise from the bottom surface to the top shall be two (2”) inches
- The weight of the ring shall be 29 lbs. For 10” I.D. rings, 62 lbs. for 28” I.D. rings, and 55 pounds for 31” I.D. rings
- The outside diameter of the rings shall be 29” for 10” I.D. rings and 48” for 28” & 31” I.D. rings
- Density: 0.6 oz. / c.i. ASTM C642
- Fabrication: Compression Molded Deposit

Materials (Continued)

- Durometer Harness: 66A ASTM D2240
- Tensile Strength: 300 psi ASTM D412
- Elongation: 90% ASTM D412
- Brittleness: -40 Deg. Fahrenheit ASTM D746
- Coefficient of Thermal Expansion: ASTM C531

The Contractor is free to submit a catalog cut from competing ‘manhole protector ring’ suppliers for the purpose of gaining approval for their use, however the minimum characteristics listed here must be met or exceeded.

Method of Measurement

(f) **Each** protector ring pre-approved by the Engineer, furnished as **new** material and are initially deployed, and which are ultimately accounted for (in-place) at the end of each separate cold-planing operation, or otherwise delivered directly to the City’s designated stockpile location, shall be paid for under **Item 3.10, Item 3.28 or Item 3.31**, whichever is applicable.

(g) Protector rings which the Engineer has authorized to be purchased under **Item 3.10, Item 3.28 or Item 3.31**, and which have been either immediately deployed on-site or have otherwise been delivered to the City’s stockpile location and neatly stacked in their designated location, shall be subsequently deemed as ‘City Owned protector rings’. Therefore any deployment of **unused/‘new’** protector rings, **retrieved from the stockpile and deployed** by the Contractor shall be paid for under **Item 2**.

Basis of Payment

(h) Under **Item 3.10**, the Contractor will be paid the contract unit price per **each** new, pre-approved and authorized gate-box protector ring or under **Item 3.28 or Item 3.31** for each new twenty-eight (28) inch inside diameter or thirty-one (31) inch inside diameter manhole protector ring respectively, pre-approved and authorized manhole protector ring furnished by the Contractor as **new** material, initially deployed throughout the various work zones during the course of the cold-planing operation, and ultimately accounted for (in-place) at the end of the cold-planing operation, or otherwise have been stockpiled at the direction of the Engineer. The unit price shall include full compensation for all labor materials, tools and equipment, and all incidentals necessary to complete the work under this Item, as directed by the Engineer, and as specified herein.

SECTION 4

Item 4 – ALLOWANCE FOR PAYMENT OF POLICE OFFICERS (THESE MONIES ARE TO BE PAID DIRECTLY THRU AN INTER-DEPARTMENTAL BILLING PROGRAM)

Description

(a) The Contractor is advised that payment of Police officers shall be performed by the City through inter-departmental billing procedures, **however under Item 4 the Contractor shall be completely responsible for ordering, and for canceling details on a day to day basis.** In the event the Contractor has ordered police details, and does not give the police department ample advance notice that work has been cancelled for that day due to inclement weather or for any other reason, **then the Contractor shall bear the expense of that billed detail.** To that end the Contractor shall completely familiarize himself with the current policies regarding and/or regulating police details. In the event police detail requests cannot be completely filled to cover the Contractor's scheduled work for any particular day then the Contractor shall adjust his work schedule accordingly and shall not hold the City responsible for any loss of time, or for any other financial loss. However the City of Newton will grant an extension of time to the original contract term for each day lost due to insufficient police staffing.

(b) **When ordering, canceling and/or communicating with the Police Services personnel the Contractor shall identify;**

- **The Location of the Project**
- **The Contract Number** (to ensure proper billing procedures for accounting and routing purposes)
- **The work as a City funded contract** (to ensure surcharges are not applied)

In the event these criteria are not clearly stated the Contractor will be held responsible for any excess charges associated with this program.

(c) The administrative sum to be allowed for **Item 4** shall be **sixty thousand dollars (\$60,000.00).**

Basis of Payment

(d) Subject to the conditional citations set forth in **Paragraph (a) and (b);** Under **Item 4**, the invoiced amount(s) shall be paid directly to the City of Newton Police Department, and/or to the Massachusetts State Police, for services rendered by Police officers. **These payments shall be made through a direct inter-departmental billing and payment program administered by the Engineer, therefore a capital outlay by the Contractor will not be required.**

SECTION 5

Item 5 - 8" CEMENT CONCRETE HANDICAP RAMP / CURB CUTS

Description

All cement concrete ramp systems shall be constructed under this item. All cement concrete handicap ramps / curb cuts shall be designed, graded and constructed per the City of Newton General Construction Details, latest edition by the contractor.

The base for the cement concrete curb cuts shall consist of a six (6) inch gravel base course and a two (2) inch course of dense graded crushed stone topped with eight (8) inches of cement concrete and/or as required by the Engineer. Dimensions shall mean the finished compacted depth. The width of the ramps (typically six (6) feet in width) will be determined in the field by the Engineer to best meet the field and end-use conditions.

Materials

Cement concrete shall be of an air entrained type conforming to the current specifications of Section M4 of the Massachusetts Standard Specifications for Highways and Bridges supplement of June 19, 1985. Cement concrete shall have a 28 day compressive strength of 4000 PSI using 3/4 inch aggregate, and with an entrained air content of 7.0 + 1.0%.

ADD MIXTURES: Ordinary or emulsified carbon black - two (2) pounds per cubic yard, unless otherwise required by the Engineer.

Upon delivery of each and every concrete mix, the Engineer shall be furnished with a slip clearly stating the design mix and the quantities of the above mentioned add mixture, and any other add mixtures present in the mix. Any concrete mix, which when tested on the job site is found to contain quantities of entrained air less than six (6) or more than eight (8) per cent or which yields a slump of less than three (3) inches or greater than five (5) inches shall be rejected, the decision of the Engineer shall be final. The Engineer reserves the right to change the above mix in order to meet the required strength test.

(i) All concrete shall be transit mix and shall conform to the current specifications of A.S.T.M. C-94. Hand mix concrete or machine mixed on the job concrete shall be used only when permitted by the City Engineer in writing.

(i) Premolded asphalt expansion joints shall conform to the requirements of AASHTO Designation M33.

(ii) All gravel materials shall meet MassDOT Standard Specifications for Highways and Bridges, Latest Edition.

Method of Construction

(c) When new concrete is to be placed adjacent to existing walkways and/or driveways the Contractor shall cleanly cut a crisp joint cut by a means, and along a line, approved by the Engineer. No jackhammering of the existing walk and/or driveway shall be allowed.

(d) The ramps shall be excavated or filled to a subgrade twelve (12) inches below and parallel to the finished grade or as required by the Engineer.

(e) Upon the prepared subbase, the gravel and dense graded crushed stone base course shall be constructed and rolled with rollers weighing not less than three (3) tons and not more than five (5) tons until the surface presents a firm unyielding surface satisfactory to the Engineer.

(f) Any area that is inaccessible to mobile mechanical equipment or in restricted areas shall be compacted with pneumatic rammers or powered hand tampers. Compaction shall be carried on until the density of the material is not less than ninety-five (95) percent of the Standard Proctor Density, as determined by Standard laboratory Compaction Test.

(g) All concrete walks and/or driveway elements shall be constructed with the use of side forms. The forms shall be clean, smooth and free from warp. Forms for straight concrete walks shall be two by fours (2"X 4"s) staked at intervals no greater than four (4) feet, forms for curved sections of concrete walks shall be four (4) inch strapping staked as required by the Engineer, but in no case at intervals greater than four (4) feet. The forms shall be thoroughly braced and set to the proposed line and grade.

(h) All concrete slabs shall be constructed in one (1) course having a total finished depth of four (4) inches, all driveway elements shall be constructed in one (1) course having a total finished depth of six (6) inches and all ramps shall be constructed in one (1) course having a total finished depth of eight (8) inches. Top or wearing courses shall not be permitted.

(i) The end of every pour shall end at joints. Fresh concrete will not be allowed to be placed against previously laid concrete which has attained its initial set, excepting at full vertical joints.

(j) The walks and/or driveway aprons shall be blocked out in rectangular sections measuring not more than six (6) feet in any dimension. Transverse joints for a distance of twenty (20) feet, more or less, shall be dummy joints with an approved edging tool which shall score the joints a minimum of one (1) inch in depth. The concrete walks shall be placed in alternate slabs twenty (20) feet, more or less, in length. The slabs for walks shall be separated by transverse premolded asphalt expansion joints one-half (1/2) inch in thickness and a depth of not less than the full thickness of the walk set at right angles to the walk and to the side forms. No finishing operation shall be performed while free water is present. Finishing operations shall be delayed until all bleed water and water sheen has left the surface and the concrete has started to stiffen. After water sheen has disappeared, edging operations where required shall be completed. After edging and jointing operations, the surface shall be floated with either aluminum or magnesium floats. Immediately following floating, the surface shall be steel-trowelled. If necessary, tooled joints and edges shall be rerun before and after troweling to maintain uniformity. After troweling, the surface shall be brushed by drawing a soft-bristled push broom with a long handle over the surface of the concrete to produce a nonslip surface. In conveying the concrete from the place of mixing to the place of deposit, the operation shall be conducted in such a manner that no mortar will be lost, and the concrete shall be so handled that the concrete will be of uniform composition throughout, showing neither excess nor lack of mortar in any one place.

(k) Premolded asphalt expansion joints shall be placed adjacent to or around existing curb, walks, buildings and other structures designated by the Engineer.

(l) No concrete shall be placed on a frozen subbase nor shall concrete be poured when the air temperature is forty (40) degrees Fahrenheit and falling, unless permitted by the Engineer, in which case the adequate means for the protection of the concrete must be provided for. No salt or other unauthorized admixtures shall be used. When completed, the newly laid concrete shall be protected from all traffic and the weather for a period of three (3) days. The Concrete shall be cured by spraying with an approved curing compound of a recognized brand applied in accordance with the manufacturer's instructions.

(m) All water service boxes, and/or any other service box, and/or any handhole, which falls within the walk/drive area, are to be raised such that the top plane of the utility cover is set flush with the finished sidewalk surface, and such work shall be carried out to the satisfaction of the Engineer. This work shall be paid for as part of Item 3.

(n) In those cases where 'frozen' water service boxes are encountered the Contractor is to bring these special cases immediately to the attention of the Engineer, and upon his order to do so, the Contractor shall either remedy the situation by a means which is acceptable to the Engineer or shall otherwise retrieve corrective materials from the City of Newton Utility, and subsequently install them to the satisfaction of the Engineer and this work shall be incidental to the project..

Method of Measurement

(p) Cement concrete ramp systems shall be measured for payment by the SQUARE YARD, complete-in-place.

Basis of Payment

(q) Under Item 5 the Contractor will be paid the contract unit price per SQUARE YARD for the cement concrete curb cuts complete-in-place, which work shall include the gravel and dense graded crushed stone base, as well as the premolded asphalt expansion joints. The unit price shall include full compensation for all labor, materials, tools and equipment and all incidentals necessary to complete the work under these items as shown on the City of Newton Standard Details, as required by the Engineer and/or as specified herein, inclusive of the raising of all service boxes found in the sidewalk to the finished grade.

(r) Excavation (exclusive of rock excavation) shall be done and paid for as part of Item 5, whichever is applicable.

(s) Granite curbing, as required by the City of Newton Standard Details, shall be done and paid for as part of Item 7-9.

ITEM 6 -DETECTABLE TILE SURFACE FOR HANDICAP RAMP / CURB CUT LOCATIONS

Description

(a) The work under this item shall consist of furnishing and installing, by embedding in wet cement concrete, a factory manufactured Composite Detectable Tile Warning Surface that is ADA guideline compliant for the purpose of indicating the presence of a handicap ramp and/or curb cut location. These surfaces shall be accessed by the general public and the physically challenged alike, therefore the installation of these surfaces will require that the Contractor exercise exceptional care in the placement and the finishing process' associated with these tiles.

Materials

(b) The Surface shall be equal * to PART NO. 2460IDPAV2 :

* A federal yellow twenty four inch by sixty inch (24"x 60") Cast-In-Place Truncated Dome (Composite Tactile) Detectable Warning System as manufactured by;

ADA Solutions, Inc.
P.O. Box 3
North Billerica MA 01862
1-800-372-0519
www.adatile.com

*An approved equal shall mean a factory-fabricated system which either meets or exceeds the physical characteristics of the representative surface which is noted above. To that end the contractor must seek approval for an alternate surface by submitting, to the City of Newton, a catalog cut of the system which he proposes to use. This submittal, and/or actual samples of the material, shall clearly describe the physical characteristics of the proposed alternative unit such that the City of Newton can readily evaluate the proposed system.

"Equality" - An item equal to that named or described in the specifications of the contract may be furnished by the Vendor and the naming of any commercial name, trademark or other identification shall not be construed to exclude any item or manufacturer not mentioned by name or as limiting competition but shall establish a standard of equality only. An item shall be considered equal to the item so named or described if (1) it is at least equal in quality, durability, appearance, strength and design; (2) it will perform at least equally the function imposed by the general design for the work being contracted for or the material being purchased; and (3) it conforms substantially, even with deviations, to the detailed requirements for the item in the specifications. The name and identification of all materials other than the one specifically named shall be submitted to the City in writing for approval, at time of bid, use or fabrication of such items. Subject to the provisions of M.G.L., Ch. 30, Sec. 39J, approval shall be at the sole discretion of the City, shall be in writing to be effective, and the decision of the City shall be final. The City may require tests of all materials so submitted to establish quality standards at the Vendor's expense. All directions, specifications and recommendations by manufacturers for installation, handling, storing, adjustment and operation of their equipment shall be complied with; responsibility for proper performance shall continue to rest with the Vendor.

(c) The Detectable Warning Surface shall be of the "CAST IN PLACE REPLACEABLE TACTILE WARNING SURFACE TILES" type or approved equal.

Method of Construction

(e) Manufacturer's warranties are to be assigned and delivered to the City of Newton.

(f) The Contractor shall install each Detectable Tile to meet the exact gradient tolerances prescribed in the current ADA guidelines which are shown in the City of Newton General Construction Details. Typically this gradient, from top to bottom, shall not exceed 7.5 % (or two inches (2") over the twenty-four (24") inch depth of the Tile). Nor shall the gradient, from side to side, exceed 1.5% (or one inch (1") over the sixty inch (60") width of the tile).

- (g) In addition to complying with the latest ADA requirements the Contractor shall install each Detectable Tile in accordance with the directives shown on the plan.
- (h) Typically each Detectable Tile shall be installed so that the front (street side) edge is set back twelve (12") inches from the face of the curb (so that six (6") inches of cement concrete remain between the back of the curb and the edge of the tile).

Method of Measurement

- (i) Detectable Panel Systems shall be measured for payment by the each, complete-in-place.

Basis of Payment

- (j) Under Item 6 the Contractor will be paid the contract unit price per EACH for the Detectable Panels. The unit price shall include full compensation for all labor, materials, tools and equipment and all incidentals necessary to complete the work under these items as shown on the City of Newton Standard Details, as required by the Engineer and/or as specified herein.

**Item 7 – RESET EXISTING CURB (WITH CONCRETE MORTAR EMBEDMENT)
(INCLUDES CURB WORK REQ'D FOR HANDICAP RAMPS)**

Description

Any existing curb that does not meet the proposed line or grade, or other curb necessarily disturbed throughout the course of these operations, or existing curb used to construct handicap ramp systems, and/or any other existing modular curb designated by the Engineer, shall be reset to the existing line and grade and shall be subsequently embedded in cement mortar.

Under this item the Contractor shall be responsible for moving existing curb to a new location on the site in order to best meet either the aesthetic and/or the closure needs of the project. This work shall be carried out at the direction of the Engineer.

Method of Construction

The curb to be reset shall be excavated down to the underside of the existing curb or lower if necessary. The existing curb shall then be set to true line and grade. Gravel 'bridging' shall be used to support the curb to achieve the initial 'line & grade' with Cement Mortar being placed around the curb soon thereafter to form an unyielding base. However, no cement concrete shall be used in any curb trench which contains puddled water.

Cement Mortar shall conform to M4.02.15 of the MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 1988, AS AMENDED, THE SUPPLEMENTAL SPECIFICATIONS DATED FEBRUARY 25, 2010, latest edition.

If the Engineer so directs, the Contractor shall remove the existing curb from its existing location, prepare an adequate gravel base and reset the curb as described above.

Any area that is inaccessible to mobile mechanical equipment or in restricted areas shall be compacted with pneumatic rammers or powered hand tampers. Compaction shall be carried on until the density of the material is not less than ninety-five (95) percent of the Standard Proctor Density, as determined by Standard laboratory Compaction Test.

Transition and flush granite curb, either of the straight or curved type, which is installed to meet handicap ramp/curb cut compliances, shall be constructed according to the Architectural Barriers Board Specifications for such ramps as shown in the City of Newton General Construction Details. This work is to be performed to exact tolerances.

Method of Measurement

Measurements taken for payment shall be taken by the **linear foot** of the reset curb, **inclusive of cement mortar embedment** material for both straight and curved curb, handicap ramps, gutter mouths, and/or corner blocks, complete-in-place.

Basis of Payment

Cement Mortar embedment material shall be paid as part of this item.

Under **Item 7** the Contractor will be paid the contract unit price per **linear foot** of reset curb, complete-in-place, which unit price **shall include cement mortar embedment material, the excavation and disposal of all excess material**, and shall further include full compensation for all labor, materials, tools and equipment, and all incidentals necessary to complete the work under this item, as shown on the plans, as directed by the Engineer and as specified herein.

**Item 8 - FURNISH & INSTALL STRAIGHT GRANITE VA-4 CURB
(WITH CEMENT MORTAR EMBEDMENT)
(INCLUDES 'ISOLATED' INSTALLATIONS & HANDICAP RAMP WORK)**

**Item 9 - FURNISH & INSTALL CURVED VA-4 GRANITE CURB
(WITH CEMENT MORTAR EMBEDMENT)
(INCLUDES HANDICAP RAMP WORK)**

Description

(a) Straight Type VA4 granite curb and curved Type VA4 granite curb shall be furnished, installed, embedded in cement, and mortared in place as directed by the Engineer and as specified herein. This work shall also include curb which is set along the sideline of the street.

(b) All earth and existing materials excavation, inclusive of all existing undesirable curb or fill, and all backfill material necessary to set the curb as specified, shall be done under these items.

Materials

(c) The curbstone shall be sawn top, split face.

(d) Materials shall conform to the current specifications as set forth in the Commonwealth of Massachusetts Department of Public Works Standard Specifications for Highways and Bridges, dated 1988, Section M9.04.1 and as shown in the City of Newton General Construction Details.

(dd) Cement Mortar shall conform to M4.02.15 of the MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 1988, AS AMENDED, THE SUPPLEMENTAL SPECIFICATIONS DATED FEBRUARY 25, 2010, latest edition.

Method of Construction

(e) Construction methods shall conform to the current specifications as set forth in the MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 1988, AS AMENDED, THE SUPPLEMENTAL SPECIFICATIONS DATED FEBRUARY 25, 2010,, latest edition, Section 501.

(f) New transition and flush granite curb, either of the straight or curved type, which is installed to meet handicap ramp/curb cut compliance shall be constructed according to the Architectural Barriers Board Specifications for such ramps as shown in the City of Newton General Construction Details. This work is to be performed to exact tolerances.

(g) The curb trench shall be excavated down to the underside of the existing curb or lower if necessary. The existing curb shall then be set to true line and grade. Gravel 'bridging' shall be used to support the curb to achieve the initial 'line & grade' with cement mortar being placed in and about the curb soon thereafter to form an unyielding base. However, no CDF shall be used in any curb trench which contains puddled water.

(h) Any area that is inaccessible to mobile mechanical equipment or in restricted areas shall be compacted with pneumatic rammers or powered hand tampers. Compaction shall be carried on until the density of the material is not less than ninety-five (95) percent of the Standard Proctor Density, as determined by Standard laboratory Compaction Test.

Method of Measurement

(i) Measurements taken for payment will be by the **linear foot** of cement mortar embedded curb actually installed in accordance with the plans and as directed by the Engineer, as measured along the front arris line of the curb. Curved curb shall include all new curb (except corner blocks) set to curves of one hundred (100) feet radius or less.

Basis of Payment

(j) **Cement Mortar material shall be paid as part of this item.**

(k) Under **Item 8 or Item 9** the Contractor will be paid the contract unit prices respectively per **linear foot** for furnishing and placing cement mortar embedded straight granite curb, including transitioned straight and/or flush/lip granite curb for handicap ramp systems, complete-in-place, and for furnishing and placing cement mortar embedded curved granite curb, including transitioned and/or flush/lip curved granite curb for handicap ramp systems, complete-in-place, **the excavation and disposal of all excess material(s)** , and for all labor, materials, tools and equipment and all incidentals necessary to complete the work under these items as shown on the plans, as directed by the Engineer and as specified herein.

ITEM 10 - 4" BITUMINOUS CONCRETE FOR 'PERMANENT' TRENCH RESURFACING

Description

When directed by the Engineer, trenches and areas disturbed by the Contractor shall be resurfaced with bituminous concrete Type I-1.

The Contractor shall continually review and maintain all trenches in order to provide safe and unobstructed passage, at all times, for both vehicular and pedestrian traffic. In addition, all trenches and areas that are permanently resurfaced by the Contractor shall be guaranteed against settlement, upheaval or failure of any kind for a period of one (1) year after the City accepts the work, and he shall replace such resurfacings at his own expense. The City Engineer shall be sole judge as to what constitutes a failure, and which portion of the resurfacing is to be replaced, and his decision shall be final.

After the sidewalk and/or curb work has been completed and tentatively accepted by the City of Newton, permanent trench resurfacing, under Item 10, shall be installed in two courses. However, prior to the installation of the four (4) inch permanent patch the Contractor must be certain that all areas are fully compacted to ninety-five (95) percent density from the bottom of the trench to the top. Further, permanent trench resurfacing operations, once begun, are to be carried out without interruption, and in a systematic and responsible manner.

To that end the Contractor is to coordinate his activities such that the trench area, at the end of the workday, has been excavated, appropriately filled and compacted with designated base materials, hindered and topped, **all in one day** in order to provide a seamless operation and to eliminate any surface unevenness between the existing roadway pavement surface and the new trench patch.

Further, all permanent trench patch resurfacing must be installed throughout each independent site and/or project zone before the Contractor will be allowed to start new construction activities elsewhere.

Materials

Bituminous concrete shall be Type I-1, mixed and transported as specified in the MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 1988, AS AMENDED, THE SUPPLEMENTAL SPECIFICATIONS DATED FEBRUARY 25, 2010, Sections 460 and M3.

All gravel and dense graded materials shall conform to the relevant provisions of the MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES DATED 1988, AS AMENDED, THE SUPPLEMENTAL SPECIFICATIONS DATED FEBRUARY 25, 2010, Sections 402, 405 and M2.

Method of Construction

Under Item 10 4" bituminous concrete for permanent trench resurfacing shall be laid on a gravel base. In the event the existing material is deemed to be unsuitable by the Engineer then the base shall be built and compacted of gravel or dense graded crushed stone as part of this item as the Engineer may deem to be appropriate. The depth of the four (4") depth permanent bituminous concrete pavement shall be laid.

Compaction of the roadway gravel base course shall be by a vibratory hand plate or an equivalent method as approved by the Engineer.

Permanent bituminous concrete shall only be applied in bright sunlight or partly cloudy weather without the threat of rain. The Contractor is not to schedule and/or apply any bituminous concrete, whose end use is for permanent installation(s), unless such favorable weather conditions are professionally forecast by a recognized weather agency and at the request of the Engineer, this forecast shall be filed with Engineer in hard-copy form. Further, no bituminous concrete shall be applied upon a residually wet surface, and no bituminous concrete which has been prematurely cooled by rain, either on the roadway or on the truck, will be accepted.

The temperature of the mixture to be laid shall be between two hundred and twenty-five

(225) degrees Fahrenheit and three hundred and twenty-five (325) degrees Fahrenheit and no mixture shall be placed when the air temperature in the shade and away from artificial heat is forty (40) degrees Fahrenheit or less. Variation from these temperatures may be permitted only on written permission of the Engineer.

The edge of the asphalt mixture adjacent to rigid curb lines, around manholes, or other solid fixtures or where no shoulder is constructed, shall be hand tamped before being rolled.

The bituminous concrete shall be laid in the prescribed number of courses as shown on the plans or as determined by the Engineer. All depths of courses shall mean the finished depths after rolling. All courses must be laid so that they will have the required thickness and be parallel to the proposed finished grade of the surface.

On trenches wider than four (4) feet and after the paving mixture has been properly spread it shall be thoroughly and uniformly compressed by rolling with power rollers. On projects involving less than one hundred and fifty (150) tons of paving mixture per day one (1) tandem roller of not less than ten (10) tons shall be used. On projects using more than one hundred and fifty (150) tons but less than three hundred and fifty (350) tons two (2) rollers shall be required with one (1) additional roller for each two hundred (200) tons of mixture per day thereafter. A day shall be construed as eight (8) hours working time. If, in the opinion of the Engineer, satisfactory compaction is not obtained by rolling with a tandem roller, the Engineer may order the rolling to be done with ten (10) to twelve (12) ton three (3) wheeled roller with wheels not less than twenty-four (24) inches wide. All rollers used shall weigh at least two hundred and fifty (250) pounds per inch width of tread. Each roller shall be in charge of a competent, experienced roller operator and shall be kept in a nearly continuous operation as practical while the work is under way. Rolling shall be continued and so executed that all roller marks, ridges, porous spots and impressions are eliminated, and the resulting surface has the required grade and contour. Rolling shall proceed at a rate not to exceed two hundred and fifty (250) square yards per hour, per roller. To prevent adhesion of the mixture to the roller the wheels shall be kept properly moistened but excess water or oil will not be permitted. Along forms, curb headers at similar structures and all places not accessible with a roller, the mixture shall be thoroughly compacted by tampers. Such tampers shall weigh not less than twenty-five (25) pounds and shall have a tamping face of not more than fifty (50) square inches. The surface of the mixture after compressing shall be smooth and true to the established crown and grade. Any mixture which becomes loose and broken, mixed with dirt or in any way defective shall be removed and replaced with fresh mixture, which shall be immediately compacted to conform to the surrounding area. Areas of one (1) square foot or more showing an excess of bitumen shall be removed and replaced.

Basis of Measurement and Payment

Under Item 10 the Contractor will be paid the contract unit price square yard of bituminous concrete Type I-1 for permanent trench resurfacing, complete in place, which unit price shall include full compensation for all excavation of undesirable material, and the disposal thereof, in addition to all labor and materials, gravel or dense graded materials as necessary and for all tools and equipment and all incidentals necessary to complete the work under this item in accordance with the plans, as directed by the Engineer and as specified herein. (The Contractor is reminded that the four (4) inch yield is to be applied in two separate two (2) inch courses).

SECTION 6**ITEM 11 – ADJUSTMENT OF EXISTING STRUCTURES
(LESS THAN OR EQUAL TO 12” INCH)****ITEM 12 – ADJUSTMENT OF EXISTING STRUCTURES
(GREATER THAN 12” INCH)****Description**

The work shall consist of adjusting the masonry and castings of present structures, as directed by the Engineer, to conform to newly proposed line and grade changes; all in accordance with these specifications and in close conformity with the lines and grades as established by the Engineer.

Materials

All materials shall meet the requirements specified in the appropriate sections of the “General Construction Details” as issued by the City of Newton Engineering Department, latest edition.

Construction Methods

The contractor shall bring the structure to the final line and grade. The masonry shall be removed to such a depth as directed by the Engineer and new masonry shall be constructed to conform to the final grades and in conformity with the requirements of these specifications. The new masonry construction, high early strength concrete collars, backfilling around structures and other incidental work shall be considered incidental to this item.

Gates and service boxes that are adjusted to line or grade or line and grade, which are located in roadway pavement areas shall have a concrete collar constructed around them.

Protection of Work

The Contractor will be held responsible for the protection of the castings. Any frames, grates, or covers damaged in any manner during the progress of the construction shall be replaced with new castings by the Contractor, at his/her expense. Prior to the actual removal of the present castings a count will be made and recorded of all castings, which are in satisfactory condition for reuse. The contractor shall supply the number of castings recorded in the initial count, when they are required for reuse or when they are to be removed from the project by the Owner.

Method of Measurement

Adjustment of structures (Item 11) to line or grade or both line and grade, when the structure measured at its widest point is less than or equal to 12 Inches, will be measured in place by the unit each, complete and approved.

Adjustment of structures (Item 12) to line or grade or both line and grade, when the structure measured at its widest point is greater than 12 Inches will be measured in place by the unit each, complete and approved.

Method of Payment

The unit price for Item 11 shall include full compensation for all labor, materials, tools and equipment and all incidentals necessary to complete the work under these items as shown on the City of Newton Standard Details, as required by the Engineer and/or as specified.

The unit price for Item 12 shall include full compensation for all labor, materials, tools and equipment and all incidentals necessary to complete the work under these items as shown on the City of Newton Standard Details, as required by the Engineer and/or as specified.

Item 13 – MATERIALS WORK ALLOWANCE(ENGINEER’S DISCRETIONARY FUND)

Description

(a) The Contractor shall include in his bid an allowance of **five hundred dollars (\$500.00)** for cylinders and for other tests conducted in the field and/or the laboratory as required by the Engineer for the control of the concrete, reclaimed pavement material, bituminous concrete pavement, or for any other material.

(b) The City will reimburse the Contractor the full amount of the material testing services provided when approved by the Engineer. The Contractor is required to submit to the City Engineer copies of evidence of payment.

Basis of Payment

(c) Under **Item 13** the Contractor will be paid the full invoice amount for approved and/or authorized material testing services conducted by an independent and qualified laboratory. **Under no circumstances will the City of Newton pay for any testing procedures which unreasonably exceed accepted industry standards (based upon three (3) additional independent quotes for similar testing procedures).**

END SECTION